

Friday, June 18th, 2010

TO ALL BIDDERS:

Dear Sir/Madam:

**Re: ADDENDUM #1
Traffic Signal Installations – Various Locations
Contract No.: 10-41, File No. 570.02-483**

This Addendum shall form part of the contract documents. The tenderer shall insert this addendum in the front cover of the contract and make the required amendments as noted herein.

1. Form of Tender

Within section C-1, Form of Tender for Contract, remove Page T1-1 and replace with the T1-15 (attached; 1 page).

Item 3-07 – Depth of Cover changed from 750mm to 1000mm.

Yours truly,

Jeff Thompson
Project Leader, Design and Construction

City of Burlington
CONTRACT #: 10-41
Traffic Signal Installations

Ad No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
3-05		Supply and install "Scepter" rigid P.V.C. conduit with 90 degree bends at traffic hand holes. Conduits to have a minimum of 750mm cover. Fish line to be included in duct. Includes restoration. UG-1 SS04				
3-05-A		75mm I.D. conduit.	m	55.00	_____	_____
3-06		Supply and install "Scepter" rigid P.V.C. conduit with 90 degree bends at traffic hand holes. Conduits to have a minimum of 600mm of cover. Fish line to be included in duct. Includes restoration. UG-1 SS04				
3-06-A		50mm I.D. conduit	m	65.00	_____	_____
1	3-07	Supply and install "Scepter" rigid P.V.C. conduit by DIRECTIONAL BORING with 90 degree bends at traffic hand holes. Conduits to have a minimum of 1000mm of cover. Fish line to be included in duct. UG-1 SS04				
	3-07-A	100mm I.D. conduit.	m	120.00	_____	_____
	3-07-B	50mm I.D. conduit.	m	35.00	_____	_____
	3-08	Construct and supply material for 1.6m x 1.6m x 150mm concrete traffic controller base. SS04 S-304 UG-2	each	1.00	_____	_____
	3-09	Construct and supply material for concrete pole base. Includes supply and place anchor assembly. UTS 616.010, 616.011, 616.20, UG-3. SS04				