CITY OF Burlington

(905) 335-7600 ext. 7818
(905) 335-7821
meyerd@burlington.ca

April 29, 2010

TO ALL CONTRACTORS

Re: ADDENDUM NO. 1
Orchard Community Park FIFA 1-star Artificail Turf Field, Contract 10-42

This Addendum shall form part of the contract documents. The tenderer shall insert this Addendum in the front cover of the contract and make the required amendments as noted.

1. Under Schedule of Unit Prices, PART 2.0 ARTIFICIAL TURF ATHLETIC FIELD, item #1, the Supply and Installation of the synthetic turf and in-fill will be by Sportica (w/ REAL 60 MS Tiger Turf). The contact information is as follows:
   i. **Josée Latulippe**
      Présidente / President
      T : (450) 741-1142 ext 222
      F : (450) 741-3332
   ii. E : jlatulippe@solsportica.com

2. Remove and replace Page 1 and 2 of the Schedule of Unit prices. Changes are noted below
   a. Under Schedule of Unit Prices, PART 2.0 ARTIFICIAL TURF ATHLETIC FIELD, item #2.1, reduce the cash allowance from $315,000 to $300,000.
   b. Under Schedule of Unit Prices, PART 2.0 ARTIFICIAL TURF ATHLETIC FIELD, item #2.4, the amount of Granular "O" depth to be 200mm not 300mm. Replace the quantity of Granular 'O' from '2,292m3' to '1,530m3'.
   c. Under Schedule of Unit Prices, PART 1.0 SITE PREPARATION, item #1.10, increase the quantity of Granular B from '1,850m3' to '2,615m3'.

FOR Dave Meyer, C.E.T.
Project Leader- Design & Construction

SCHEDULE OF UNIT PRICES

Item	Spec No.	Description	Unit	Quantity	Unit Price	Total
PART 1.0		**SITE PREPARATION:**				
1.1		Mobilization	LS	1.0	$	$
1.2		Supply, install,maintain, and remove Modu-Loc construction fencing	l.m.	532.0	$	$
1.3		Supply, install and maintain silt control fence as per OPSD 219.110	l.m.	64.0	$	$
1.4		Remove and dispose of concrete pads and granular base	m^2	15.0	$	$
1.5		Remove and dispose of asphalt paving and granular base	m^2	20.0	$	$
1.6		Remove, modify, and reinstall existing players benches	ea.	2.0	$	$
1.7		Remove and relocate existing electrical control	LS	1.0	$	$
1.8		Supply and install catchbasin as per OPSD 701.010 and OPSD 400.010, include connection to existing storm sewer	ea.	1.0	$	$
1.9		Strip, remove, and dispose of sub-excavated topsoil material	m^3	1,530.0	$	$
1.10	A#1	Supply and install granular 'B' fill to pre-grade	m^3	2,615.0	$	$
1.11		Supply and install quick couplers and water connections	LS	1.0	$	$
1.12		Rough grading (swales)	m^2	2,450.0	$	$
		TOTAL THIS SECTION:				**$**

SCHEDULE OF UNIT PRICES

Item	Spec No.	Description	Unit	Quantity	Unit Price	Total
PART 2.0		**ARTIFICIAL TURF ATHLETIC FIELD:**				
2.1	A#1	Supply and install sythetic turf and infill - Turf selection to be determined			Allowance	$ **300,000.00**
2.2		Coordinate turf installation subcontractor	LS	1.0		$
2.3		Supply and install field sub-drainage system	LS	1.0	$	$
2.4	A#1	Supply and install granular 'O' sub-base	m^3	1,530.0	$	$
2.5		Supply and install Free Draining Finishing Layer	m^3	382.0	$	$
2.6		Supply and install concrete turf anchor curbing COB AMEND	l.m.	366.0	$	$
2.7		Supply and install concrete barrier curbing COB AMEND	l.m.	82.0	$	$
2.8		Supply and install concrete paving COB AMEND	m^2	240.0	$	$
2.9		Supply and install heavy duty asphalt paving COB AMEND	m^2	38.0	$	$
2.10		Supply and install 1500mm ht. black vinyl chain link fence	l.m.	266.0	$	$
2.11		Supply and install 3000mm ht. black vinyl chain link fence	l.m.	12.0	$	$
2.12		Supply and install 6000mm ht. black vinyl chain link fence	l.m.	84.0	$	$
2.13		Supply and install 8'x24' Kwik Goal World Competition Goal complete	ea.	2.0	$	$
2.14		Supply and install sod including fine grading	m^2	2,450.0	$	$
		TOTAL THIS SECTION:				**$**