


# GRINDSTONE CREEK EROSION CONTROL MITIGATION



## UNSWORTH AVE TO SUMACH DR

ISSUED FOR REVIEW- 2022/05/11  
 CONTRACT NUMBER - XXXXXXXXX


KEY MAP



### DRAWING INDEX

SEDIMENT AND EROSION CONTROL AND STAGING PLAN AOC 1, 2 & 3	C101
SEDIMENT AND EROSION CONTROL AND STAGING PLAN AOC 4	C102
PROPOSED PLAN - AREA OF CONCERN 1 - STA: 0+320 TO 0+440	C201
PROPOSED PLAN - AREA OF CONCERN 2 - STA: 0+190 TO 0+310	C202
PROPOSED PLAN - AREA OF CONCERN 3 - STA: 0+125 TO 0+160	C203
PROPOSED PLAN - AREA OF CONCERN 14- STA: 0+020 TO 0+080	C204
RESTORATION PLAN - AOC 1, 2 AND 3 - STA: 0+125 TO 0+440	C301
HABITAT STRUCTURE PLAN AND DETAILS	C401






TRUNK DIAMETER (DBH) *2	MINIMUM TREE PROTECTION ZONE (MTPZ) DISTANCES REQUIRED *3	CRITICAL ROOT ZONE (CRZ) DISTANCES REQUIRED *3&4
<10 cm	1.8 m	1.8 m
11-40 cm	2.4 m	4.0 m
41-50 cm	3.0 m	5.0 m
51-60 cm	3.6 m	6.0 m
61-70 cm	4.2 m	7.0 m
71-80 cm	4.8 m	8.0 m
81-90 cm	5.4 m	9.0 m
91-100+ cm	6.0 m	10.0 m

- NOTES:
- THE ROOTS OF A TREE CAN EXTEND FROM THE TRUNK TO APPROXIMATE 2-3 TIMES THE DISTANCE OF THE DRIP LINE.
  - DIAMETER AT BREAST HEIGHT (DBH) IS THE MEASUREMENT OF TREE TRUNK TAKEN AT 1.4 METRES ABOVE GROUND.
  - MINIMUM TREE PROTECTION ZONE AND CRITICAL ROOT ZONE DISTANCES ARE TO BE MEASURED FROM THE OUTSIDE EDGES OF THE TREE BASE TOWARDS THE DRIP LINE AND MAY BE LIMITED BY AN EXISTING PAVED SURFACE, PROVIDED THE EXISTING PAVED SURFACE REMAINS INTACT THROUGHOUT THE CONSTRUCTION WORK AND IS SUBJECT TO SECTION 6 OF THIS SPECIFICATION.
  - WHERE WORK IS BEING PERFORMED BEYOND THE MINIMUM TREE PROTECTION ZONE BUT WITHIN THE CRITICAL ROOT ZONE THE WORKS ARE SUBJECT TO SECTION 8 OF THIS SPECIFICATION.



DETAIL TREE PROTECTION DETAIL (BURLINGTON) 1

Tree ID #	Common Name	Size (cm)	Location
3	SUGAR MAPLE	27.5	AOC 4
143	BLACK WALNUT	19	AOC 1
150	BLACK WALNUT	65	AOC 1
152	DEAD	100	AOC 1
166	EUROPEAN BUCKTHORN	14	AOC 1
167	DEAD	10	AOC 1
168	BLACK WALNUT	38	AOC 1
169	AMERICAN BASSWOOD	13.5	AOC 1
171	BLACK WALNUT	20	AOC 1
172	GREEN ASH	14	AOC 1
173	BLACK WALNUT	41	AOC 1
175	BLACK WALNUT	23	AOC 1
182	MANITOBA MAPLE	27.3	AOC 3
183	BLACK WALNUT	33	AOC 3
198	BLACK ALDER	23	AOC 3
199	BLACK ALDER	25.5	AOC 3
200	MANITOBA MAPLE	17.5	AOC 3
234	MANITOBA MAPLE	15	AOC 2
228	BLACK WALNUT	54	AOC 1


- CONSTRUCTION PHASING:
- ESTABLISH ACCESS TO SITE AND STAGING AREAS AS NOTED ON THE CONSTRUCTION DRAWINGS.
  - INSTALL SILT, CONSTRUCTION AND TREE PROTECTION FENCING AS WELL AS SITE SIGNAGE AS REQUIRED TO THE SATISFACTION OF THE ENGINEER AND THE CITY OF BURLINGTON PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY.
  - ALL IN-STREAM CONSTRUCTION TO BE COMPLETED DURING LOW FLOW CONDITIONS.
  - CONSTRUCTION WORKS ARE TO COMMENCE AT THE UPSTREAM END OF THE SITE.




DETAIL HEAVY DUTY SILT FENCE OPSD 219.130 (2015) 3



DETAIL SILT SOCKS SCALE: N.T.S. 4



DETAIL METER BAG COFFER DAM SCALE: N.T.S. 5



DETAIL TYPICAL DEWATERING AND BYPASS DETAIL 2

EROSION, SEDIMENT CONTROL AND DEWATERING NOTES:

- BE ADVISED THAT CONSERVATION HALTON MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVED PERMIT DOES NOT EXEMPT THE PROPERTY OWNER/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAW, OR ANY RIGHTS UNDER COMMON LAW.
  - FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT, PREFERABLY AN ENVIRONMENTAL MONITOR, WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, CONSERVATION HALTON, AND ANY OTHER APPROPRIATE PARTIES.
  - THE EROSION AND SEDIMENT CONTROL (ESC) PLAN IS A DYNAMIC DOCUMENT, WHICH MAY BE SUBJECT TO CHANGE OR MODIFICATIONS AS A RESULT OF SITE DEVELOPMENTS OR CHANGES ON SITE. ANY DEVIATION FROM APPROVED PLANS BE DESIGNED BY A QUALIFIED PROFESSIONAL.
  - IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR CONSERVATION HALTON RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.
  - ALL ACTIVITIES, INCLUDING MAINTENANCE PROCEDURES, SHALL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBBLE, CONCRETE OR OTHER DELETERIOUS SUBSTANCES INTO THE WATER. VEHICULAR REFUELLING AND MAINTENANCE WILL BE CONDUCTED A MINIMUM OF 30m FROM THE WATER.
  - THE CONTRACTOR SHALL MONITOR THE FIVE-DAY WEATHER FORECAST ON A DAILY BASIS TO ANTICIPATE WEATHER CONDITIONS AND SHALL BE PREPARED TO LEAVE THE SITE IN A STABLE AND SECURE CONDITION SHOULD WATER LEVELS RISE. PRIOR TO AN ANTICIPATED LARGE WEATHER EVENT, THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROLS AND ENSURE THE SITE AND EROSION AND SEDIMENT CONTROL MEASURES ARE SECURE TO MITIGATE AGAINST WEATHER CONDITIONS. ALL WORKS SHALL BE PERFORMED DURING FAVORABLE WEATHER CONDITIONS.
  - ALL DEWATERING SHALL BE DISCHARGED AT LEAST 15M FROM THE CREEK INTO A SEDIMENT TRAP. NO DEWATERING SHALL BE SENT DIRECTLY TO ANY WATERCOURSE OR SEWER. THESE CONTROL MEASURES SHALL BE MONITORED FOR EFFECTIVENESS AND MAINTAINED OR REVISED TO MEET THE OBJECTIVE OF PREVENTING SEDIMENT FROM ENTERING THE WATERCOURSE.
  - THE INLET PUMP HEAD MUST BE COVERED WITH FILTER FABRIC OR CLEAR STONE AND HAVE AN APPROVED FISH SCREEN; THE OUTLET PUMP MUST DISCHARGE TO SEDIMENT BAG OR BASIN. DISCHARGE FROM THE BAG IS TO BE RELEASED TO A VEGETATED LOCATION OR IF VEGETATED LOCATION IS NOT AVAILABLE, A FLOW DISSIPATING STRUCTURE SHOULD BE PROVIDED. THE SEDIMENT BAG MUST BE LOCATED AT LEAST 15M AWAY FROM THE RECEIVING WATER BODY. THE MESH SIZE OF THE FISH SCREEN PLACED ON THE INTAKE PIPE WILL BE NO LARGER THAN 2.54 MM AS PER DFO INTERIM CODE OF PRACTICE.
- CONSTRUCTION WORK RESTRICTIONS:
- CONSTRUCTION WITHIN THE CREEK IS NOT PERMITTED DURING/FOLLOWING A RAINFALL EVENT. DURING THIS TIME, THE CONTRACTOR IS TO STABILIZE THE SITE AND ALLOW FLOWS THROUGH THE WORK AREA. THIS APPROACH IS TO BE UTILIZED WHEN FLOW RATES IN THE CREEK EXCEED BASEFLOW/LOW FLOW CONDITIONS.
  - DURING THE DEWATERING, IF THE SIZE OF SEDIMENT PARTICLE IS LESS THAN OPENING OF THE FILTER BAG, THEN A SEDIMENT TANK SHOULD BE USED FOR SILTATION PURPOSES.
  - DURING CLOSURE OF THE PERMANENT WATERCOURSE CHANNEL, OR THE TEMPORARY WATER PASSAGE SYSTEM, ANY STRANDED FISH SHALL BE RELEASED OUTSIDE OF THE DISTURBED AREAS BY A QUALIFIED BIOLOGIST. THIS WORK WILL BE CONDUCTED UNDER LICENCE FROM THE MINISTRY OF NATURAL RESOURCES AND FORESTRY. THE CONTRACTOR IS RESPONSIBLE FOR SUPPLYING ALL MATERIALS, OBTAINING ASSOCIATED PERMITS, AND ANY ADDITIONAL COSTS INCURRED BY COMPLETING A FISH RESCUE BY A QUALIFIED BIOLOGIST.
  - ALL DISTURBED AREAS ARE TO BE STABILIZED DAILY OR PROTECTED WITH EROSION AND SEDIMENT CONTROL.
  - SILT CONTROL FENCE SHALL BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL REMAIN IN PLACE DURING AND AFTER CONSTRUCTION UNTIL THE VEGETATION HAS BEEN ESTABLISHED AND THE SITE HAS BEEN STABILIZED.
  - ALL STOCKPILE AREAS ARE TO BE ENCLOSED WITH HEAVY DUTY SILT CONTROL FENCING. ALL TEMPORARY SOIL OR DIRT STOCKPILES ARE TO BE PROVIDED WITH THE NECESSARY SEDIMENT AND EROSION CONTROL FEATURES, INCLUDING SEEDING IF ANTICIPATED TO BE STORED MORE THAN ONE MONTH. STOCKPILES MUST NOT BE LOCATED IN AREAS OF CONCENTRATED FLOW AND MINIMUM OF 15m FROM THE TOP OF BANK OR WATERCOURSE. NO FILL WILL BE PERMANENTLY LEFT ON SITE. ALL LEFTOVER FILL WILL BE TRUCKED OFF SITE AND FINAL FILL DESTINATION WILL BE PROVIDED TO CONSERVATION AUTHORITY.
  - ADDITIONAL EROSION AND SEDIMENT CONTROL MATERIALS (SILT FENCE, STRAW BALES, CLEAR STONE) ARE TO BE KEPT ON SITE FOR EMERGENCIES AND REPAIRS.
  - EROSION AND SEDIMENT CONTROLS METHODS ARE TO BE CONTINUOUSLY EVALUATED AND UPGRADES ARE TO BE IMPLEMENTED, WHEN NECESSARY OR AS DIRECTED BY THE ENGINEER.
  - THE CONTRACTOR IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION. ANY SEDIMENT LADEN WATER WILL NOT BE ALLOWED TO DISCHARGE TO THE CREEK.
  - SHOULD THERE BE CONTINUOUS PUMPING PROPOSED AFTER HOURS TECHNICAL IS TO BE ASSIGNED TO ENSURE THAT THE APPROPRIATE TREATMENT SYSTEM (PUMPING EQUIPMENT, SETTLEMENT PONDS, SEDIMENTATION TANK, ETC.) IS FUNCTIONING PROPERLY.
  - AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ON-SITE FOR EMERGENCIES.
  - ANY SEDIMENT SPILL FROM THE SITE MUST BE REPORTED TO MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE (CALL SPILL ACTION CENTER AT 1-800-268-6060)
  - EROSION AND SEDIMENT CONTROL METHODS ARE TO BE INSPECTED, MAINTAINED AND CONTINUOUSLY EVALUATED WEEKLY, AFTER ANY RAIN EVENT, ANY SNOW MELT EVENT. IF A SITE IS LEFT ALONE FOR 30 DAYS OR LONGER, A MONTHLY INSPECTION IS REQUIRED. UPGRADES ARE TO BE IMPLEMENTED WHEN NECESSARY OR AS DIRECTED BY ENGINEER.
  - ALL MAINTENANCE AND REPAIRS AS DIRECTED BY ENGINEER OR NOTICED DURING INSPECTION OF EROSION AND SEDIMENT CONTROLS SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF INSPECTION.
  - SEDIMENT SHOULD BE REMOVED FROM THE SEDIMENT CONTROL FENCING ONCE SEDIMENT HAS ACCUMULATED TO A LEVEL OF ONE THIRD THE HEIGHT OF THE FENCING OR TO A HEIGHT OF 30cm. ALL ACCUMULATED SEDIMENT IS REQUIRED TO BE REMOVED PRIOR TO THE REMOVAL OF THE CONTROL MEASURES.
- GENERAL NOTES:
- ALL AQUATIC WORK IS TO BE COMPLETED BETWEEN JULY 1ST AND SEPTEMBER 14TH.
  - ALL UNSUITABLE AND/OR EXCESS MATERIAL IS TO BE DISPOSED OF AT AN OFF-SITE LOCATION TO BE ARRANGED FOR BY THE CONTRACTOR.
  - ALL MEASUREMENTS FOR THIS PROJECT ARE IN MILLIMETRES UNLESS OTHERWISE INDICATED.
  - PRIOR TO COMMENCING CONSTRUCTION WORKS, THE CONTRACTOR SHALL WALK THE SITE WITH THE ECOLOGIST TO IDENTIFY AREAS WITH INVASIVE SPECIES. THESE AREAS WILL BE ADDRESSED APPROPRIATELY FOLLOWING THE INVASIVE SPECIES MANAGEMENT DOCUMENT AND DIRECTION FROM THE ECOLOGIST. THIS MAY INCLUDE REMOVAL, AVOIDANCE OF THIS AREA, OR OTHER DIRECTION AS GIVEN BY SITE ENGINEER.
  - DURING CONSTRUCTION ALL VEGETATION AND STRUCTURES ON PRIVATE PROPERTY ADJACENT TO THE WORK IS TO BE PROTECTED OR RESTORED TO ORIGINAL CONDITION IF REMOVAL IS REQUIRED.
  - NON-WOVEN GEOTEXTILE IS TO BE TERRAFIX 270R OR APPROVED EQUIVALENT.
  - ALL WORKS AND MATERIALS ARE TO BE IN ACCORDANCE WITH APPLICABLE ONTARIO PROVINCIAL STANDARD SPECIFICATIONS AND/OR CITY OF BURLINGTON STANDARDS.
  - CONTRACTOR SHALL BE RESPONSIBLE FOR ALL LAYOUT, SURVEY AND LOCATION OF UTILITIES.
  - ALL CONSTRUCTION AND TREE PROTECTION FENCING SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION, AFTER LAYOUT, AND SHALL BE INSPECTED AND APPROVED BY THE ENGINEER.
  - PRIOR TO TREE REMOVAL, THE CONTRACTOR SHALL MAKE THEMSELVES AWARE OF THE MIGRATORY BIRD CONVENTION ACT, 1994, AND THE POTENTIAL IMPACT NESTING BIRDS MAY HAVE ON THE ANTICIPATED START DATE AND CONSTRUCTION SCHEDULE. TREE REMOVALS AND VEGETATION CLEARING SHALL BE AVOIDED BETWEEN THE TERRESTRIAL TIMING WINDOW APRIL 1ST AND OCTOBER 15TH.
  - CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY CONSERVATION HALTON. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDE OF THE WATERCOURSE OR WETLAND.
  - ALL IN-WATER AND NEAR-WATER WORKS WILL BE CONDUCTED IN THE DRY AND MUST BE STAGED WITH APPROPRIATE EROSION AND SEDIMENT CONTROLS. PLAN THE WORK ACCORDINGLY WITH THE WEATHER FORECAST.
  - ALL DISTURBED SLOPES WITHIN THE VALLEY SYSTEM SHALL BE STABILIZED WITH EROSION CONTROL BLANKET.
  - TEMPORARY ACCESS ROADS AND DISTURBED AREAS WILL BE LINED WITH WOOD CHIPS AND/OR MUD MATS TO AVOID COMPACTING FROM MACHINERY AND/OR TRAFFIC.
  - AT NO TIMES WILL CONSTRUCTION EQUIPMENT BE PERMITTED TO OPERATE ON THE EXPOSED SHALE CHANNEL BED WITHOUT APPROVAL FROM THE ENGINEER. THE CONTRACTOR SHALL USE THE APPROPRIATE CONSTRUCTION MACHINERY TO OPERATE WITHIN THIS CONSTRAINT (E.G., EXCAVATOR WITH EXTENDED REACH). WHERE ACCESS TO THE SHALE CHANNEL BED IS REQUIRED TO INSTALL THE WORKS, ACCESS SHALL BE AS MUCH AS POSSIBLE. LOAD DISTRIBUTION MECHANISMS SHALL BE EMPLOYED, AND MACHINERY SHALL NOT BE AS SMALL AS POSSIBLE TO EFFECTIVELY COMPLETE THE WORK. MACHINERY SHALL NOT BE PERMITTED TO BE MOVED ALONG THE CREEK BED FOR ANY REASON.
  - AFTER THE END OF THE TWO-YEAR PLANTING WARRANTY, AN INSPECTION OF ALL PLANTED MATERIAL WILL BE COMPLETED BETWEEN CONTRACTOR AND CONTRACT ADMINISTRATOR TO IDENTIFY ALL PLANT MATERIAL WARRANTY ISSUES WHICH REQUIRE REPLACEMENT OR ADDITIONAL MEASURES TO COMPLY WITH THE CONTRACT. ADDITIONALLY ALL TREE SUPPORT SYSTEMS (WIRE AND T-BARS/WOOD POSTS) WILL REQUIRE REMOVAL BY CONTRACTOR AT THIS TIME.
  - SNOW FENCING OR OTHER BARRIER SHOULD BE INSTALLED DURING THE FIRST GROWING SEASON TO PROTECT PLANTS FROM TRAMPLING (I.E. PEDESTRIANS, DOGS) AND TO ALSO DISCOURAGE THE USE OF THE OLD TRAIL AND ACCESS TRAILS FOLLOWING CONSTRUCTION OF THE NEW TRAIL.

LEGEND

EXISTING

- CHANNEL CENTRELINE
- PROPERTY LIMIT
- EX. CONTOURS
- BOTTOM OF BANK
- TOP OF BANK
- WATER LINE
- EX. RIPPLE ROCK
- EX. TREE
- TREE/BRUSH LINE
- TREE REMOVAL
- IDENTIFIED BAT TREES

CONSTRUCTION

- CONSTRUCTION FENCE
- SILT FENCE
- SILT SOCKS
- TREE HOARDING FENCE
- COFFER DAM
- SILT ISOLATION CURTAIN (TURBIDITY CURTAIN)
- CONSTRUCTION ACCESS ROUTE
- EX. 2YR FLOODLINE

NO.	DATE	DESCRIPTION	APPD.
2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP




EROSION CONTROL MITIGATION GRINDSTONE CREEK UNSWORTH AVE TO SUMACH DR

SEDIMENT AND EROSION CONTROL AND STAGING PLAN AOC 1, 2, 3




DRN: KV	DSN: MP	CHKAPP: MP
DATE: 2022/05/11	DRAWING NUMBER	
SCALE: 1:500	C101	
PRO. No: 2116		




**DETAIL TREE PROTECTION DETAIL (BURLINGTON)** 1

TRUNK DIAMETER (DBH) *2	MINIMUM TREE PROTECTION ZONE (MPZ) DISTANCES REQUIRED *3	CRITICAL ROOT ZONE (CRZ) DISTANCES REQUIRED *3&4
<10 cm	1.8 m	1.8 m
11-40 cm	2.4 m	4.0 m
41-50 cm	3.0 m	5.0 m
51-60 cm	3.6 m	6.0 m
61-70 cm	4.2 m	7.0 m
71-80 cm	4.8 m	8.0 m
81-90 cm	5.4 m	9.0 m
91-100+ cm	6.0 m	10.0 m

- NOTES:**
- THE ROOTS OF A TREE CAN EXTEND FROM THE TRUNK TO APPROXIMATE 2-3 TIMES THE DISTANCE OF THE DRIP LINE.
  - DIAMETER AT BREAST HEIGHT (DBH) IS THE MEASUREMENT OF TREE TRUNK TAKEN AT 1.4 METRES ABOVE GROUND.
  - MINIMUM TREE PROTECTION ZONE AND CRITICAL ROOT ZONE DISTANCES ARE TO BE MEASURED FROM THE OUTSIDE EDGES OF THE TREE BASE TOWARDS THE DRIP LINE AND MAY BE LIMITED BY AN EXISTING PAVED SURFACE, PROVIDED THE EXISTING PAVED SURFACE REMAINS INTACT THROUGHOUT THE CONSTRUCTION WORK AND IS SUBJECT TO SECTION 6 OF THIS SPECIFICATION.
  - WHERE WORK IS BEING PERFORMED BEYOND THE MINIMUM TREE PROTECTION ZONE BUT WITHIN THE CRITICAL ROOT ZONE THE WORKS ARE SUBJECT TO SECTION 8 OF THIS SPECIFICATION.



**DETAIL HEAVY DUTY SILT FENCE** OPSD 219.130 (2015) 3



**DETAIL SILT SOCKS** SCALE: N.T.S. 4

**EROSION, SEDIMENT CONTROL AND DEWATERING NOTES:**

- BE ADVISED THAT CONSERVATION HALTON MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAW, OR ANY RIGHTS UNDER COMMON LAW.
- FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT, PREFERABLY AN ENVIRONMENTAL MONITOR, WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, CONSERVATION HALTON, AND ANY OTHER APPROPRIATE PARTIES.
- THE EROSION AND SEDIMENT CONTROL (ESC) PLAN IS A DYNAMIC DOCUMENT, WHICH MAY BE SUBJECT TO CHANGE OR MODIFICATIONS AS A RESULT OF SITE DEVELOPMENTS OR CHANGES ON SITE. ANY DEVIATION FROM APPROVED PLANS BE DESIGNED BY A QUALIFIED PROFESSIONAL.
- IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR CONSERVATION HALTON RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.
- ALL ACTIVITIES, INCLUDING MAINTENANCE PROCEDURES, SHALL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBBLE, CONCRETE OR OTHER DELETERIOUS SUBSTANCES INTO THE WATER. VEHICULAR REFUELLING AND MAINTENANCE WILL BE CONDUCTED A MINIMUM OF 30m FROM THE WATER.
- THE CONTRACTOR SHALL MONITOR THE FIVE-DAY WEATHER FORECAST ON A DAILY BASIS TO ANTICIPATE WEATHER CONDITIONS AND SHALL BE PREPARED TO LEAVE THE SITE IN A STABLE AND SECURE CONDITION SHOULD WATER LEVELS RISE. PRIOR TO AN ANTICIPATED LARGE WEATHER EVENT, THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROLS AND ENSURE THE SITE AND EROSION AND SEDIMENT CONTROL MEASURES ARE SECURE TO MITIGATE AGAINST WEATHER RELATED CONDITIONS. ALL WORKS SHALL BE PERFORMED DURING FAVORABLE WEATHER CONDITIONS.
- ALL DEWATERING SHALL BE DISCHARGED AT LEAST 15M FROM THE CREEK INTO A SEDIMENT TRAP. NO DEWATERING SHALL BE SENT DIRECTLY TO ANY WATERCOURSE OR SEWER. THESE CONTROL MEASURES SHALL BE MONITORED FOR EFFECTIVENESS AND MAINTAINED OR REVISED TO MEET THE OBJECTIVE OF PREVENTING SEDIMENT FROM ENTERING THE WATERCOURSE.
- THE INLET PUMP HEAD MUST BE COVERED WITH FILTER FABRIC OR CLEAR STONE AND HAVE AN APPROVED FISH SCREEN; THE OUTLET PUMP MUST DISCHARGE TO SEDIMENT BAG OR BASIN. DISCHARGE FROM THE BAG IS TO BE RELEASED TO A VEGETATED LOCATION OR IF VEGETATED LOCATION IS NOT AVAILABLE, A FLOW DISSIPATING STRUCTURE SHOULD BE PROVIDED. THE SEDIMENT BAG MUST BE LOCATED AT LEAST 15M AWAY FROM THE RECEIVING WATER BODY. THE MESH SIZE OF THE FISH SCREEN PLACED ON THE INTAKE PIPE WILL BE NO LARGER THAN 2.54 MM AS PER DFO INTERIM CODE OF PRACTICE.

**CONSTRUCTION PHASING AOC 4:**


- ESTABLISH ACCESS TO SITE AND STAGING AREAS AS NOTED ON THE CONSTRUCTION DRAWINGS.
- INSTALL SILT, CONSTRUCTION AND TREE PROTECTION FENCING AS WELL AS SITE SIGNAGE AS REQUIRED TO THE SATISFACTION OF THE ENGINEER AND THE CITY OF BURLINGTON PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY.
- ALL IN-STREAM CONSTRUCTION TO BE COMPLETED DURING A PERIOD OF DRY WEATHER TO ENSURE EFFECTIVENESS AND STABILITY OF THE SILT CURTAIN.

**CONSTRUCTION WORK RESTRICTIONS:**



- CONSTRUCTION WITHIN THE CREEK IS NOT PERMITTED DURING/FOLLOWING A RAINFALL EVENT. DURING THIS TIME, THE CONTRACTOR IS TO STABILIZE THE SITE AND ALLOW FLOWS THROUGH THE WORK AREA. THIS APPROACH IS TO BE UTILIZED WHEN FLOW RATES IN THE CREEK EXCEED BASEFLOW/LOW FLOW CONDITIONS.
- DURING THE DEWATERING, IF THE SIZE OF SEDIMENT PARTICLE IS LESS THAN OPENING OF THE FILTER BAG, THAN A SEDIMENT TANK MUST BE USED FOR SILTATION PURPOSES.
- DURING CLOSURE OF THE PERMANENT WATERCOURSE CHANNEL, OR THE TEMPORARY WATER PASSAGE SYSTEM, ANY STRANDED FISH SHALL BE RELEASED OUTSIDE OF THE DISTURBED AREAS BY A QUALIFIED BIOLOGIST. THIS WORK WILL BE CONDUCTED UNDER LICENCE FROM THE MINISTRY OF NATURAL RESOURCES AND FORESTRY. THE CONTRACTOR IS RESPONSIBLE FOR SUPPLYING ALL MATERIALS, OBTAINING ASSOCIATED PERMITS, AND ANY ADDITIONAL COSTS INCURRED BY COMPLETING A FISH RESCUE BY A QUALIFIED BIOLOGIST.
- ALL DISTURBED AREAS ARE TO BE STABILIZED DAILY OR PROTECTED WITH EROSION AND SEDIMENT CONTROL.
- SILT CONTROL FENCE SHALL BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL REMAIN IN PLACE DURING AND AFTER CONSTRUCTION UNTIL THE VEGETATION HAS BEEN ESTABLISHED AND THE SITE HAS BEEN STABILIZED.
- ALL STOCKPILE AREAS ARE TO BE ENCLOSED WITH HEAVY DUTY SILT CONTROL FENCING. ALL TEMPORARY SOIL OR DIRT STOCKPILES ARE TO BE PROVIDED WITH THE NECESSARY SEDIMENT AND EROSION CONTROL FEATURES, INCLUDING SEEDING IF ANTICIPATED TO BE STORED MORE THAN ONE MONTH. STOCKPILES MUST NOT BE LOCATED IN AREAS OF CONCENTRATED FLOW AND MINIMUM OF 15m FROM THE TOP OF BANK OR WATERCOURSE. NO FILL WILL BE PERMANENTLY LEFT ON SITE. ALL LEFTOVER FILL WILL BE TRUCKED OFF SITE AND FINAL FILL DESTINATION WILL BE PROVIDED TO CONSERVATION AUTHORITY.
- ADDITIONAL EROSION AND SEDIMENT CONTROL MATERIALS (SILT FENCE, STRAW BALES, CLEAR STONE) ARE TO BE KEPT ON SITE FOR EMERGENCIES AND REPAIRS.
- EROSION AND SEDIMENT CONTROL METHODS ARE TO BE CONTINUOUSLY EVALUATED AND UPGRADES ARE TO BE IMPLEMENTED, WHEN NECESSARY OR AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION. ANY SEDIMENT LADEN WATER WILL NOT BE ALLOWED TO DISCHARGE TO THE CREEK.
- SHOULD THERE BE CONTINUOUS PUMPING PROPOSED, AN AFTER HOURS TECHNICAL IS TO BE ASSIGNED TO ENSURE THAT THE APPROPRIATE TREATMENT SYSTEM (PUMPING EQUIPMENT, SETTLEMENT PONDS, SEDIMENTATION TANK, ETC.) IS FUNCTIONING PROPERLY.
- AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ON-SITE FOR EMERGENCIES.
- ANY SEDIMENT SPILL FROM THE SITE MUST BE REPORTED TO MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE (CALL SPILL ACTION CENTER AT 1-800-268-6060)
- EROSION AND SEDIMENT CONTROL METHODS ARE TO BE INSPECTED, MAINTAINED AND CONTINUOUSLY EVALUATED WEEKLY, AFTER ANY RAIN EVENT, ANY SNOW MELT EVENT, IF A SITE IS LEFT ALONE FOR 90 DAYS OR LONGER, A MONTHLY INSPECTION IS REQUIRED. UPGRADES ARE TO BE IMPLEMENTED WHEN NECESSARY OR AS DIRECTED BY ENGINEER.
- ALL MAINTENANCE AND REPAIRS AS DIRECTED BY ENGINEER OR NOTICED DURING INSPECTION OF EROSION AND SEDIMENT CONTROLS SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF INSPECTION.
- SEDIMENT SHOULD BE REMOVED FROM THE SEDIMENT CONTROL FENCING ONCE SEDIMENT HAS ACCUMULATED TO A LEVEL OF ONE-THIRD THE HEIGHT OF THE FENCING OR TO A HEIGHT OF 30cm. ALL ACCUMULATED SEDIMENT IS REQUIRED TO BE REMOVED PRIOR TO THE REMOVAL OF THE CONTROL MEASURES.

**GENERAL NOTES:**

- ALL WORK IS TO BE COMPLETED BETWEEN JULY 1ST AND SEPTEMBER 14TH.
- ALL UNSUITABLE AND/OR EXCESS MATERIAL IS TO BE DISPOSED OF AT AN OFF-SITE LOCATION TO BE ARRANGED FOR BY THE CONTRACTOR.
- ALL MEASUREMENTS FOR THIS PROJECT ARE IN MILLIMETRES UNLESS OTHERWISE INDICATED.
- PRIOR TO COMMENCING CONSTRUCTION WORKS, THE CONTRACTOR SHALL WALK THE SITE WITH THE ECOLOGIST TO IDENTIFY AREAS WITH INVASIVE SPECIES. THESE AREAS WILL BE ADDRESSED APPROPRIATELY FOLLOWING THE INVASIVE SPECIES MANAGEMENT DOCUMENT AND DIRECTION FROM THE ECOLOGIST. THIS MAY INCLUDE REMOVAL, AVOIDANCE OF THIS AREA, OR OTHER DIRECTION AS GIVEN BY SITE ENGINEER.
- DURING CONSTRUCTION ALL VEGETATION AND STRUCTURES ON PRIVATE PROPERTY ADJACENT TO THE WORK IS TO BE PROTECTED OR RESTORED TO ORIGINAL CONDITION IF REMOVAL IS REQUIRED.
- NON-WOVEN GEOTEXTILE IS TO BE TERRAFIX 270R OR APPROVED EQUIVALENT.
- ALL WORKS AND MATERIALS ARE TO BE IN ACCORDANCE WITH APPLICABLE ONTARIO PROVINCIAL STANDARD SPECIFICATIONS AND/OR CITY OF BURLINGTON STANDARDS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ALL LAYOUT, SURVEY AND LOCATION OF UTILITIES.
- ALL CONSTRUCTION AND TREE PROTECTION FENCING SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION, AFTER LAYOUT, AND SHALL BE INSPECTED AND APPROVED BY THE ENGINEER.
- PRIOR TO TREE REMOVAL, THE CONTRACTOR SHALL MAKE THEMSELVES AWARE OF THE MIGRATORY BIRD CONVENTION ACT, 1994, AND THE POTENTIAL IMPACT NESTING BIRDS MAY HAVE ON THE ANTICIPATED START DATE AND CONSTRUCTION SCHEDULE. TREE REMOVALS AND VEGETATION CLEARING SHALL BE AVOIDED BETWEEN THE TERRESTRIAL TIMING WINDOW APRIL 1ST AND OCTOBER 15TH.
- CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY CONSERVATION HALTON. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDE OF THE WATERCOURSE OR WETLAND.
- ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY AND MUST BE STAGED WITH APPROPRIATE EROSION AND SEDIMENT CONTROLS. PLAN THE WORK ACCORDINGLY WITH THE WEATHER FORECAST.
- ALL DISTURBED SLOPES WITHIN THE VALLEY SYSTEM SHALL BE STABILIZED WITH EROSION CONTROL BLANKET.
- TEMPORARY ACCESS ROADS AND DISTURBED AREAS WILL BE LINED WITH WOOD CHIPS AND/OR MUD MATS TO AVOID COMPACTION FROM MACHINERY AND EQUIPMENT.
- AT NO TIMES WILL CONSTRUCTION EQUIPMENT BE PERMITTED TO OPERATE ON THE EXPOSED SHALE CHANNEL BED WITHOUT APPROVAL FROM THE ENGINEER. THE CONTRACTOR SHALL USE THE APPROPRIATE CONSTRUCTION MACHINERY TO OPERATE WITHIN THIS CONSTRAINT (E.G., EXCAVATOR WITH EXTENDED REACH), WHERE ACCESS TO THE SHALE CHANNEL BED IS REQUIRED TO INSTALL THE WORKS. ACCESS SHALL BE LIMITED AS MUCH AS POSSIBLE, LOAD DISTRIBUTION MECHANISMS SHALL BE EMPLOYED, AND MACHINERY USED SHALL BE AS SMALL AS POSSIBLE TO EFFECTIVELY COMPLETE THE WORK. MACHINERY SHALL NOT BE PERMITTED TO BE MOVED ALONG THE CREEK BED FOR ANY REASON.
- AFTER THE END OF THE TWO-YEAR PLANTING WARRANTY, AN INSPECTION OF ALL PLANTED MATERIAL WILL BE COMPLETED BETWEEN CONTRACTOR AND CONTRACT ADMINISTRATOR TO IDENTIFY ALL PLANT MATERIAL WARRANTY ISSUES WHICH REQUIRE REPLACEMENT OR ADDITIONAL MEASURES TO COMPLY WITH THE CONTRACT. ADDITIONALLY ALL TREE SUPPORT SYSTEMS (WIRE AND T-BARS/WOOD POSTS) WILL REQUIRE REMOVAL BY CONTRACTOR AT THIS TIME.
- SNOW FENCING OR OTHER BARRIER SHOULD BE INSTALLED DURING THE FIRST GROWING SEASON TO PROTECT PLANTS FROM TRAMPLING (I.E., PEDESTRIANS, DOGS), AND TO ALSO DISCOURAGE THE USE OF THE OLD TRAIL AND ACCESS TRAILS FOLLOWING CONSTRUCTION OF THE NEW TRAIL.



ONTARIO PROVINCIAL STANDARD DRAWING		Nov 2015	Rev 2
<b>TURBIDITY CURTAIN</b>		OPSD 219.260	



**LEGEND**

**EXISTING**

- CHANNEL CENTRELINE
- PROPERTY LIMIT
- EX. CONTOURS
- BOTTOM OF BANK
- TOP OF BANK
- WATER LINE
- EX. RIFFLE ROCK
- EX. TREE
- TREE/BRUSH LINE
- TREE REMOVAL
- IDENTIFIED BAT TREES

**CONSTRUCTION**


- CONSTRUCTION FENCE
- SILT FENCE
- SILT SOCKS
- TREE HOARDING FENCE
- COFFER DAM
- SILT ISOLATION CURTAIN (TURBIDITY CURTAIN)
- CONSTRUCTION ACCESS ROUTE
- EX. 2YR FLOODLINE

2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP




**EROSION CONTROL MITIGATION GRINDSTONE CREEK**  
UNSWORTH AVE TO SUMACH DR

**SEDIMENT AND EROSION CONTROL AND STAGING PLAN AOC 4**



DRN: KV	DSN: MP	CHK/APP: MP
DATE: 2022/05/11	DRAWING NUMBER	
SCALE: 1:500	<b>C102</b>	
PRO. No: 2116		



**GRANULAR SCREENINGS**  
THE FOLLOWING IS THE GRADATION CHART LIMITS FOR 4.75mm (E7) WASHED GRANITE CHIP.

SIZE/TEST	TARGET
9.5mm	100-100
6.7mm	90-100
4.75mm	65-75
2.36mm	12-20
1.18mm	0-7
75um	0-2

RESTORE DISTURBED EDGES WITH TOPSOIL AND SEED. SEED TO BE OSC EARLY SUCCESSION DRY PRAIRIE MEADOW MIX 8115 OR APPROVED EQUAL.


SUPPLY AND PLACE 150mm DEPTH OF 4.75mm (E7) WASHED GRANITE CHIP SCREENING OF APPROVED EQUAL AS PER GRADATION INFORMATION CHART ON LEFT. LIGHTLY COMPACT WITH 1 TONNE ROLLER. SCREENING TO CONTAIN APPROX. 7% MOISTURE FOR COMPACTION.

SCRAPE EXISTING VEGETATED SURFACE TO A MAX. DEPTH OF 100mm TO REMOVE HUMUS LAYER. CAST MATERIAL TO SIDE OF TRAIL TO BE USED FOR BLENDING WITH SURROUNDING GRADE. WHERE NATIVE MATERIAL IS EXISTING GRANULAR TRAIL, SCRAPE SURFACE TO LEVEL AND USE AS BASE. DO NOT EXCAVATE EXISTING GRANULAR MATERIAL.

NOTE:  
1. EX. TRAILS ARE 2.40m WIDE UNLESS OTHERWISE NOTED ON DRAWINGS.  
2. PR. TRAIL 3.0m WIDE  
3. TRAIL LAYOUT TO BE MARKED AND CONFIRMED ON-SITE WITH CITY REPRESENTATIVE.






**DETAIL: GRANITE CHIP SCREENING - CITY OF BURLINGTON**

1:50



**AOC 1 REMOVALS PLAN**

SCALE 1:250




**SECTIONS**

SCALE 1:150

**AOC 1 - TREE REMOVALS**

Tree ID #	Common Name	Size (cm)	Notes
143	BLACK WALNUT	19	GOOD
150	BLACK WALNUT	65	GOOD
152	DEAD	100	DEAD
166	EUROPEAN BUCKTHORN	14	GOOD
167	DEAD	10	DEAD
168	BLACK WALNUT	38	GOOD
169	AMERICAN BASSWOOD	13.5	GOOD, ON SLOPE, STRONG LEAN
171	BLACK WALNUT	20	GOOD, ON SLOPE
172	GREEN ASH	14	FAIR, ASH BORER DAMAGE
173	BLACK WALNUT	41	GOOD, TWO TRUNKS AND 44
175	BLACK WALNUT	23	FAIR, MULTIPLE DEAD BRANCHES
228	BLACK WALNUT	54	FAIR, MODERATE BRANCH DIEBACK, LOCATED DIRECTLY BEDSIDE PATH



**PROPOSED TRAIL PROFILE**

SCALE: H1:250 V1:50

STATION	C/A/ PROPOSED PROFILE	C/A/ EXISTING PROFILE	C/A/ TRAIL PROFILE
0+005	83.51	83.45	83.45
0+010	83.89	83.46	83.46
0+015	84.29	83.47	83.62
0+020	84.69	83.47	84.55
0+025	85.09	83.47	85.48
0+030	85.49	83.48	86.24
0+035	85.89	83.59	86.47
0+040	86.29	83.73	86.64
0+045	86.69	84.03	86.81
0+050	87.09	84.37	86.99
0+055	87.31	86.01	87.26
0+060	87.08	86.24	87.65
0+065	86.67	86.31	88.02
0+070	86.26	86.30	88.24
0+075	85.85	86.19	87.92
0+080	85.45	85.91	86.48
0+085	85.05	85.28	85.46
0+090	84.65	84.74	84.46
0+095	84.25	84.30	84.29
0+100	83.85	83.88	83.88
0+105	83.45	83.45	83.45
0+110	83.05	83.05	83.05

**LEGEND**

**EXISTING**

- CHANNEL CENTRELINE
- PROPERTY LIMIT
- EX. CONTOURS
- BOTTOM OF BANK
- TOP OF BANK
- WATER LINE
- EX. RIFFLE ROCK
- EX. TREE
- TREE/BURSH LINE
- TREE REMOVAL
- IDENTIFIED BAT TREES

**PROPOSED**

- PR. CONTOURS
- ARMOUR STONE
- BRUSH LAYER
- PR. ROCK
- LOG
- CONSTRUCTION ACCESS
- LIMIT OF GRADING
- PROPOSED TRAIL
- LONG TERM STABLE SLOPE LINE (LTSSL)
- LTSSL + 6.0m EROSION ALLOWANCE

**REVISIONS**

NO.	DATE	DESCRIPTION	APPD.
2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP




**EROSION CONTROL MITIGATION GRINDSTONE CREEK**  
UNSWORTH AVE TO SUMACH DR


**AREA OF CONCERN 1 PROPOSED PLAN**  
STA: 0+320 TO 0+440



DRN: KV	DSN: MP	CHK/APP: MP
DATE: 2022/05/11	DRAWING NUMBER	
SCALE: H 1:250 V 1:50	<b>C201</b>	
PRO. No: 2116		





**AOC 2 PROPOSED PLAN**  
SCALE 1:100




**PROFILE @ CENTRELINE GRINDSTONE CREEK**  
SCALE: H1:100 V1:25

STATION	PROPOSED TOP OF ARMOURSTONE	C.A. EXISTING TOP OF SHALE PROFILE
0+250	79.36	79.36
0+255	81.10	79.34
0+260	81.10	79.45
0+265	81.10	79.62
0+270	81.10	79.71
0+275	81.52	79.82
0+280	81.52	79.91
0+285	81.52	79.74
0+290	81.52	79.98




**SECTIONS**  
SCALE 1:50




**AOC 2 REMOVALS PLAN**  
SCALE 1:200

AOC 2 - TREE REMOVALS			
Tree ID #	Common Name	Size (cm)	Notes
234	MANITоба MAPLE	15	FAIR, STRONG LEAN IN TRUNK DAMAGE AT BASE OF TRUNK



BRUSH LAYER		
COMMON NAME	SCIENTIFIC NAME	% OF MIX
RED OSIER DOGWOOD	CORNUS SERICEA	10%
PUSSY WILLOW	SALIX DISCOLOR	30%
SANDBAR WILLOW	SALIX EXIGUA	30%
SLENDER WILLOW	SALIX PETIOLARIS	30%



**VEGETATED ARMOURSTONE DETAIL**  
SCALE 1:25

**LEGEND**

**EXISTING**

- CHANNEL CENTRELINE
- PROPERTY LIMIT
- EX. CONTOURS
- BOTTOM OF BANK
- TOP OF BANK
- WATER LINE
- EX. RIFFLE ROCK
- EX. TREE
- TREE/BRUSH LINE
- TREE REMOVAL
- IDENTIFIED BAT TREES

**PROPOSED**

- PR. CONTOURS
- ARMOUR STONE
- BRUSH LAYER
- WRAPPED SOIL/ROCK TREATMENT
- PR. ROCK
- LOG
- CONSTRUCTION ACCESS
- LIMIT OF GRADING

**AOC 2 - ROCK TABLE 1**

Recommended B-Axis Size of Substrate (mm)	Portion by Volume (%)
Angular Stone	Vegetated Revetment
Granular B/ Native material	10
50-100	30
100-200	40
200-300	20


NO.	DATE	DESCRIPTION	APPD.
2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP

REVISIONS




**EROSION CONTROL MITIGATION GRINDSTONE CREEK**  
UNSWORTH AVE TO SUMACH DR

**AREA OF CONCERN 2 PROPOSED PLAN**  
STA: 0+190 TO 0+310




DRN: KV	DSN: MP	CHK/APP: MP
DATE: 2022/04/29	DRAWING NUMBER	
SCALE: 1:200	C202	
PRO. No: 2116		




**AOC 3 PROPOSED PLAN**  
SCALE 1:100

AOC 3 - TREE REMOVALS			
Tree ID #	Common Name	Size (cm)	Notes
182	MANITOBA MAPLE	27.3	POOR, STRONG LEAN, MANY DEAD BRANCHES
183	BLACK WALNUT	33	GOOD
198	BLACK ALDER	23	GOOD, ON LEAN
199	BLACK ALDER	25.5	GOOD
200	MANITOBA MAPLE	17.5	FAIR

BRUSH LAYER		
COMMON NAME	SCIENTIFIC NAME	% OF MIX
RED OSIER DOGWOOD	CORNUS SERICEA	10%
PUSSY WILLOW	SALIX DISCOLOR	30%
SANDBAR WILLOW	SALIX EXIGUA	30%
SLENDER WILLOW	SALIX PETIOLARIS	30%




**DETAIL: BRUSH LAYER**  
SCALE 1:25




**SECTION**  
SCALE 1:50

AOC 3 - ROCK TABLE 1		
Recommended B-Axis Size of Substrate (mm)	Portion by Volume (%)	
Angular Stone	Vegetated Revetment	
Granular B/ Native material	10	
50-100	10	
100-200	10	
200-300	20	
400-500	25	
600	25	
Sum	100	
Depth	1000	



**AOC 3 REMOVALS PLAN**  
SCALE 1:150



**LEGEND**

- EXISTING**
- CHANNEL CENTRELINE
  - PROPERTY LIMIT
  - EX. CONTOURS
  - BOTTOM OF BANK
  - TOP OF BANK
  - WATER LINE
  - EX. RIFFLE ROCK
  - EX. TREE
  - TREE/BRUSH LINE
  - TREE REMOVAL
  - IDENTIFIED BAT TREES
- PROPOSED**
- PR. CONTOURS
  - ARMOUR STONE
  - BRUSH LAYER
  - PR. ROCK
  - LOG
  - CONSTRUCTION ACCESS
  - LIMIT OF GRADING


NO.	DATE	DESCRIPTION	APPD.
2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP



**EROSION CONTROL  
MITIGATION  
GRINDSTONE CREEK**

UNSWORTH AVE TO SUMACH DR



**AREA OF CONCERN 3  
PROPOSED PLAN  
STA: 0+125 TO 0+160**



DRN: KV	DSN: MP	CHK/APP: MP
DATE: 2022/05/11	DRAWING NUMBER	
SCALE: 1:100	<b>C203</b>	
PRO. No: 2116		

AOC 4 - ROCK TABLE 1	
Size of Substrate (mm)	Portion by Volume (%)
Angular Stone	Rock toe protection
Granular B/ Native material	10
50-100	30
100-200	30
200-300	20
400-500	10
Sum	100

AOC 4 - ROCK TABLE 2	
Size of Substrate (mm)	Portion by Volume (%)
Angular Stone	Soil lifts
Soil	70
Granular B	15
50-100	15
Sum	100



**COIR BLANKET WRAPPED LIFTS:**

- COIR BLANKET TO BE 700G EROSION CONTROL BLANKET, OR EQUIVALENT
- THE SOIL BACKFILL USED FOR LIFTS AND TOPSOIL USED FOR LAYERING WITH THE LIVE BRANCHES SHALL BE FREE FROM ANY GRAVEL OR COBBLE MATERIAL.
- SOIL BACKFILL SHALL BE COMPACTED SUCH THAT FUTURE SETTLING WILL BE KEPT TO A MINIMUM, YET NOT SUCH THAT THE UNDERLYING BRUSH IS DISPLACED OR DAMAGED.
- THE TOP OF THE BACKFILL FOR THE FIRST LIFT SHALL BE SLOPED AT APPROXIMATELY 5% AWAY FROM THE STREAM.
- PLACE A LAYER OF 2.0m WIDE COIR 700G EROSION CONTROL BLANKET, OR EQUIVALENT, ON TOP OF THE TOPSOIL AND LIVE BRANCHES SUCH THAT 0.75m OF THE BLANKET WILL BE BURIED BELOW THE NEXT SOIL LIFT. ALLOW THE REMAINING 1.25m OF BLANKET TO HANG OVER THE PRECEDING SOIL LIFT OR COIR FIBRE LOGS.
- PLACE A SECOND LAYER OF 2.0m WIDE NON-WOVEN COIR MATTING OVER THE EROSION CONTROL BLANKET TO THE SAME LIMITS.
- SOIL CAN BE COMPACTED BY STACKING A PIECE OF SAWN LUMBER BOARD EDGEWAYS UP TO THE LIFT HEIGHT SPECIFIED AND SECURING WITH WOODEN STAKES TO PROVIDE A RIGID BACKSTOP FOR COMPACTING SOIL LIFT.
- PLACE SOIL BACKFILL UP TO THE LIFT HEIGHT SPECIFIED OF NO GREATER THAN 0.3m BEING CAREFUL NOT TO PUSH/PULL OR TEAR THE FABRIC PREVIOUSLY PLACED.
- THE TOP OF THE SOIL BACKFILL SHALL BE FLAT WITHIN THE LIFT SETBACK DISTANCE. THE SOIL BACKFILL SHALL BE SLOPED AT AN APPROXIMATE 5% SLOPE AWAY FROM THE STREAM.
- TOP DRESS THE SOIL LIFT WITH THE APPROVED SEED MIX (DRAWING C-500) FROM THE FACE OF THE SOIL LIFT BACK INTO THE FLOODPLAIN AT LEAST 1.2m.
- REMOVE THE SAWN LUMBER AND WOODEN STAKES FROM THE FACE OF THE SOIL LIFT AND WRAP THE FACE AND TOP OF THE SOIL LIFT USING THE WOVEN AND NON-WOVEN COIR MATTING HANGING OVER THE PREVIOUS LIFT/COIR FIBRE LIFTS.
- THE EROSION CONTROL FABRIC SHALL BE PULLED AS TIGHT AS POSSIBLE WITHOUT TEARING OR EXCESSIVELY DISTORTING THE FABRIC.

**LIVE STAKES AND BRUSH LAYER**


- LIVE STAKES TO CONSIST OF DOGWOODS AND WILLOWS

LIVESTAKES/BRUSH LAYER MIX		
COMMON NAME	SCIENTIFIC NAME	% OF MIX
RED OSIER DOGWOOD	CORNUS SERICEA	10%
PUSSY WILLOW	SALIX DISCOLOR	30%
SANDBAR WILLOW	SALIX EXIGUA	30%
SLENDER WILLOW	SALIX PETIOLARIS	30%

- PLACE A LAYER OF TOPSOIL AND LIVE BRANCHES ON TOP OF EACH SOIL LIFT SUCH THAT APPROXIMATELY 0.15 TO 0.30m OF EACH LIVE BRANCH WILL BE EXPOSED AND THE REMAINDER (0.60 TO 1.20m) OF EACH LIVE BRANCH WILL BE COVERED BY THE NEXT SOIL LIFT.
- LIVE STAKES TO BE A MINIMUM 0.75m LONG AND EMBEDDED INTO THE SOIL LIFT MIN. 0.6m. LIVE STAKES TO BE SPACED IN 2 ROWS 0.5m ON CENTRE.


**TREE REPLACEMENT - AOC 4**

QTY	BOTANICAL NAME	COMMON NAME	CAL (MM)	ROOT	COMMENTS
1	<i>Acer saccharum</i>	SUGAR MAPLE	45	BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING



DETAIL: VEGETATED BANK PROTECTION

1:30



**SEED MIX TABLES**

**CONSERVATION HALTON UPLAND DRY MEADOW MIX**

SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Rudbeckia hirta</i>	BLACK EYED SUSAN	15
<i>Andropogon gerardii</i>	BLUE BLUESTEM	30
<i>Symphoricarum cordifolius</i>	BLUE WOOD ASTER	1
<i>Solidago canadensis var. canadensis</i>	CANADA GOLDENROD	2
<i>Anemone canadensis</i>	CANADA ANEMONE	1
<i>Asclepias syriaca</i>	COMMON MILKWEED	5
<i>Oenothera biennis</i>	EVENING PRIMROSE	2
<i>Euthamia graminifolia</i>	GRASS-LEAVED GOLDENROD	1
<i>Schizachyrium scoparium</i>	LITTLE BLUESTEM	20
<i>Carex granularis</i>	MEADOW/OPEN FILED SEDGE	12
<i>Symphoricarum novae-angliae</i>	NEW ENGLAND ASTER	1
<i>Clematis virginiana</i>	VIRGINS BOWER	5
<i>Monarda fistulosa var. fistulosa</i>	WILD BERGAMOT	5

\*\*SOW AT 25KG/HA\*\*

**CONSERVATION HALTON MEADOW MARSH MIX**

SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Carex bebbii</i>	BEBBS SEDGE	1
<i>Labella siphilitica</i>	BLUE LOBELIA	1
<i>Verbena hastata</i>	BLUE VERVAIN	15
<i>Eupatorium perfoliatum</i>	BONASET	2
<i>Scirpus atrovirens</i>	DARK-GREEN BULRUSH	5
<i>Carex vulpinoidea</i>	FOX SEDGE	25
<i>Euthamia graminifolia</i>	GRASS-LEAVED GOLDENROD	1
<i>Carex granularis</i>	MEADOW/OPEN FILED SEDGE	10
<i>Symphoricarum puniceum</i>	PURPLE STEMMED ASTER	1
<i>Juncus effusus ssp. solutus</i>	SOFT RUSH	5
<i>Eutrochium maculatum var. maculatum</i>	SPOTTED JOE PYE WEED	2
<i>Mimulus ringens</i>	MONKEY FLOWER	1
<i>Carex stipata</i>	STALK GRAIN SEDGE	2
<i>Glyceria grandis</i>	TALL MANNIA GRASS	2
<i>Scirpus cyperinus</i>	WOOLGRASS	2
<i>Poa palustris</i>	FOWL BLUEGRASS	25

\*\*SOW AT 25KG/HA\*\*

**CONSERVATION HALTON NURSE CROP MIX (FALL) - 6824mm<sup>2</sup>**




SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Elymus canadensis</i>	CANADA WILD RYE	35
<i>Avena sativa</i>	ANNUAL OATS	25
<i>Agrostis stolonifera</i>	CREEPING BENT GRASS	20
<i>Festuca rubra</i>	RED FESCUE	20

\*\*WATERING MAY BE REQUIRED TO PROMOTE SUCCESSFUL ESTABLISHMENT\*\* OR JULY\*\*

\*\*SOW AT 25KG/HA\*\*

**AOC 4 - TREE REMOVALS**

Tree ID#	CommonName	Size (cm)
3	SUGAR MAPLE	27.5



SECTION SCALE 1:100

**LEGEND**

**EXISTING**

- Channel Centreline
- Property Limit
- Ex. Contours
- Bottom of Bank
- Top of Bank
- Water Line
- Ex. Riffle Rock
- Ex. Tree
- Tree/Brush Line
- Tree Removal
- Identified Bat Trees

**PROPOSED**

- Pr. Contours
- Armour Stone
- Brush Layer
- Wrapped Soil/Rock Treatment
- Pr. Rock
- Log
- Construction Access
- Limit of Grading

---

2. 2022/05/11 ISSUED FOR APPROVAL MP

1. 2022/01/25 ISSUED FOR APPROVAL MP

NO.	DATE	DESCRIPTION	APPD.

**REVISIONS**

**EROSION CONTROL MITIGATION GRINDSTONE CREEK**

UNSWORTH AVE TO SUMACH DR

**AREA OF CONCERN 4 PROPOSED PLAN STA: 0+020 TO 0+080**

DRN: KV DSN: MP CHK/APP: MP



DATE: 2022/05/11 DRAWING NUMBER: C204

SCALE: 1:100


PRO. No: 2116

CELL A - PLANTING AREA (11 CELLS)							
TREES	QTY	BOTANICAL NAME	COMMON NAME	CAL (MM)	HT (cm)	ROOT	COMMENTS
DECIDUOUS	13	<i>Populus tremulaoides</i>	TREMBLING ASPEN	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
	13	<i>Quercus rubra</i>	RED OAK	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
	14	<i>Acer saccharum</i>	SUGAR MAPLE	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
CONIFEROUS	13	<i>Thuja Occidentalis</i>	WHITE CEDAR		150	BALLED AND BURLAPPED	
	13	<i>Tsuga Occidentalis</i>	EASTERN HEMLOCK		150	BALLED AND BURLAPPED	
SHRUBS	66	<i>Prunus virginiana</i>	CHOKECHERRY	60	1 GAL.	MIN. 3 STEMS	
	66	<i>Cornus racemosa</i>	GREY DOGWOOD	60	3 GAL.	MIN. 3 STEMS	
	66	<i>Sambucus canadensis</i>	BLACK ELDERBERRY	60	3 GAL.	MIN. 3 STEMS	
	66	<i>Viburnum acerifolium</i>	MAPLE-LEAVED VIBURNUM	60	3 GAL.	MIN. 3 STEMS	
	66	<i>Cornus alternifolia</i>	ALTERNATE-LEAF DOGWOOD	60	3 GAL.	MIN. 3 STEMS	

CELL B - PLANTING AREA (4 CELLS)							
TREES	QTY	BOTANICAL NAME	COMMON NAME	CAL (MM)	HT (cm)	ROOT	COMMENTS
TREES	3	<i>Salix nigra</i>	BLACK WILLOW	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
	3	<i>Populus balsamifera</i>	BALSUM POPLAS	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
	3	<i>Populus deltoides</i>	COTTONWOOD	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
	4	<i>Quercus macrocarpa</i>	BUR OAK	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
SHRUBS	3	<i>Acer saccharinum</i>	SILVER MAPLE	45		BALLED AND BURLAPPED	SINGLE LEADER, FULL BRANCHING
	16	<i>Cornus stolonifera</i>	RED OSIER DOGWOOD	60	3 GAL.	MIN. 3 STEMS	
	16	<i>Sambucus canadensis</i>	BLACK ELDERBERRY	60	3 GAL.	MIN. 3 STEMS	
	16	<i>Viburnum lentago</i>	NANNYBERRY	60	3 GAL.	SINGLE LEADER, FULL BRANCHING	
	16	<i>Salix petiolaris</i>	SLENDER WILLOW	60	3 GAL.	MIN. 3 STEMS	
16	<i>Salix bebbiana</i>	BEBB'S WILLOW	60	3 GAL.	MIN. 3 STEMS		



- RECOMMENDED
- TAMP SOIL FIRMLY TO REMOVE AIR POCKETS
  - SOAK BACKFILLED SOIL WITH WATER AFTER PLANTING
  - CONSIDER ADDING MYCORRHIZAL INOCULANT TO SOIL



**LEGEND**

RESTORATION PLANTINGS

- UPLAND DRY MEADOW MIX
- MEADOW MARSH MIX
- PLANTING CELL A
- PLANTING CELL B
- TEMPORARY SNOW FENCE

NO.	DATE	DESCRIPTION	APPD.
2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP

**REVISIONS**

**CITY OF Burlington**

**ecosystem recovery inc.**  
PROFESSIONAL ENGINEERS

**EROSION CONTROL MITIGATION GRINDSTONE CREEK**  
UNSWORTH AVE TO SUMACH DR

**AOC 1, 2 AND 3 RESTORATION PLAN**  
STA: 0+125 TO 0+440

**J. L. PRINCE**  
100112049  
May 10/22  
PROVINCE OF ONTARIO

DRN: KV	DSN: MP	CHK/APP: MP
DATE: 2022/05/11	DRAWING NUMBER	
SCALE: 1:250	<b>C301</b>	
PRO. No: 2116		

**SEED MIX TABLES**

CONSERVATION HALTON UPLAND DRY MEADOW MIX		
SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Rudbeckia hirta</i>	BLACK EYED SUSAN	15
<i>Andropogon gerardii</i>	BLUE BLUESTEM	30
<i>Symphyotrichum cordifolius</i>	BLUE WOOD ASTER	1
<i>Solidago canadensis var. canadensis</i>	CANADA GOLDENROD	2
<i>Anemone canadensis</i>	CANADA ANEMONE	1
<i>Asclepias syriaca</i>	COMMON MILKWEED	5
<i>Oenothera biennis</i>	EVENING PRIMROSE	2
<i>Euthamia graminifolia</i>	GRASS-LEAVED GOLDENROD	1
<i>Schizachyrium scoparium</i>	LITTLE BLUESTEM	20
<i>Carex granularis</i>	MEADOW/OVEN FILED SEDGE	12
<i>Symphyotrichum novae-angliae</i>	NEW ENGLAND ASTER	1
<i>Clematis virginiana</i>	VIRGINS BOWLER	5
<i>Monarda fistulosa var. fistulosa</i>	WILD BERGAMOT	5

\*\*SOW AT 25KG/HA\*\*


CONSERVATION HALTON MEADOW MARSH MIX		
SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Carex bebbii</i>	BEBB'S SEDGE	1
<i>Labellia siphilitica</i>	BLUE LOBELIA	1
<i>Verbena hastata</i>	BLUE VERVAIN	15
<i>Eupatorium perfoliatum</i>	BONESET	2
<i>Scirpus atrovirens</i>	DARK-GREEN BULRUSH	5
<i>Carex vulpinoidea</i>	FOX SEDGE	25
<i>Euthamia graminifolia</i>	GRASS-LEAVED GOLDENROD	1
<i>Carex granularis</i>	MEADOW/OVEN FILED SEDGE	10
<i>Symphyotrichum puniceum</i>	PURPLE STEMMED ASTER	1
<i>Juncus effusus ssp. Solutus</i>	SOFT RUSH	5
<i>Eutrochium maculatum var. maculatum</i>	SPOTTED JOE PYE WEED	2
<i>Mimulus ringens</i>	MONKEY FLOWER	1
<i>Carex stipata</i>	STALK GRAIN SEDGE	2
<i>Glyceria grandis</i>	TALL MANNA GRASS	2
<i>Scirpus cyperinus</i>	WOOLGRASS	2
<i>Poa palustris</i>	FOWL BLUEGRASS	25

\*\*SOW AT 25KG/HA\*\*

CONSERVATION HALTON NURSE CROP MIX (FALL) - 6824mm²		
SCIENTIFIC NAME	COMMON NAME	% OF MIX
<i>Elymus canadensis</i>	CANADA WILD RYE	35
<i>Avena sativa</i>	ANNUAL OATS	25
<i>Agrostis stolonifera</i>	CREEPING BENT GRASS	20
<i>Festuca rubra</i>	RED FESCUE	20

\*\*WATERING MAY BE REQUIRED TO PROMOTE SUCCESSFUL ESTABLISHMENT\*\*  
OR JULY\*\*  
\*\*SOW AT 25KG/HA\*\*





**NOTE:**

- BAT BOX: PLACE ROCKET BAT BOX WITHIN 6m OF TREE LINE, BUT NOT UNDER TREE CANOPY.
- BRUSH PILES:
  - PLACE BRUSH PILES ABOVE 2YR FLOOD ELEVATION
  - NUMBER OF BRUSH PILES TO BE CONFIRMED ON SITE FOLLOWING A REVIEW OF AVAILABLE MATERIALS FOLLOWING TREE REMOVALS.
  - POTTED VINES AND GROUND COVER TO BE PLANTED IN AND AROUND PILES TO STABILIZE THE PILES.

**LEGEND**

**EXISTING**

- CHANNEL CENTRELINE
- PROPERTY LIMIT
- EX. CONTOURS
- BOTTOM OF BANK
- TOP OF BANK
- WATER LINE
- EX. RIFFLE ROCK
- EX. TREE
- TREE/BRUSH LINE
- TREE REMOVAL
- IDENTIFIED BAT TREES

**PROPOSED**

- PR. CONTOURS
- ARMOUR STONE
- BRUSH LAYER
- WRAPPED SOIL/ROCK TREATMENT
- PR. ROCK
- LOG
- PR. 2YR FLOODLINE
- BRUSH PILE
- BAT BOX

NO.	DATE	DESCRIPTION	APPD.
2.	2022/05/11	ISSUED FOR APPROVAL	MP
1.	2022/01/25	ISSUED FOR APPROVAL	MP



**EROSION CONTROL MITIGATION GRINDSTONE CREEK**  
UNSWORTH AVE TO SUMACH DR

**HABITAT STRUCTURES PLAN AND DETAILS**



DRN: KV	DSN: MP	CHK/APP: MP
DATE: 2022/05/11	DRAWING NUMBER	
SCALE: 1:250	C401	
PRO. No: 2116		

