LANDTEK LIMITED
Consulting Engineers
205 Nebo Road, Unit 3
Hamilton, Ontario
Canada
L8W 2E1
Phone: 905-383-3733
Fax: 905-383-8433
engineering@landteklimited.com
www.landteklimited.com

Geotechnical Investigation
Proposed Mixed-use Development
Phase 3- Lot C

747 and 761 Brant Street
Burlington, Ontario
L7R 2H6 and L7R 2H7

Prepared for:

Brant Street Joint Venture
% Molinaro Group
472 Brock Avenue, Unit 103
Burlington, Ontario
L7S 1N1

Landtek File: 20253-C
May 28, 2021

EXECUTIVE SUMMARY

SCOPE OF SERVICES

Proposed Development	Brant Street Joint Venture is intending to develop the site identified as civic addresses 747 and 761 Brant Street in Burlington, Ontario for a primarily residential and limited commercial use. Based on the Proposed Site Plan provided to Landtek, as developed by Graziani + Corazza Architects Inc., the proposed structure is to comprise of an 8-storey tower with a surrounding three to seven storey podium. The structure will include a maximum of two levels of basement parking. The footprint of the proposed structure is to cover the full site area.
Report Deliverables	The Geotechnical Investigation is required to determine the subsurface conditions underlying the site and to provide design and construction recommendations for the proposed new mixed-use development.

SITE DETAILS AND SETTING

Coordinates	596634, 4798498	**Site Area (approx.)**	3,831 m^2 (0.95 acres)
Site Description	The site is situated in a developed predominantly mixed commercial and residential area and is bounded by Ghent Avenue to the northwest and Brant Street to the southwest. Residential and commercial premises bound the site to the northeast and southeast respectively. The site is currently the location of a three-storey apartment brick building and a two-storey building. The remainder of the site is covered by an asphalt paved parking lot and access route and maintained landscaped areas.		
Geology	Topsoil and asphalt were encountered at the ground level. Underlying the surface material is fill material. The fill extends to depths of approximately 3.0 m below existing ground level. Underlying the fill is clayey silt till and red shale. Red shale bedrock was encountered underlying the till.		
Groundwater	During drilling, groundwater was not encountered, with all the boreholes remaining open and dry to the maximum auger drilled depth of approximately 7.6 m below existing ground level. Groundwater conditions at depth and within the shale bedrock, as screened by the monitoring wells, indicate piezometric water levels of between approximately 1.95 m and 3.15 m depth below ground level.		

ENGINEERING CONSIDERATIONS

Foundations	It is assumed that the proposed structure will include a maximum of two levels of basement. Based on the ground conditions observed at the borehole locations, it is considered by Landtek that bearing conditions to support the proposed residential development, or elements thereof, on concrete footings can be provided by the shale bedrock underlying the site.
Settlements	The SLS condition will not govern foundation design in bedrock as the stress required to induce the typical 25 mm settlement criteria at the SLS is anticipated to exceed the ULS. As such. settlements for foundations seated within bedrock are to be deemed negligible (i.e. less than 15 mm).
Earthquake Considerations	Based on the soil conditions encountered, and in accordance with Table 4.1.8.4.A. of the current Ontario Building Code (herein "*OBC*"), the site is considered to be a 'C' Site Class.

CONSTRUCTION CONSIDERATIONS

Excavations	The native soils to be encountered during excavation at the site are expected, in general, to behave as *"Type 2" and "Type 3"* materials according to the OHSA classification in Part III. Type 2 materials are characteristic of the generally very stiff clayey silt till deposits. The fill material encountered on site is considered Type 3 soil. The "*shale bedrock*" encountered at depth has strength properties that exceed a Type 1 soil.
Subsurface Concrete	The native soils generally have a mild sulphate environment and a low chloride concentration. For parking garage decks and ramps, a C-1 exposure class is recommended.
Dewatering	Considerations for groundwater control during construction have been provided under separate cover.

TABLE OF CONTENTS

SECTION PAGE(S)

1.0 INTRODUCTION 1

2.0 SITE SETTING 2
2.1 Site Location and Description 2
2.2 Published Geology 2

3.0 FIELDWORK AND INVESTIGATION METHODOLOGY 4

4.0 SUBSURFACE CONDITIONS 5
4.1 Overview 5
4.2 Existing Pavement Structure 5
4.3 Organic Soil/Topsoil 5
4.4 Fill Material 5
4.5 Clayey Silt Till 5
4.6 Bedrock 6
4.7 Groundwater 6

5.0 FOUNDATION DESIGN CONSIDERATIONS 8
5.1 Shallow Foundations on Bedrock 8
5.2 Frost Susceptibility 9
5.3 Settlement Considerations 9
5.4 Seismic Design Considerations 9
5.6 Existing Buildings Demolition 9
5.7 Damp Proofing and Waterproofing Considerations 10

6.0 FLOOR SLAB AND PERIMETER DRAINAGE CONSIDERATIONS 11

7.0 EARTH PRESSURE CONSIDERATIONS ON SUBSURFACE WALLS 12

8.0 SOIL CORROSIVITY AND SUBSURFACE CONCRETE 14
8.1 Soil Corrosivity 14
8.2 Concrete Class Considerations 14
8.3 Methods for Specifying Concrete 15

9.0 EXCAVATION AND BACKFILL CONSIDERATIONS 16
9.1 General Excavation Considerations 16
9.2 Construction Dewatering Considerations 17
9.3 General Backfill Considerations 17
9.4 Bedrock Considerations 18

10.0 TEMPRARY SHORING CONSIDERATIONS 19

11.0 SITE SERVICING CONSIDERATIONS 20

12.0 SOIL MANAGEMENT CONSIDERATIONS 21

13.0 PAVEMENT CONSIDERATIONS 22
13.1 Road Widening along Brant Street 22
13.2 Subgrade Preparation and Drainage 21
13.3 Pavement Construction Considerations 23
13.4 Deck Pavement Design Considerations 23

14.0 CLOSURE 25

TABLE OF CONTENTS

SECTION PAGE(S)

TABLES

Table 4.1.1 Summary of Boreholes Conditions Encountered 5
Table 4.7.1 Summary of Water Level Measurements 6
Table 5.1.1 Recommended Limit State Foundation Design Values..... 8
Table 8.1.1 Results of Soil Corrosivity Potential..... 14
Table 13.1.1 Recommended Pavement Structure for Brant Street Widening..... 22

FIGURES

Figure 2.1.1 Area of Proposed Redevelopment 2
Figure 9.1.1 Criteria for Assessing Excavation Shoring Requirements..... 17

APPENDICES

Appendix A Limitations of Report
Appendix B Symbols and Terms Used in the Report
Classification of Soils for Engineering Purposes
Appendix C Drawing 20253C-01 - Borehole Location Plan
Borehole Logs
Appendix D Drawing 20253C-02 - Engineering Commentaries – General Requirements for Drainage to Basement Structures
Drawing 20253C-03 - Engineering Commentaries – General Requirements for Underfloor Drainage Systems
Appendix E Chemical Laboratory Testing Results
Appendix F Rock Core Testing Results

1.0 INTRODUCTION

Landtek Limited (herein "*Landtek*") is pleased to submit this geotechnical investigation report for the proposed mixed-use development at the site identified as civic addresses 747 and 761 Brant Street in Burlington, Ontario. Authorization to proceed with the work was received from Mr. Sam DiSanto on behalf of Brant Street Joint Venture on August 11th, 2020. The scope of services undertaken for this geotechnical investigation was completed in accordance with proposal reference P20159R, dated May 22nd, 2020.

Brant Street Joint Venture is intending to develop the site for a primarily residential and limited commercial use. Based on the Preliminary Site Plan provided to Landtek, as developed by Graziani + Corazza Architects Inc. (herein "*Graziani + Corazza*"), the proposed development is to comprise the following:

- An eight-storey tower with a surrounding three to seven storey podium;
- A 90 m^2 privately owned public space (POPS) located at the northwest section of the site;
- An access and egress route from Ghent Avenue leading into the proposed underground parking levels; and,
- Road widening along Brant Street.

The development is to include two levels of underground parking, the structural footprint of which is expected to cover the full site area. It is assumed that no significant grade changes are proposed and that the proposed development will also include full site servicing.

The primary objectives of this investigation are:

- To confirm the subsurface soil and groundwater conditions for foundation design and construction;
- Provide design and construction recommendations with regards to building foundations, floor slabs, pavement structures, and subsurface drainage and utilities; and,
- Assess the characteristics of the soils to be excavated and their suitability for reuse on site.

This report has been prepared for the Client, the nominated engineers, designers, and project managers pertaining to the proposed mixed-use development at the site identified as civic addresses 747 and 761 Brant Street in Burlington, Ontario. Further dissemination of this report is not permitted without Landtek's prior written approval. Further details of the limitations of this report are presented in Appendix A.

2.0 SITE SETTING

2.1 Site Location and Description

The site is located in Burlington, Ontario, and is centered at approximate grid reference 596634, 4798498 (UTM 17T coordinates). The approximate Geodetic elevation of the ground surface at the borehole locations ranges between 91.1 m and 91.3 m.

The site location is shown in Figure 2.1.1 below.



Figure 2.1.1: Area of Proposed Redevelopment

The site, identified as "Parcel C" of the Brant+Ghent development area, is approximately 3831 m^2 (0.95 acres) in plan area. It is situated in a developed predominantly mixed commercial and residential area and is bounded by Ghent Avenue to the northwest and Brant Street to the southwest. Residential and commercial premises bound the site to the northeast and southeast respectively.

The site is currently the location of a three-storey apartment brick building and a two-storey building. The remainder of the site is covered by an asphalt paved parking lot and access route and maintained landscaped areas.

2.2 Published Geology

Based on previous geotechnical experience for the area and a review of the existing geological publications for the site area, Ontario Geological Survey (OGS) Map 2509: "*Quaternary Geology*

of the Hamilton Area", the native subsurface soil conditions in the area of the site are anticipated to consist of lacustrine and outwash sand overlying glacial till deposits of the Halton Till.

According to the OGS Map M2336 "*Paleozoic Geology of the Hamilton Area*", the superficial geology is underlain by red shale bedrock of the Queenston Formation. Based on the information provided by the OGS Map M2034 "*Bedrock Topography of the Hamilton Area*", bedrock is inferred to underly the site at a depth of approximately 4 m to 6 m below ground level.

Information provided by historical borehole records in the vicinity of the site, and held by the OGS, generally confirms the anticipated geological conditions beneath the site. Based on the data from records for Borehole ID 621028, located northwest of the site, the superficial soil profile confirms the presence of silt, sand and clay deposits to a depth of approximately 3.4 m. The bedrock in the area is red shale of the Queenston Formation and is identified as being at depths in the order of 3.4 m to 4.1 m below existing ground level.

3.0 FIELDWORK AND INVESTIGATION METHODOLOGY

Fieldwork undertaken by Landtek at the site, identified as "*Parcel C*" of the wider Brant+Ghent development area included clearance of underground services, borehole layout, borehole drilling and soil sampling, and field supervision. The geotechnical investigation was undertaken in conjunction with a hydrogeological investigation being conducted by Landtek for the site. Three boreholes (boreholes BH9, BH10, and BH11) were drilled at "*Parcel C*" on August 31st, 2020. The boreholes were logged using those standard symbols and terms defined in Appendix B. The Borehole Location Plan, Drawing 20253C-01, and associated borehole logs are provided in Appendix C.

The boreholes were drilled using a CME-75 track-mounted drilling rig equipped with continuous flight solid and hollow stem augers and were advanced to practical auger refusal on bedrock at depths of between approximately 6.0 m and 7.6 m below existing ground level. Standard Penetration Tests (SPT's) and split spoon samples were taken during drilling at selected depths. Boreholes BH9 and BH11 were then extended into the bedrock using air rotary and rotary HQ coring methodology respectively to depths of approximately 9.3 m below existing ground level. Full time supervision of drilling and coring operations was carried out by a representative of Landtek.

Boreholes BH9 and BH11 were completed as monitoring wells to monitor groundwater levels along the proposed anticipated lowest basement excavation and were renamed BH/MW9 and BH/MW11 respectively. The monitoring well consisted of new 50 mm poly-vinyl chloride (PVC) screen with No.10 slots threaded onto a matching riser. The screens and risers were pre-threaded including o-ring seals such that no glues or solvents were used to connect the pipe sections. The annular space between the PVC well and the borehole was backfilled to approximately 0.3 m above the top of the screen section with sand pack, and then with bentonite to existing ground level. A J-Plug lockable air-tight cap was installed on the riser. The borehole logs in Appendix C present the monitoring well installation details and the results of the subsequent groundwater level monitoring visit completed on September 24, 2020.

All soil samples were transported to the Landtek's in-house, Canadian Council of Independent Laboratories (CCIL) certified laboratory and visually examined to determine their textural classification. Moisture content testing was carried out on all samples. Selected, composite samples were submitted to AGAT Laboratories Ltd. (herein *"AGAT*") to be analyzed for soil corrosivity to assist with any protective requirements for buried concrete and metal infrastructure.

The rock cores collected were examined to determine their rock classification. Selected rock core samples were subsequently submitted to Geomechanica Inc. (herein "*Geomechanica*") for Unconfined Compressive Strength (UCS) testing. The results of the rock core testing are presented in Appendix F to this report.

Borehole locations were established by Landtek using measurements and offsets relative to existing, permanent site structures and centreline chainages. Approximate ground surface Geodetic elevations at the borehole locations were established by Landtek in reference to the topographical survey for the site, as completed by A.T. McLaren Limited and dated February 12, 2016.

4.0 SUBSURFACE CONDITIONS

4.1 Overview

The borehole information is generally consistent with the geological data identified in Sections 2.2, with the native soils comprising of a veneer of clayey silt till. Red shale bedrock was encountered underlying the till deposits.

The detailed borehole logs are presented in Appendix C, with the subsurface conditions encountered summarized in the following Table 4.1.1. Subsurface conditions encountered by the boreholes are discussed further in the sections following.

Table 4.1.1: Summary of Borehole Conditions Encountered

BH ID	Surface Material (mm)			Superficial Soils Depth (m) and (Description)		Bedrock Contact
	Asphalt	Granular	Topsoil	Fill	Native Soil	
BH/MW9	±50	±200	-	0.3 – 3.0 (clayey silt)	3.0 – 3.5 (clayey silt till)	3.5 m
BH10	-	-	50	0.1 – 3.0 (clayey silt)	-	3.0 m
BH/MW11	±50	±100	-	0.2 – 3.0 (clayey silt)	-	3.0 m

4.2 Existing Pavement Structure

Boreholes BH9 and BH11 were drilled in the existing asphalt pavement areas at the site, with asphalt thicknesses of approximately 50 mm. Pavement granular material was encountered underlying the asphalt and consists of approximately 100 mm to 200 mm of crushed limestone (gravel sizes).

4.3 Organic Soil/Topsoil

An approximately 50 mm thick layer of organic soil was encountered from ground surface in borehole BH10. The organic soil thicknesses may vary across the site, and the thickness measured at the borehole location may not be representative of the topsoil depth throughout the site.

4.4 Fill Material

Fill material was encountered in all boreholes underlying the topsoil/organic soil and pavement granular material and extends to depths of approximately 3.0 m below existing ground level. The fill material generally comprised of clayey silt. The fill material also includes trace fractions of gravel.

SPT ‘‘N’’ values ranging from 3 to 23 were reported within the fill materials, indicating their compactness condition to be variable from poor to well, but generally poorly compacted.

4.5 Clayey Silt Till

Clayey silt till was encountered in borehole BH9 underlying the fill material at a depth of approximately 3.0 m and extends to a depth of 3.5 m below existing ground level. The till contains

traces of gravel and red shale and is brownish grey in colour. The till is of a generally very stiff consistency.

4.6 Bedrock

Red shale of the Queenston Formation was encountered in all boreholes underlying the till and fill material at depths of approximately 3.0 m below existing ground level. The shale is generally weak and highly weathered on initial contact, being recovered and behaving as a "*residual soil*" to a depth of approximately 7.6 m. Below this depth the shale becomes more competent.

Strength testing performed on intact rock core specimens indicate rock strength of the competent shale in the order of 27.3 MPa to 39.5 MPa, indicating that the bedrock can be classified as having a strength grade of R3, and being "*medium strong*" according to the Canadian Foundation Engineering Manual. Though not encountered during this investigation, it should be noted that the layered nature of the shale bedrock is such that it may contain discontinuous green and red siltstone and occasional limestone seams that tend to be much sounder and harder than the shale strata.

The Rock Quality Designation (RQD) values of the competent shale bedrock were in the order of 83 % to 100 % indicating the bedrock to be of "*good to excellent*" quality at depth.

4.7 Groundwater

During drilling, groundwater was not encountered, with all the boreholes remaining open and dry to the maximum auger drilled depth of approximately 7.6 m below existing ground level.

On completion of drilling, boreholes BH9 and BH11 were converted to monitoring wells identified as MW9 and MW11 respectively. Water level readings recorded in the monitoring wells on September 24, 2020 are summarized in Table 4.7.1.

Table 4.7.1: Summary of Water Level Measurements

BH ID	Northing	Easting	Ground Elevation	Water Strike Depth[1] (mbgl[2])	Well Screen Depth (mbgl[2])	Measured Water Level (m)		
						Depth	Elevation	Date
BH/MW9	4798530	596633	91.3 m	-	6.1 - 9.1	3.15	88.15	Sept. 24, 2020
BH10	4798500	596628	91.3 m	-	NA	-	-	-
BH/MW11	4798494	596662	91.1 m	-	6.3 - 9.3	1.95	89.18	Sept. 24, 2020

1. Water strike depths were reported to the maximum drill depth of 7.6 m achieved using auger drilling methodologies only. They do not include the deeper drill depths into bedrock achieved using follow-on air rotary and rotary HQ coring methodologies.
2. Meters below ground level

Groundwater conditions at depth and within the shale bedrock, as screened by monitoring wells BH/MW9 and BH/MW11, indicate piezometric water levels of between approximately 1.95 m and 3.15 m depth below ground level.

It should be noted that groundwater conditions and surface water flow conditions are expected to vary according to the time of the year and seasonal precipitation levels. Water seepage is also expected from soil fissures above the water table.

5.0 FOUNDATION DESIGN CONSIDERATIONS

5.1 Shallow Foundations on Bedrock

Based on the ground conditions observed at the borehole locations, it is considered by Landtek that bearing conditions to support the proposed development, or elements thereof, on concrete footings can be provided by the shale bedrock underlying the site. It is understood that all elements of the proposed development will include a maximum of two levels of basement. On this basis, it is anticipated that foundations for a structure with two levels of basement will be seated at depths between approximately 6.0 m and 7.0 m below existing ground level, equating to Geodetic elevations of between approximately 85.1 m and 84.1 m.

Table 5.1.1 summarizes the recommended geotechnical reactions at the Serviceability Limit State (herein "*SLS*") and factored geotechnical resistances at the Ultimate Limit State (herein "*ULS*") for the weathered shale. Where foundations are seated in competent bedrock, the SLS State condition will not govern their design as the stress required to induce the typical 25 mm settlement criteria at the SLS is anticipated to exceed the ULS. It should be noted that the design parameters have been determined by Landtek for the design stage only.

In accordance with the Ontario Building Code (herein "*OBC*"), 9.12.2.2 (5), and based on local experience, the shallowing of exterior and interior footings to 0.9 m and 0.6 m depth below the basement finished floor level respectively, may be adopted for the proposed development. Such shallowing of foundations is to be limited to only those areas where a minimum of one basement level is to be included.

Where the bearing levels of the footings are at different design elevations, the footing base levels should be stepped along a line of 7V:10H, drawn upwards from the lowest footing, to avoid overlapping stresses.

Subsurface conditions can vary over relatively short distances and the subsurface conditions revealed at the test locations may not be representative of subsurface conditions across the site. Therefore, a Geotechnical Engineer should be engaged during construction to examine the exposed sub-soil and bedrock quality and condition, and confirm the subsurface conditions are consistent with design assumptions. This is in compliance with field review requirements in the National Building Code, Volume 1, Clause 4.2.2.3.

Table 5.1.1: Recommended Limit State Foundation Design Values

Founding Elevation Range		Founding Stratum	Foundation Design Value	
Depth	Approx. Elevation [5]		SLS [1 2]	ULS [3 4]
6.0± m to 7.6± m	85.1 m to 83.5 m	Bedrock (Weathered Shale)	600 kPa	900 kPa
7.6± m to 8.5± m	83.5 m to 82.6 m	Bedrock (Competent Shale)	-	2 MPa

Notes:
1. The National Building Code general safety criterion for the serviceability limit states is: SLS resistance ≥ effect of service loads.
2. Recommended SLS bearing values conform to Estimated Values based on soil types given in Tables K-8 and K-9 of the National Building Codes User's Guide.
3. The ULS resistance factor for shallow foundations is 0.5, as given in Table K-1 of the National Building Code User's Guide.
4. The National Building Code general safety criterion for the ultimate limit states is: factored ULS resistance ≥ effect of factored loads.
5. Geodetic elevations based on Topographic Survey Plan "*Drawing No. 34885-2"* prepared by A.T. McLaren Limited and dated February 12, 2016.

5.2 Frost Susceptibility

The silt and clay soils encountered at shallow depths across the site are considered sensitive to water and frost, and their physical and mechanical properties are dependent on in-situ moisture content. As such, the subsurface soils at the site are considered to have a moderate to high frost susceptibility, being classified as Frost Group "*F4*" (Table 13.1 of the "*Canadian Foundation Engineering Manual*", 4th Edition). However, the identified depths for foundations, as given in Section 5.1 are considered to be below the maximum extents of influence from frost penetration in the Burlington area.

Should any re-grading be required as part of the proposed development and adjacent to the new structures, it will be important to ensure that the associated exterior footings will have a minimum of 1.2 m of soil cover, or equivalent suitable insulation, for frost protection.

Concerns regarding frost protection to footings are more directed towards those seated within soils. Foundations in the shale bedrock are generally deemed exempt from any frost protection requirements. This given however, consideration should be given to the use of non-frost susceptible materials as backfill for foundation wall excavations and the installation of foundation drainage in order to minimize the risk of adfreezing.

5.3 Settlement Considerations

Based on the outline information provided for the nature of the proposed development of the site, it is anticipated that the loads to be applied to the ground by any such structure will be generally moderate intensity. As such, associated settlements are not expected to be large. Therefore, the general limiting of the total settlement to 25 mm and the differential settlement to 19 mm by the recommended geotechnical reaction at the SLS is considered appropriate.

The SLS condition will not govern foundation design in bedrock as the stress required to induce the typical 25 mm settlement criteria at the SLS is anticipated to exceed the ULS. As such. settlements for foundations seated within bedrock are to be deemed negligible (i.e. less than 15 mm).

5.4 Seismic Design Considerations

Based on the soil conditions encountered, and in accordance with Table 4.1.8.4.A. of the current Ontario Building Code (herein "*OBC*"), the site is considered to be a 'C' Site Class. The acceleration and velocity-based site coefficients, F_a and F_v, should be determined from Tables 4.1.8.4.B. and 4.1.8.4.C. respectively of the OBC for the above recommended Site Class. The seismic design data given in Table 1.2 of Supplementary Standard SB-1 in Volume 2 of the OBC, for selected Municipal locations, should be used to complete the seismic analysis.

5.6 Existing Buildings Demolition

It is understood that the existing buildings located on site will be demolished prior to the proposed development. For the purposes of this report, it has been assumed that the existing structures and all associated substructures will be removed in full prior to development.

Should there be a need to fill excavations created by the demolition of the existing structure with engineered fill or unshrinkable backfill prior to commencing the proposed development, Landtek should be contacted to determine the most appropriate placement requirements of the fill material.

5.7 Damp Proofing and Waterproofing Considerations

Based on the anticipated maximum two levels of basement parking, groundwater strike information and the groundwater levels recorded during this investigation, it is expected that limited, local groundwater seepage will be encountered within the excavation footprint of the proposed basement levels.

On this basis, it is considered that the subsurface walls of the basement areas should be damp proofed and should comply with OBC requirements. It is recommended that the damp proofing system include a Delta Drainage Board or MiraDrain 2000 series product, or an approved alternative, along with an asphalt-based spray-on wall coating. A long-term dewatering system (i.e. sump pumps etc.) will be required, and the anticipated volumes and pumping rates for such permanent, post-construction dewatering systems are provided by Landtek's Hydrogeological Investigation report for the site.

For any structures that are to extend below the proposed founding elevation (i.e. elevator shafts etc.) it is recommended that they be appropriately waterproofed from their base up to the underside of the proposed floor slab. Any construction joints between such structures and the proposed floor slab should be also waterproofed.

6.0 FLOOR SLAB AND PERIMETER DRAINAGE CONSIDERATIONS

Based on the borehole soil conditions and preliminary design information provided to Landtek, it should be possible to construct the lowest (i.e. basement) floor slab level using slab-on-grade methods. The subgrade support condition is anticipated to be shale bedrock, which should provide competent conditions for placing the vapour barrier material. However, after the subgrade has been prepared to the underfloor design elevation it is recommended that the area be assessed by Landtek to determine if there is a need for any remedial work.

It is recommended that a minimum 200 mm layer of clear, 19 mm crushed quarried stone be used as the vapour barrier under the floor slab. The vapour barrier stone should meet the requirements of Ontario Provincial Standard Specifications (herein "*OPSS*") 1004 for 19 mm Type II clear stone. If a graded crushed stone is substituted for clear stone, the material should be limited to a maximum of 5 % fines (passing the 0.075 mm sieve). The floor slab thickness should meet the specifications of the project based on anticipated floor loadings.

The finished exterior ground surface should be sloped away from the buildings at a grade in the order of 2 %.

The concrete properties should meet the requirements of OPSS 1350. Contraction and isolation jointing practices should be in accordance with current Portland Cement Association recommendations, as given in the engineering bulletin "*Concrete Floors on Ground*", second edition, by R. E. Spears, and W. C. Panarese.

The design of concrete slabs may be made on the basis of a value of modulus of subgrade reaction of 200 MPa/m for the shale bedrock.

Perimeter drainage should be provided around all subsurface floor areas where water may accumulate. Underfloor drains may be required depending on excavation and groundwater seepage conditions. It is anticipated that, based on the assumed maximum of two levels of basement, limited groundwater seepage should be anticipated during periods of wet weather. This given, it is recommended that underfloor drains be provided at all deep foundation locations. The drainage system should comply with the OBC and associated amendments. Further details pertaining to perimeter and underfloor drainage systems are provided in Drawings 20253C-02 and 20253C-03 respectively, in Appendix D.

After the subgrade has been prepared to the underfloor design elevation it is recommended that the area be proof-rolled with a loaded tandem axle dump truck to delineate if there are soft or unstable ground conditions that require repair. This operation should be completed before the underfloor vapour barrier granular material is placed.

7.0 EARTH PRESSURE CONSIDERATIONS ON SUBSURFACE WALLS

The earth pressure, p, acting on subsurface walls at any depth, h, in metres below the ground surface assumes an equivalent triangular fluid pressure distribution and may be calculated using the expression below. It is assumed that granular material is used as backfill. Allowances for pressure due to compaction operations should be included in the earth pressure determinations and a value of 12 kPa is applicable for a vibratory compactor and granular material.

If the structure retaining soil can move slightly, the active earth pressure case can be used in determining the lateral earth pressure. For restrained structures and no yielding an "at rest" earth pressure condition should be used. The determination of the earth pressures should be based on the following expression:

$$P_1 = K (\delta h + q)$$

where:

P_1 = the pressure in kPa acting against any subsurface wall at depth, h, in metres (feet) below the ground surface;

K = the at rest earth pressure coefficient considered appropriate for subsurface walls; OPSS 1010 Granular B Type 1 (pit-run sand and gravel) material has an effective angle of friction estimated to be 32° with a corresponding at rest earth pressure coefficient, K_o, of 0.45; and,

δ = the moist bulk unit weight of the retained backfill; 21.5 kN/m^3.

and,

q = the value for any adjacent surcharge in kPa, which may be acting close to the wall; and,

h = the depth, in m, at which the pressure is calculated

Granular B backfill should meet OPSS 1010 Type I or Type II material specifications. The granular fill should be compacted to a minimum of 97 % of the material's Standard Proctor Maximum Dry Density (herein "*SPMDD*"), or to the levels and backfilling procedures specified.

Given the presence of shale bedrock beneath the site, the following parameters should be applied for the bedrock when considering lateral pressures on subsurface walls:

- Internal angle of friction (ϕ) should be taken as 28°; and,
- Bulk unit weight (γ) should be taken as 25.5 kN/m^3.

In designing a subsurface wall within bedrock, a uniform pressure distribution is assumed and is consistent with the maximum earth pressure calculated for the wall where in soil. However, below the weathered bedrock zone, the design does not accommodate for lateral rock swell.

Lateral rock swell will be of concern as fresh bedrock will be exposed in the excavation faces and will be more prone to swell than the shallower, more weathered bedrock zone. No real rate of swell can be put on the bedrock as it is very variable.

There are various approaches to overcome rock swell in design and excavation. There is a generally accepted industry practice which assumes that bedrock exposed for a period of more than 120 days will have swelled such that no significant stresses will be exerted upon foundation walls. Alternatively, a number of methods of mitigation are generally accepted to include:

- The limiting of bedrock exposure to no more than 7 days;
- The application of a mud-mat/shotcrete onto the exposed rock face once excavated;
- The installation of a layer of compressible fill material (e.g. Ethafoam Plank products) between the rock face and the back of the structural wall; and/or,
- The over-excavation of the bedrock ±0.6 m and backfilling the void space with 19 mm Clear Stone.

It should be noted that the variability of the Queenston Formation shales means that, without site-specific testing, no definitive time at which point the swell becomes negligible can be assigned.

8.0 SOIL CORROSIVITY AND SUBSURFACE CONCRETE

8.1 Soil Corrosivity

One selected soil sample was submitted to AGAT for analysis of PH, soil conductivity and redox potential, and concentrations of sulphides, sulphates, and chlorides.

The American Water Works Association (AWWA) document, "*Polyethylene Encasement for Ductile-Iron Pipe Systems*" *ANSI/AWWA C105/A21.5-18,* dated December 1, 2018, uses a 10-point scoring method to determine the soil corrosivity potential. For each given soil sample, points were assigned to the different parameters to evaluate their contribution towards the corrosivity of soil. The test results are provided in Appendix E and are summarized in Table 8.1.1.

Table 8.1.1: Results of Soil Corrosivity Potential

Sample ID	Composite Sample Depth	Parameters Analysed	Measured Value	ANSI/AWWA Point Rating	Total ANSI/AWWA Points
BH10-SS5 and SS6	4.5 – 6.0 (m)	Sulphide (%)	<0.05	0	7
		pH (pH units)	8.75	3	
		Resistivity (ohm.cm)	2440	2	
		Redox Potential (mV)	166	0	
		Moisture (%)	8.0	2	

Corrosion protection for buried metallic improvements or steel is recommended, when a score of 10 points or greater is reported. Based on the ANSI/AWWA value of 7 for the overburden soils obtained from borehole BH10, it is considered that the soils at the site have no corrosion potential. It should be noted that the analytical results only provide an indication of the potential for corrosion.

The contribution of chloride ions to soil corrosivity towards buried metallic improvements or steel structures is very significant. According to the Corrosion Guidelines (Caltrans, January 2015, version 2.1), a site is considered corrosive if, "*chloride concentration is 500 ppm or greater, sulphate concentration is 2000 ppm or greater, or the pH is 5.5 or less*. "

In addition, the Canadian Standards Association (CSA) A23.1-14 "*Concrete materials and methods of concrete construction*", Table 3, "*Additional requirements for concrete subjected to sulphate attack*", states that design requirements for sulphate resistant concrete are only necessary when the water soluble sulphate content of the soil in which the concrete is to be embedded is greater than 0.1 % (1,000 µg/g).

The representative soil samples at the site are reported to contain sulphate and chloride ion concentrations of 163 µg/g (ppm) and 32 µg/g (ppm) respectively. This given, the test results indicate a negligible degree of sulphate and chloride attack on buried reinforced concrete structures.

8.2 Concrete Class Considerations

The requirements for subsurface concrete subject to a sulphate and chloride environment are presented in Canadian Standards Association specification, CSA A23.1-14 *"Concrete Materials*

and Methods of Concrete Construction, Tables 1-4".

Given the mild sulphate and low chloride test results, normal General use (GU) hydraulic cement can be used for the below grade concrete structures. However, it is recommended that the concrete exposure class for the parking garage decks and ramps be C-1 and the concrete have the following minimum properties:

- minimum 56-day compressive strength: 35 MPa;
- maximum water to cement ratio: 0.40;
- chloride ion penetrability requirement: < 1500 coulombs (within 91 days)
- cementing materials: GU (general use hydraulic cement) or GUb (blended general use)
- air content: as per CSA A23.1-14 Table 4, air content category 1 (freeze-thaw environment)

The concrete should be placed without segregation and should be consolidated to achieve a uniform dense mass.

8.3 Methods for Specifying Concrete

Alternative methods of specifying concrete for a project are outlined in CSA A23.1-14 and allow for "*Performance*" or "*Prescription*" based methods. Each method attaches different levels of responsibility to the owner, the contractor, and the concrete supplier. The pros and cons of each method should be examined prior to completion of the specifications for the project.

9.0 EXCAVATION AND BACKFILL CONSIDERATIONS

9.1 General Excavation Considerations

All temporary excavations and unbraced side slopes in the soils should conform to standards set out in the Occupational Health and Safety Act, Ontario Regulation 213/91 "*Construction Projects*" (herein "*OHSA*"). The subsurface soils to be encountered during excavation at the site are expected to behave as "*Type 3"* and "*Type 2*" materials according to the OHSA classification in Part III. Type 3 soils are characteristic of the "*fill material*" while the generally very stiff "*native clayey silt till"* is considered a Type 2 soil. The "*shale bedrock*" encountered at depth has strength properties that exceed a Type 1 soil.

It should be possible to excavate the overburden soils using a hydraulic backhoe. Moist Type 3 and Type 2 soils are expected to be stable for short construction periods at slopes of approximately 45° to the horizontal (i.e. 1V:1H).

A backhoe equipped with a hydraulic breaker and/or a bucket with rock-ripping 'tiger teeth' may be required in the shale strata and particularly where seams and bands of harder strata (such as siltstone or limestone) are encountered within the shale. Significant ground vibrations resulting from excavation works are not anticipated other than those associated with normal construction activities. The shale is expected to remain relatively stable at near vertical slopes for short periods of time. It is recommended that the shale excavation slopes be scaled of loose rock pieces and overhang and cut back to about 10V: 1H.

Consideration should be given to existing service trenches and backfill that may be present directly behind cut slopes within the native soils that may appear to be stable on first excavation. In these circumstances, slopes can suddenly slough or collapse due to the effects of the adjacent backfill. Consequently, for excavation conditions that cannot satisfy the OHSA requirements for unbraced 1H:1V side slopes, a trench box system should be used, or temporary shoring should be installed to maintain safe working conditions. This may be more applicable to service trench excavations, though may also apply to basement excavations etc., particularly where in close proximity to new road pavements or associated infrastructure.

It should be noted that the design of a temporary shoring system, should one be required, is the responsibility of the Contractor. Therefore, a specialist shoring contractor should be consulted to provide the most appropriate shoring type method and associated installation procedures. In any event, the shoring design should be based on the procedures outlined in the latest edition of the "*Canadian Foundation Engineering Manual*". It is also recommended that lateral and vertical movement of the shoring system be monitored during construction to ensure that movements are within the acceptable range.

Excavations for new foundations should satisfy the criteria given in the example shown in Figure 9.1.1 to avoid overlapping stresses and minimize the risk of undermining existing adjacent structures, including utilities, and/or triggering additional settlements of the existing structures due to soil disturbance.




Figure 9.1.1: Criteria for Assessing Excavation Shoring Requirements (Not to Scale)

9.2 Construction Dewatering Considerations

Considerations regarding groundwater control and dewatering requirements during construction have been provided under separate cover.

9.3 General Backfill Considerations

Backfill next to foundation walls and in service trenches should be selected to be compactable in narrow trench conditions. The on-site clayey silt till and weathered shale are expected to be reusable as trench backfill and backfill around the proposed structures on the site. Any variation in the moisture contents of the soils encountered may require selective separation of material to avoid the use of wet soil. Experience with shale indicates that long term settlements can occur unless quality control procedures are in place to ensure the shale particle sizes are broken down to minus 200 mm material, the moisture content of the material is maintained at near optimum levels, and the material is placed in maximum lift thicknesses of 300 mm.

Site servicing trench backfill should be uniformly compacted to a density that minimizes the risk of long-term settlements. It is recommended that the target compaction specification for trench backfill be 97 % SPMDD with no individual test below 95 % SPMDD.

During inclement weather the native soils may become too wet to achieve satisfactory compaction. If construction is proposed for late in the year, a reduced level of trench compaction with a higher risk of future settlements is to be anticipated, and it is recommended that provisional contract quantities be established for the supply and placement of imported granular fill under such circumstances. The imported granular should meet the requirements of OPSS 1010 for Granular B Type I material as a minimum requirement.

9.4 Bedrock Considerations

Competent shale of the Queenston Formation has the characteristics of becoming soft or degraded after excavation and subsequent exposure to the elements, the results of which would be basal heaving and compression from rock squeezing along excavation side walls. As such, these effects should be minimized during construction, and requires a well-planned construction program to ensure that the exposure of the shale bedrock is kept to a minimum, as identified in Section 7.0.

Methane gas is known to be present within the fracture networks of the Queenston Formation shale, normally below the top 1 m and becoming more concentrated with depth. As such, the potential could exist for the development of an explosive or oxygen-depleted air environment. Therefore, Landtek recommends that the appropriate air space monitoring is undertaken within all confined excavations, particularly those located close to or within bedrock, as defined by the OHSA.

10.0 TEMPORARY SHORING CONSIDERATIONS

The installation of temporary shoring is also recommended to maintain safe working conditions and eliminate the possibility of loss of ground and damage to nearby structures and buried utilities on the adjacent road allowances during excavation for the basement construction.

The requirement and application of shoring to support excavation side slopes will be dependent on the required excavation depth and the proximity of existing or newly constructed infrastructure adjacent to the excavation.

The preferred method of shoring will consist of a concrete caisson wall. This type of system is expected to provide the additional benefit of sealing the excavation from water penetration and loss of soil fines into the open excavation. Soldier piles and timber lagging may be considered as an option for a shoring system, though this type of system may require measures to prevent the loss of soil between the spaces of lagging boards where a wet or flowing soil layer may be present. Consideration may be also given to the application of shotcrete where groundwater is encountered and/or where Queenston Formation shale bedrock is exposed in the excavation faces.

The shoring methods may provide lateral restraining force through the use of rakers or tieback anchors. Tieback anchors provide additional advantage since they do not protrude into the excavations as rakers would. However, the use of tieback anchors is also dependent upon whether permission is needed or whether it is physically possible to extend the anchors to the required distance into neighbouring properties.

It should be noted that the design of any temporary shoring system is the responsibility of the Contractor. Therefore, a specialist shoring contractor should be consulted to provide the most appropriate shoring type method and associated installation procedures. In any event, the shoring design should be based on the procedures outlined in the latest edition of the Canadian Foundation Engineering Manual. It is also recommended that lateral and vertical movement of the shoring system be monitored during construction to ensure that movements are within the acceptable range.

11.0 SITE SERVICING CONSIDERATIONS

There is no indication that special pipe bedding materials or procedures are required for the installation of services. All bedding cover and backfill materials should be selected in accordance with OPSS 1010 Aggregates – Base, Subbase, Select Subgrade, and Backfill Material.

The pipes should be placed with a minimum bedding thickness in conformance of OPSD 802.010, 802.013 and 802.014 for flexible pipe and OPSD 802.030, 031, 032, 033 and 034 for rigid pipes. The type of bedding shall be selected to suit the applicable pipe strength and site conditions.

Bedding material shall be placed in layers not exceeding 300 mm in thickness, loose measurement, and compacted to 95 % of the SPMDD before a subsequent layer is placed. Site servicing trench backfill should be uniformly compacted to a density that minimizes the risk of long-term settlements. Bedding on each side of the pipe shall be completed simultaneously. At no time shall the levels on each side differ by more than the 300 mm uncompacted layer. The remainder of the trench should be backfilled as per the requirements defined in Section 9.0.

It is assumed all services will have a minimum of 1.2 m of soil cover for frost protection. For services installed at shallower depths, suitable insulation for frost protection is recommended.

12.0 SOIL MANAGEMENT CONSIDERATIONS

Construction for the proposed development may involve cut and fill operations. From a geotechnical perspective, and in order to optimize the use of the on-site soils, a Soil Management Plan should be established. The plan objective should be to achieve a self-sustainable development with respect to excavated materials and control the placement of organic soils so that there is negligible impact on the settlement performance of the compacted fill material.

The soil management criteria should be as follows:

- Surface vegetation, topsoil and organic soils should not be placed within the proposed roadways, below finished subgrade level for pavement construction or building limits. These materials should be placed in landscaped areas where settlements are not critical;

- Excavated soils for structural fill in pavement areas and building floor slab areas, which does not have topsoil or organic matter and are compactable with moisture contents within 2 % to 3 % of the optimum value, should be placed and compacted to a target density of 97 % of the SPMDD with no individual test result below 95 % SPMDD; if engineered fill is required to support building foundations, the engineered fill should be placed and compacted in lifts to a target density of 100 % SPMDD with no individual tests below 98 % SPMDD; the soil should be placed in a loose lift thickness not exceeding 250 mm and should be compacted using a large (10 ton or larger) pad-foot type roller with vibratory capability; if engineered fill to support building foundations is being considered it is recommended that a pre-construction meeting be scheduled to review the proposed fill materials, fill placement and compaction procedures, and the testing and inspection requirements;

- Soils to be placed in landscaped areas where settlements are not critical should receive nominal compaction effort in order to achieve at least 90 % of the SPMDD; and,

- Prior to the placement of underfloor granular fill, the exposed subgrade soil should be inspected and proof-rolled using a loaded tandem axle truck and traversing the exposed subgrade for full coverage; the proof-rolling should be monitored by a geotechnical representative of this office to delineate any soft areas which may require repair.

13.0 PAVEMENT CONSIDERATIONS

13.1 Road Widening along Brant Street

The proposed development includes road widening along Brant Street. Brant Street is classified by the Corporation of the City of Burlington (herein "*City of Burlington*") as a minor arterial road. The pavement structure should match the existing structure or alternatively be constructed as per the recommended pavement structure layer thicknesses provided in Table 13.1.1.

In the absence of anticipated traffic volumes or traffic loading requirements, the pavement structure thicknesses take into account the accepted design practice that the total pavement structure thickness should meet or exceed one-half the anticipated depth of frost penetration for the geographical area, or as close as practicable for the given purpose of the pavement. For the Burlington area, this is 1.2 m. Site specific development requirements set out by the City of Burlington may override the recommendations of this report.

Table 13.1.1: Recommended Pavement Structure for Brant Street Widening

Pavement Layer	Brant Street Widening/ Improvement (Minor Arterial Road)
Surface Course Asphalt OPSS HL3	50 mm
Binder Course Asphalt OPSS HL8	110 mm
Granular Base OPSS Granular A	150 mm
Granular Subbase OPSS Granular B, Type II	450 mm
Total Thickness	760 mm

Notes:
1. If construction proceeds late in the year (i.e. November and December), the design thickness of pavement granular materials may have to be increased to address potential problems with subgrade instability and facilitate construction vehicle and truck access.

13.2 Subgrade Preparation and Drainage

The overall performance of the pavement structure will greatly depend upon the support provided by the developed subgrade. A number of factors should be considered at the construction stages to ensure that an acceptable subgrade condition is developed and maintained:

- Sub-drains should be installed and should be 100 mm diameter perforated plastic pipe, with outfalls to catch basins at a continuous and uniform grade. The sub-drains should conform to OPSD 216.01;
- Any soft areas of notable deflection to the subgrade should be sub-excavated and replaced with a suitable backfill material approved by a qualified geotechnical engineer and compacted to 98 % of its SPMDD;
- The subgrade should be properly shaped, crowned and then proof-rolled under the full time observation of a geotechnical representative of this office to delineate any soft areas which may require repair before placing the granular materials; and,
- Surface water should not be allowed to pond on the surface of or adjacent to the outside edges of any developed subgrade.

It is important to ensure that any necessary repairs are undertaken to the subgrades prior to pavement construction to avoid creating "*bathtub*" conditions in the subgrade that will ultimately translate through the overlying pavement structure.

Any proposed subdrains and associated connections are to be installed in accordance with the City of Burlington's Standard Drawings.

13.3 Pavement Construction Considerations

The following considerations should be maintained during paving:

- The requirements defined by OPSS 310 and OPSS.PROV.313 for the design and construction of lap joints between and transitions from existing and new asphaltic concrete pavements when connecting the new pavement construction to the existing pavements of adjacent roads;
- A tack coat should be applied to all contact surfaces prior to placing any hot mix asphalt layers or between asphaltic layers as per OPSS 308; and,
- The placing, spreading and rolling of the asphalt should be in accordance with current provincial standards or the City of Burlington Engineering Standards.

Granular Base Course and Subbase

The granular base course materials should meet OPSS Granular "A" specifications. Quarried 20 mm limestone crushed to Granular "A" gradation specifications is recommended. If the option with granular subbase material is used, the granular subbase should meet OPSS Granular B Type II requirements for 100 % crushed quarried bedrock (50 mm crusher-run limestone).

Hot Mix Asphalt

The binder course and surface course asphalt should meet current specifications for HL8 and HL3 respectively, as prescribed by the City of Burlington or, alternatively, OPSS.MUNI 1150.

The standard asphalt binder grade for the climate conditions in the Burlington area is PG 58-28. Given the anticipated high volume of commercial truck traffic, a bump up to a higher PG grade of asphalt cement may be considered.

Compaction

Granular base course and subbase course fill material should be compacted to 100 % SPMDD. Hot mix asphalt should be compacted to the criteria set out by the City of Burlington.

13.4 Deck Pavement Design Considerations

It is understood that the footprint of the proposed development will cover the site area in full. As such, any pavement structures are anticipated to be deck structures rather than standalone pavement structures.

Such deck pavements should comprise a minimum 50 mm cover of OPSS HL 3 asphalt or minimum 80 mm cover of interlocking concrete pavers. The bedding or grading material to be placed between the concrete deck and the asphalt pavement surface or interlocking concrete

pavers should comprise either blinding sand or OPSS Granular A material, depending on the thickness of the layer required.

14.0 CLOSURE

The Limitations of Report, as stated in Appendix A, are an integral part of this report.

Soil samples will be retained and stored by Landtek for a period of three months after the report is issued. The samples will be disposed of at the end of the three-month period unless a written request from the client to extend the storage period is received.

We trust this report will be of assistance with the design and construction of the proposed development. Should you have any questions, please do not hesitate to contact our office.

Yours sincerely,

LANDTEK LIMITED

Isaac Asonya, B.S.Eng.
Author

James Dann, B.Eng. (Hons)
Manager, Geotechnical Projects

LICENSED PROFESSIONAL ENGINEER
R. DI CIENZO
PROVINCE OF ONTARIO

Ralph Di Cienzo, P. Eng.
Consulting Engineer

APPENDIX A
LIMITATIONS OF REPORT

The conclusions and recommendations given in this report are based on information determined at the borehole locations. Subsurface and ground water conditions between and beyond the Boreholes may be different from those encountered at the borehole locations, and conditions may become apparent during construction that could not be detected or anticipated at the time of the geotechnical investigation. It is recommended practice that Landtek be retained during construction to confirm that the subsurface conditions throughout the site are consistent with the conditions encountered in the Boreholes.


The comments made in this report on potential construction problems and possible remedial methods are intended only for the guidance of the designer. The number of Boreholes may not be sufficient to determine all the factors that may influence construction methods and costs. For example, the thickness and quality of surficial topsoil or fill layers may vary markedly and unpredictably. Additionally, bedrock contact depths throughout the site may vary significantly from what was encountered at the exact borehole locations. Contractors bidding on the project, or undertaking construction on the site should make their own interpretation of the factual borehole information, and establish their own conclusions as to how the subsurface conditions may affect their work.

The survey elevations in the report were obtained by Landtek Limited or others, and are strictly for use by Landtek in the preparation of the geotechnical report. The elevations should not be used by any other parties for any other purpose.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. Landtek Limited accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken based on this report.

This report does not reflect environmental issues or concerns related to the property unless otherwise stated in the report. The design recommendations given in the report are applicable only to the project described in the text and then only if constructed substantially in accordance with the details stated in this report. Since all details of the design may not be known, it is recommended that Landtek Limited be retained during the final design stage to verify that the design is consistent with the report recommendations, and that the assumptions made in the report are still valid.

APPENDIX B
SYMBOLS AND TERMS USED IN THE REPORT



RELATIVE PROPORTIONS

Term	Range
Trace	0 - 5%
A Little	5 – 15%
Some	15 – 30%
With	30 – 50%

CLASSIFICATION BY PARTICLE SIZE

Boulder ---------- > 200 mm
Cobble ---------- 80 mm – 200 mm
Gravel -
Coarse ---------- 19 mm – 80 mm
Fine ---------- 4.75 mm – 19 mm
Sand -
Coarse ---------- 4.75 mm – 2 mm
Medium -------- 2 mm – 0.425 mm
Fine ---------- 0.425 mm – 0.75 mm
Silt ---------- 0.075 mm – 0.002 mm
Clay ---------- < 0.002 mm

DENSITY OF NON-COHESIVE SOILS

Descriptive Term	Relative Density	Standard Penetration Test
Very Loose	0 – 15%	0 – 4 Blows Per 300 mm Penetration
Loose	15 – 35%	4 – 10 Blows Per 300 mm Penetration
Compact	35 – 65%	10 – 30 Blows Per 300 mm Penetration
Dense	65 – 85%	30 – 50 Blows Per 300 mm Penetration
Very Dense	85 – 100%	Over 50 Blows Per 300 mm Penetration


CONSISTENCY OF COHESIVE SOILS

Descriptive Term	Undrained Shear Strength kPa (psf)	N Value Standard Penetration Test	Remarks
Very Soft	< 12 (< 250)	< 2	Can penetrate with fist
Soft	12 – 25 (250 – 500)	2 – 4	Can indent with fist
Firm	25 – 50 (500 –1000)	4 – 8	Can penetrate with thumb
Stiff	50 – 100 (1000 – 2000)	8 – 15	Can indent with thumb
Very Stiff	100 – 200 (2000 – 4000)	15 – 30	Can indent with thumb-nail
Hard	> 200 (> 4000)	> 30	Can indent with thumb-nail

Notes: 1. Relative density determined by standard laboratory tests.
2. N value – blows/300 mm penetration of a 623 N (140 Lb.) hammer falling 760 mm (30 in.) on a 50 mm O.D. split spoon soil sampler. The split spoon sampler is driven 450 mm (18 in.) or 610 mm (24 in.). The “N” value is the Standard Penetration Test (SPT) value and is normally taken as the number of blows to advance the sampler the last 300 mm.


APPENDIX B CONTINUED
CLASSIFICATION OF SOILS FOR ENGINEERING PURPOSES
ASTM Designation: D 2487 - 69 AND D 2488 – 69
(Unified Soil Classification System)

Major Divisions			Group Symbols	Typical Names	Classification Criteria		
Coarse-grained soils More than 50% retained on No. 200 sieve *	Gravels 50% or more of coarse fraction retained on No. 4 sieve	Clean gravels	GW	Well-graded gravels and gravel-sand mixtures, little or no fines	Classification on basis of percentage of fines Less than 5% pass No. 200 sieve . . . . . GW, GP, SW, SP More than 12% pass No. 200 sieve . . . . . GM, GC, SM, SC 5 to 12% pass No.200 sieve . . . . . Borderline classifications requiring use of dual symbols	C_u=D60/D10 greater than 4; C_z = $(D30)^2$/(D10xD60) between 1 and 3	
			GP	Poorly graded gravels and gravel-sand mixtures, little or no fines		Not meeting both criteria for GW	
		Gravels with fines	GM	Silty gravels, gravel-sand-silt mixtures		Atterberg limits below "A" line or P.I. less than 4	Atterberg limits plotting in hatched area are borderline classifications requiring use of dual symbols
			GC	Clayey gravels, gravel-sand-clay mixtures		Atterberg limits above "A" line with P.I. greater than 7	
	Sands More than 50% of coarse fraction passes No. 4 sieve	Clean Sands	SW	Well-graded sands and gravelly sands, little or no fines		C_u=D60/D10 greater than 6; C_z = $(D30)^2$/ (D10xD60) between 1 and 3	
			SP	Poorly graded sands and gravelly sands, little or no fines		Not meeting both criteria for SW	
		Sands with fines	SM	Silty sands, sand-silt mixtures		Atterberg limits below "A" line or P.I. less than 4	Atterberg limits plotting in hatched area are borderline classifications requiring use of dual symbols
			SC	Clayey sands, sand-clay mixtures		Atterberg limits above "A" line with P.I. greater than 7	
Fine-grained soils 50% or more passes No. 200 sieve *	Silts and clays Liquid limit 50% or less		ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands	Plasticity Chart For classification of fine-grained soils and fine fraction of coarse-grained soils. Atterberg limits plotting in hatched area are borderline classifications requiring use of dual symbols. Equation of A-line: PI=0.73 (LL-20)		
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silts			
			OL	Organic silts and organic silts of low plasticity			
	Silts and clays Liquid limit greater than 50%		MH	Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts			
			CH	Inorganic clays of high plasticity, fat clays			
			OH	Organic clays of medium to high plasticity			
	Highly organic soils		Pt	Peat, much and other highly organic soils	* Based on the material passing the 3 in. (76mm) sieve.		




APPENDIX C

DRAWING 20253C-01 – BOREHOLE LOCATION PLAN
BOREHOLE LOGS



LANDTEK LIMITED
205 Nebo Road, Unit 3
Hamilton, Ontario L8W 2E1
p: +1 (905) 383-3733 ○ f: +1 (905) 383-8433
engineering@landteklimited.com
www.landteklimited.com

project location



Key plan provided by Google Earth.

Approximate location of borehole as drilled by Landtek Limited on August 31, 2020.

Approximate location of boreholes completed as monitoring wells and installed by Landtek Limited on August 31, 2020.

Borehole and monitoring well locations are considered approximate.

Base plan provided by Graziani + Corazza Architects Inc.

revisions/ submissions

#	date	description
1	September 16, 2020	Issued for report
2	May 28, 2021	Issued for report

client
Brant Street Joint Venture

municipality
The Corporation of the City of Burlington

project
Geotechnical Investigation
747 & 761 Brant Street

sheet
Borehole Location Plan

date: May 28, 2021
drawn: MDC
checked: IA
project #: 20253C
scale: NOT TO SCALE


20253C-01


LANDTEK LIMITED


BH/MW 9

Project No.:	20253C	Drill Date:	August 31, 2020
Project:	Geotechnical Investigation	Drill Method:	[ ] solid stem [x] hollow stem [x] Triconing
Location:	Brant Street and Ghent Avenue, Burlington, Ontario	Datum:	Geodetic (Approximate)

Material Description	Elev. Depth	Sample No.	Sample Type
Ground Surface	91.3		
±50 mm of asphalt	0.0	1	SS
± 200 mm of crushed limestone			
FILL: clayey silt, trace gravel, dark brown, firm, moist		2	SS
		3	SS
	88.3		
CLAYEY SILT TILL: trace gravel, trace shale, brownish grey, very stiff, moist	3.0	4	SS
	3.5		
SHALE BEDROCK (Queenston Formation) very weak to weak, highly weathered, red, moist		5	SS
		6	SS
	82.2		TRICONE DRILLING
	9.1		
AUGER REFUSAL			
BOREHOLE TERMINATED			







Notes:
1. Groundwater not encountered during auger drilling (to depths of 6.5 m)
2. Water level reading: 3.15 m on September 24, 2020

PP = pocket penetrometer TCV = total combustible vapour BRD = bulk relative density
PL = plastic limit LL = liquid limit PI = plasticity index FV = field vane LV = lab vane VS = vane sensitivity

LANDTEK LIMITED
205 Nebo Road, Unit 3
Hamilton, Ontario, Canada, L8W 2E1
Ph: (905) 383-3733 Fax: (905) 383-8433
www.landteklimited.com

LANDTEK LIMITED

BH 10

Project No.:	20253C	Drill Date:	August 31, 2020
Project:	Geotechnical Investigation	Drill Method:	[ ] solid stem [x] hollow stem [ ] Coring
Location:	Brant Street and Ghent Avenue, Burlington, Ontario	Datum:	Geodetic (Approximate)

Material Description	Symbol	Elev. Depth	Samples No.	Samples Type	Scale (m)	SPT "N" Value	Soil Moisture (%)	GWL	Monitor Details	Test Data
Ground Surface		91.3								
±50 mm of Topsoil		0.0								
FILL: clayey silt, trace gravel, trace iron staining, stiff to very stiff, moist			1	SS		11	10			
			2	SS		23	11			
			3	SS		10	15			
SHALE BEDROCK (Queenston Formation) very weak to weak, highly weathered, red, moist		3.0	4	SS		50/125mm	11			
			5	SS		50/100mm	8			
			6	SS		50/100mm	8			
AUGER REFUSAL **BOREHOLE TERMINATED**		6.0								

SPT "N" Value: 0 25 50 75 100 | Soil Moisture (%): 0 25 50 | Scale (m): 0.0 -0.5 -1.0 -1.5 -2.0 -2.5 -3.0 -3.5 -4.0 -4.5 -5.0 -5.5 -6.0 -6.5 -7.0 -7.5 -8.0 -8.5 -9.0 -9.5 -10.0 -10.5 -11.0 -11.5 -12.0 -12.5 -13.0 -13.5 -14.0 -14.5 -15.0 -15.5 -16.0 -16.5 -17.0 -17.5 -18.0 -18.5 -19.0 -19.5 -20.0

Notes: 1. Groundwater not encountered during drilling

PP = pocket penetrometer TCV = total combustible vapour BRD = bulk relative density
PL = plastic limit LL = liquid limit PI = plasticity index FV = field vane LV = lab vane VS = vane sensitivity

LANDTEK LIMITED
205 Nebo Road, Unit 3
Hamilton, Ontario, Canada, L8W 2E1
Ph: (905) 383-3733 Fax: (905) 383-8433
www.landteklimited.com

LANDTEK LIMITED

BH/MW 11

Project No.:	20253C	Drill Date:	August 31, 2020
Project:	Geotechnical Investigation	Drill Method:	[ ] solid stem [x] hollow stem [x] Coring
Location:	Brant Street and Ghent Avenue, Burlington, Ontario	Datum:	Geodetic (Approximate)

Material Description	Elev. Depth	Samples No.	Samples Type	Test Data
Ground Surface	91.1			Flush mount
±50 mm of asphalt ± 100 mm of crushed limestone **FILL:** clayey silt, trace gravel, trace iron staining, soft to stiff, very moist to wet	0.0	1 2 3	SS SS SS	WL = 1.95 m Sept. 24, 2020
	88.1			
SHALE BEDROCK (Queenston Formation) very weak to weak, highly weathered, red, moist	3.0	4	SS	bentonite backfill to 0.3 m below existing pavement surface
7.6 m to 9.3 m: slightly weathered to fresh, medium strong	83.5	5	SS	sand backfill to 6.0 m
Recovery = 100 %; RQD = 83 % ∂ = 25.7 kN/m³; UCS strength = 27.3 MPa	7.6	RUN #1	63 mm Dia. Core	6.3 m
Recovery = 100 %; RQD = 100 % ∂ = 25.7 kN/m³; UCS strength = 39.5 MPa	8.5 81.8	RUN #2	63 mm Dia. Core	3.0 m of slotted 50 mm dia. PVC pipe
BOREHOLE TERMINATED	9.3			9.3 m

SPT "N" Value: 9, 8, 3, 50 /125 mm, 50 /75 mm

Soil Moisture (%): 27, 22, 22, 19, 5

Notes:
1. Groundwater not encountered during auger drilling (to depths of 7.6 m)
2. Water level reading: 1.95 m on September 24, 2020


PP = pocket penetrometer TCV = total combustible vapour BRD = bulk relative density
PL = plastic limit LL = liquid limit PI = plasticity index FV = field vane LV = lab vane VS = vane sensitivity

LANDTEK LIMITED
205 Nebo Road, Unit 3
Hamilton, Ontario, Canada, L8W 2E1
Ph: (905) 383-3733 Fax: (905) 383-8433
www.landteklimited.com

APPENDIX D

DRAWING 20253C-02 – ENGINEERING COMMENTARIES – GENERAL REQUIREMENTS FOR DRAINAGE TO BASEMENT STRUCTURES

DRAWING 20253C-03 – ENGINEERING COMMENTARIES – GENERAL REQUIREMENTS FOR UNDERFLOOR DRAINAGE SYSTEMS



① 100 mm, perforated or slotted pipe placed below the upper level of the floor slab.;
③ Filter material that is compatible with the grain size characteristics of the fine grained foundation and backfill soils, as well as with the perforations of the pipe;
④ Filter material continuously or intermittently placed next to the foundation wall to intercept water draining from window wells, down exterior walls and from low areas near the building;
⑤ Damp-proofing on wall – optional depending on the quality of the concrete wall;
⑥ Optional use of sheet drain, or synthetic fire blanket, next to the foundation wall to replace the soil filter according to ④;
⑦ Foundation and backfill soils, which may contain fine grained and erosion-susceptible materials;
⑧ "*Topping off*" material is to be graded such that it slopes outwards to lead surface water away from the building. It is usually desirable to use low permeability topsoil to reduce the risk of overloading the drainage pipe.


Based on Figure 12.1, Canadian Foundation Engineers Manual, Fourth Edition, 2006.

Additional Notes:

1. The perforated or slotted drainage pipe is to lead to a positive drainage sump or outlet. The invert of the pipe is to be a minimum of 150 mm below the underside of the proposed floor slab.
2. Backfill materials to the interior of the foundation walls may be clean, organic-free soils that can be compacted to the specified density within in a confined space.
3. Heavy, vibratory compaction equipment should not be used within 450 mm of the foundation wall. Fill is not to be placed or compacted within 1.8 m of the wall unless fill is being placed simultaneously on both sides of the wall.
4. The moisture barrier beneath the floor slab is to comprise at least 200 mm of compacted19mm clear stone or an equivalent free-draining material.
5. Should the 19 mm clear stone require surface blinding then 6mm stone chips are to be used.
6. The slab on grade should not be structurally connected to the foundation wall or footing.

LANDTEK LIMITED
205 Nebo Road, Unit 3
Hamilton, Ontario L8W 2E1
p: +1 (905) 383-3733 ◦ f: +1 (905) 383-8433
engineering@landteklimited.com
www.landteklimited.com

General Requirements for Drainage to Basement Structures			
client	Brant Street Joint Venture		
project	747 & 761 Brant Street, Burlington, Ontario		
project #	20253-C	drawing #	20253C-02



Notes:

1. Drainage tile to consist of 100 mm diameter weeping tile or equivalent perforated pipe leading to a positive sump or outlet, spaced between columns;
2. 19 mm clear stone – 150 mm top and side of drain. If the drain is not on the footing then place 100 mm of 19 mm clear stone below the drain;
3. Wrap the clear stone with an approved filter fabric (e.g. Terrafix 270R or equivalent);
4. Moisture barrier to be at least 200 mm of compacted, 19 mm clear stone or equivalent (and approved), free-draining material. A vapour barrier may be required for specialty floor coverings;
5. Typically, the slab-on-grade is not structurally connected to the wall or footing. However, if it is connected to the walls it should be designed accordingly;
6. Underfloor drain invert to be at least 300 mm below underside of floor slab. Drainage tile should be placed in parallel rows 6 m to 8 m centres one way. Place drains on 100 mm of 19 mm clear stone and 150 mm of 19 mm clear stone on top and sides. Enclose clear stone with filter fabric as prescribed in Note (3);
7. Do not connect underfloor drainage to perimeter drainage. The two systems are to remain separate.
8. Locate solid discharge at the middle of each bay between soldier piles;
9. Vertical drainage board (e.g. MiraDrain 6000 or equivalent) with filter cloth should be continuous from bottom to 1.2 m below exterior finished grade;
10. The entire subgrade is to be sealed with an approved filter fabric as in Note (3) where non-cohesive (silty/sandy/granular) soils are encountered below the groundwater table;
11. The basement walls must be waterproofed using bentonite or an equivalent waterproofing system;
12. The Geotechnical Report should be reviewed for site-specific details. Final detail must be approved before system is considered acceptable.

LANDTEK LIMITED
205 Nebo Road, Unit 3
Hamilton, Ontario L8W 2E1
p: +1 (905) 383-3733 ◦ f: +1 (905) 383-8433
engineering@landteklimited.com
www.landteklimited.com

General Requirements for Underfloor Drainage Systems

client	Brant Street Joint Venture		
project	747 & 761 Brant Street, Burlington, Ontario		
project #	20253-C	drawing #	20253C-03

APPENDIX E

CHEMICAL LABORATORY TESTING RESULTS

AGAT Laboratories

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
http://www.agatlabs.com

Certificate of Analysis

AGAT WORK ORDER: 20T656425

PROJECT: 20253

CLIENT NAME: LANDTEK LTD.

ATTENTION TO: Isaac Asonya

SAMPLING SITE:

SAMPLED BY:

Corrosivity Package

DATE RECEIVED: 2020-09-28

DATE REPORTED: 2020-10-06


Parameter	Unit	G / S: A	G / S: B	G / S: C	RDL	BH2-SS4 and SS5 Soil 2020-09-25 17:00 1495539	BH5-SS7 and SS8 Soil 2020-09-25 17:00 1495548	BH8-SS3 and SS4 Soil 2020-09-25 17:00 1495549	BH10-SS5 and SS6 Soil 2020-09-25 17:00 1495550
Chloride (2:1)	µg/g	NA	NA	NA	2	30	34	120	32
Sulphate (2:1)	µg/g				2	105	45	278	163
pH (2:1)	pH Units				NA	8.70	8.57	8.00	8.75
Electrical Conductivity (2:1)	mS/cm	0.57	0.7	0.7	0.005	0.262[<A]	0.236[<A]	0.551[<A]	0.409[<A]
Resistivity (2:1) (Calculated)	ohm.cm				1	3820	4240	1810	2440
Redox Potential 1	mV				NA	154	129	169	161
Redox Potential 2	mV				NA	165	138	163	179
Redox Potential 3	mV				NA	178	133	166	166

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: A Refers to Table 1: Full Depth Background Site Condition Standards - Soil - Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use, B Refers to Table 2: Full Depth Generic Site Condition Standards in a Potable Ground Water Condition - Soil - Residential/Parkland/Institutional Property Use - Medium and Fine Textured Soils, C Refers to Table 3: Full Depth Generic Site Condition Standards in a Non-Potable Ground Water Condition - Soil - Residential/Parkland/Institutional Property Use - Medium and Fine Textured Soils
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

1495539-1495550 EC, pH, Chloride and Sulphate were determined on the extract obtained from the 2:1 leaching procedure (2 parts DI water: 1 part soil). Resistivity is a calculated parameter.
Redox potential measured on as received sample. Due to the potential for rapid change in sample equilibrium chemistry with exposure to oxidative/reduction conditions laboratory results may differ from field measured results.
Redox potential measurement in soil is quite variable and non reproducible due in part, to the general heterogeneity of a given soil. It is also related to the introduction of increased oxygen into the sample after extraction. The interpretation of soil redox potential should be considered in terms of its general range rather than as an absolute measurement.

Analysis performed at AGAT Toronto (unless marked by *)

Certified By:



Results relate only to the items tested. Results apply to samples as received.

AGAT Laboratories

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
http://www.agatlabs.com

Certificate of Analysis

AGAT WORK ORDER: 20T658808

PROJECT: 20T656425

CLIENT NAME: LANDTEK LTD.

ATTENTION TO: Isaac Asonya

(201-042) Sulfide

DATE SAMPLED: Oct 01, 2020 | DATE RECEIVED: Oct 02, 2020 | DATE REPORTED: Oct 07, 2020 | SAMPLE TYPE: Other

Analyte:	Sulfide
Unit:	%
Sample ID (AGAT ID) RDL:	0.05
BH2-SS4 and SS5-1495539 (1509766)	<0.05
BH5-SS7 and SS8-1495548 (1509767)	<0.05
BH8-SS3 and SS4-1495549 (1509768)	0.14
BH10-SS5 and SS6-1495550 (1509769)	<0.05

Comments: RDL - Reported Detection Limit

Analysis performed at AGAT 5623 McAdam Rd., Mississauga, ON (unless marked by *)

Certified By: Sherin Moussa

Results relate only to the items tested. Results apply to samples as received.

APPENDIX F

ROCK CORE TESTING RESULTS

GEOMECHANICA

Rock Laboratory Testing Results

A report submitted to:

Isaac Asonya
Landtek Limited
205 Nebo Road
Hamilton, Ontario
Canada, L8W 2E1

Prepared by:

Bryan Tatone, PhD, PEng

Omid Mahabadi, PhD, PEng
Geomechanica Inc.
#900-390 Bay St.
Toronto ON
M5H 2Y2 Canada
Tel: +1-647-478-9767
lab@geomechanica.com

October 6, 2020
Project number: 20253A, B, C

Abstract

This document summarizes the results of rock laboratory testing, including 3 Uniaxial Compressive Strength (UCS) tests and 3 Point Load Tests (PLT). The results of each test type are presented in separate sub-sections herein.

In this document:

1 Uniaxial Compressive Strength Tests 1
2 Point Load Testing 3
Appendices 6

Disclaimer: This report was prepared by Geomechanica Inc. for Landtek Limited. The material herein reflects Geomechanica Inc.'s best judgment given the information available at the time of preparation. Any use which a third party makes of this report, any reliance on or decision to be made based on it, are the responsibility of such third parties. Geomechanica Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

1 Uniaxial Compressive Strength Tests

1.1 Overview

This section summarizes the results of uniaxial compressive strength (UCS) testing. The testing was performed in Geomechanica's rock testing laboratory using a 150 ton (1.3 MN) Forney loading frame equipped with pressure-compensated control valve to maintain an axial displacement rate of approximately 0.10 mm/min (Figure 1). The preparation and testing procedure of each sample included the following:

1. Unwrapping of the core sample, inspecting it for damage, and re-wrapping it in electrical tape to minimize exposure to moisture during subsequent specimen preparation.
2. Diamond cutting of the core sample to obtain cylindrical specimens with an appropriate length (length:diameter = 2:1) and nearly parallel end faces.
3. Diamond grinding of the specimen to obtain flat (within ± 0.025 mm) and parallel end faces (within 0.25°).
4. Placing of the specimen into the loading frame, applying a 1 kN axial load, and removing the electrical tape.
5. Axially loading the specimens to rupture while continuously recording axial force and axial deformation to determine the peak strength (UCS).



Figure 1: Forney loading frame setup for uniaxial compression testing.

Using a precision V-block mounted on the magnetic chuck of the surface grinder, test specimens met the end flatness, end parallelism, and perpendicularity criteria set out in ASTM D4543-19. The side straightness criteria, as checked with a feeler gauge, was met for all samples and the minimum length:diameter criteria was met for all specimens unless noted otherwise in Table 1. Testing of the specimens followed ASTM D7012-14 Method C.

1.2 Results

The results of UCS testing are summarized in Table 1. Additional specimen measurements and test details are provided in the summary spreadsheet that accompanies this report.

*

Table 1: Summary of Uniaxial Compression test results.

Sample	Depth (m)	Bulk density ρ (g/cm^3)	UCS (MPa)	Lithology	Failure description
20253A-BH1, Run 4	12.00 - 12.20	2.606	44.3	Queenston Shale	1
20253B-BH5, Run 2	10.30 - 10.58	2.598	47.8	Queenston Shale	2
20253C-BH11, Run 2	9.00 - 9.20	2.625	39.5	Queenston Shale	1
	Average	2.610	43.9		
	Standard deviation	0.011	3.4		

[1] Axial splitting failure

[2] Partial hourglass failure

1.3 Specimen photographs

Photographs of the specimen before and after testing are presented in the Appendix of this report.

*

2 Point Load Testing

2.1 Overview

This section summarizes the results of Point Load Testing (PLT). The tests were performed using a Carver 12-ton hydraulic press with point load test platens and equipped with a 0-5000 psi digital pressure gauge with a peak pressure holding capability (Figure 2). Testing was completed on rock core samples. Axial tests were performed according to ASTM D5731-16.



Figure 2: Point load tester equipped with digital pressure gauge.

2.2 Results

The results of the PLT tests are summarized in Table 2. Note that the load, *P*, in kN was calculated from the measured peak pressure, as:

$$P = p \times A_{ram} \tag{1}$$

where, *p* is the peak pressure in kPa and A_{ram} is the effective cross-sectional area of the hydraulic ram in square metres. The effective diameter of the ram of the employed tester was 52 mm.

The uncorrected point load strength (I_s) is calculated as:

$$I_s = \frac{P}{{D_e}^2} \tag{2}$$

where, D_e is the equivalent core diameter in mm calculated as:

$$D_e{}^2 = D^2 \quad \text{for diameteral tests} \tag{3}$$

$$= \frac{4A}{\pi} \quad \text{for axial tests} \tag{4}$$

where D is the distance between platens in mm and A is the minimum cross sectional area of a plane through the platen contact points. The value of A is given by:

$$A = W \times D \tag{5}$$

where W is the width of the specimen.

The size correction factor (F) is obtained from the expression:

$$F = \left(\frac{D_e}{50}\right)^{0.45} \tag{6}$$

and the size-corrected point load strength ($I_{s(50)}$) for a core with D = 50 mm was calculated as:

$$I_{s50} = F \times I_s. \tag{7}$$

Table 2: Summary of PLT results.

Sample	Depth (m)	Test type A-axial D-diametric	Distance Between Platens, D (mm)	Failure Load P (kN)	Effective Diameter De (mm)	Uncorrected Point Strength, Strength, I_s (MPa)	Size Correction Factor, F	Size-Corrected Point Load Strength, $I_{s(50)}$ (MPa)
20253A-BH1, Run 2	10.30 - 10.40	A [1]	35.00	3.84	53.05	1.36	1.03	1.40
		A [1]	34.00	7.72	52.29	2.82	1.02	2.88
		A [2]	32.00	8.24	50.72	3.20	1.01	3.22
		A [2]	40.00	13.98	56.71	4.35	1.06	4.60
					Axial Mean	2.93		3.03
					Estimated UCS ($24I_{s(50)}$)			72.72 MPa
20253B-BH5, Run 1	10.16 - 10.38	A [1]	38.00	7.19	55.34	2.35	1.05	2.46
		A [3]	38.00	16.11	55.34	5.26	1.05	5.50
		A [1]	19.00	2.80	39.13	1.83	0.90	1.64
		A [1]	24.50	1.52	44.44	0.77	0.95	0.73
					Axial Mean	2.55		2.58
					Estimated UCS ($24I_{s(50)}$)			61.92 MPa
20253C-BH11, Run 1	8.25 - 8.46	A [1]	22.00	1.30	41.91	0.74	0.92	0.69
		A [1]	25.00	3.38	44.68	1.69	0.95	1.61

Continued on next page

Table 2 – Summary of PLT results. (continued from previous page)

Sample	Depth (m)	Test type A-axial D-diametric	Distance Between Platens, D (mm)	Failure Load P (kN)	Effective Diameter De (mm)	Uncorrected Point Strength, Strength, I_s (MPa)	Size Correction Factor, F	Size-Corrected Point Load Strength, $I_{s(50)}$ (MPa)
		A [1]	28.00	2.21	47.28	0.99	0.98	0.96
		A [1]	42.00	6.37	57.91	1.90	1.07	2.03
		A [1]	35.50	3.48	53.24	1.23	1.03	1.26
		A [1]	27.00	0.95	46.43	0.44	0.97	0.43
		A [1]	24.00	2.01	43.78	1.05	0.94	0.99
					Axial Mean	1.15		1.14
					Estimated UCS ($24I_{s(50)}$)			27.36 MPa

[1] Queenston Formation - red shale
[2] Queenston Formation - greenish-grey reduction zone
[3] Queenston Formation - red shale with limestone inter-beds

Appendices

Specimen sheets

- 20253A-BH1, Run 4
- 20253B-BH5, Run 2
- 20253C-BH11, Run 2

Uniaxial Compression Test

Client	Landtek Limited	**Project**	20253A, B, C
Sample	20253A-BH1, Run 4	**Depth**	12.00 - 12.20

Specimen parameters	
Diameter (mm) [a]	63.25
Length (mm) [a]	125.06
Bulk density ρ (g/cm^3)	2.606
UCS (MPa)	44.3
Lithology	Queenston Shale
Failure description [b]	1

[a] Additional specimen measurement/details provided in accompanying summary spreadsheet.
[b] Failure description: [1] Axial splitting failure;

Prior to testing



After testing



Remarks:

Performed by	BSAT	**Date**	2020-10-05

Uniaxial Compression Test

Client	Landtek Limited	**Project**	20253A, B, C
Sample	20253B-BH5, Run 2	**Depth**	10.30 - 10.58

Specimen parameters	
Diameter (mm) [a]	63.13
Length (mm) [a]	131.82
Bulk density ρ (g/cm^3)	2.598
UCS (MPa)	47.8
Lithology	Queenston Shale
Failure description [b]	2

[a] Additional specimen measurement/details provided in accompanying summary spreadsheet.
[b] Failure description: [2] Partial hourglass failure;

Prior to testing



After testing



Remarks:

Performed by	BSAT	**Date**	2020-10-05

GEOMECHANICA

Uniaxial Compression Test

Client	Landtek Limited	**Project**	20253A, B, C
Sample	20253C-BH11, Run 2	**Depth**	9.00 - 9.20

Specimen parameters	
Diameter (mm) [a]	63.10
Length (mm) [a]	130.64
Bulk density ρ (g/cm^3)	2.625
UCS (MPa)	39.5
Lithology	Queenston Shale
Failure description [b]	1

[a] Additional specimen measurement/details provided in accompanying summary spreadsheet.
[b] Failure description: [1] Axial splitting failure;

Prior to testing



After testing



Remarks:

Performed by	BSAT	**Date**	2020-10-05