Phase One Environmental Site Assessment

Millcroft Golf Club (Block E)

Burlington, Ontario

Prepared For:

Millcroft Greens Corporation

4900 Palladium Way, Suite 105,

Burlington, ON

L7M 0W7

DS Project No : 19-199-102
Date: 2020-01-30
Revised: 2020-07-02

DS CONSULTANTS LTD.
6221 Highway 7, Unit 16
Vaughan, Ontario, L4H 0K8
Telephone: (905) 264-9393
www.dsconsultants.ca

Executive Summary

DS Consultants Ltd. (DS) was retained by Millcroft Greens Corporation (the "Client") to conduct a Phase One Environmental Site Assessment (ESA) of a portion of the Millcroft Golf Club, designated "Block E" located at 4274 Dundas Street in the City of Burlington, Ontario, herein referred to as the "Phase One Property". The Phase One Property is a 0.61-hectare (1.52 acres) parcel of land situated within a residential neighbourhood in the City of Burlington, Ontario. The Property currently incudes a one (1) storey rectangular structure made of concrete block and bricks with vertical siding exterior walls (Building A) that is used for maintenance and storage of lawn mowers and golf carts. The building also functions as the changing and lunchroom for the superintendent and maintenance workers of the golf club.

DS understands that this Phase One ESA may be used to support the filing of a Record of Site Condition (RSC) as part of the proposed redevelopment of the Phase One Property for residential purposes. It is further understood that the proposed development will consist of residential dwellings. It is the opinion of DS that the intended future property use (residential) constitutes a more sensitive property use, as defined under O.Reg. 153/04 (as amended) than the current commercial land use. Given that the proposed change in property use is to a more sensitive property use, the filing of a Record of Site Condition (RSC) with the Ontario Ministry of Environment, Conservation and Parks (MECP) will be mandated under O.Reg. 153/04 (as amended).

The Phase One ESA was completed to satisfy the intent of the requirements, methodology and practices for a Phase One ESA as described in Ontario Regulation 153/04 (as amended). The objectives of the Phase One ESA is to identify the presence or absence of potentially contaminating activities (PCAs) on the Phase One Property and/or within the Phase One Study Area, and to determine if the PCAs identified within the Phase One Study Area are likely to result in an Area of Potential Environmental Concern (APEC) on the Phase One Property. The information obtained by the Phase One ESA will be used to assess whether further investigation in the form of a Phase Two ESA is merited. It should be noted that this Phase One ESA does not include any sampling or testing and is based solely on a review of readily available data, and observations made during the Phase One Site Reconnaissance.

Based on the findings of the Phase One ESA, DS presents the following findings:

- The Phase One Property appears to have been used for agricultural purposes from the late 1800s until 2004, when the existing maintenance building was constructed. The current structure is used for the maintenance, storage of supplies and golf carts and lawnmowers used at Millcroft Golf Club.
- The topography on the Phase One Property and within the Phase One Study Area is generally flat with a surficial elevation of 155 metres above sea level (masl) and a slight slope to the

south-east. Based on the local topography, the shallow groundwater flow direction is inferred to be southwest towards Appleby Creek. Long term groundwater monitoring would be required in order to confirm the direction of groundwater flow on the Phase One Property;

- Based on a review of the OGS Earth database, the Phase One Property is situated with a south slope physiographic region. The overburden (surficial geology) in the vicinity of the Phase One Property is described as "till plains (drumlinized)", and the bedrock is described as shale, limestone, dolostone, and siltstone of the Queenston Formation. Based on a review of the MECP Well Records, the bedrock underlying the Phase One Property is anticipated to be encountered at an approximate depth of 8 metres below ground surface (mbgs);
- The following issues of potential environmental concern were identified on the Phase One Property:
    - The Property was registered as a waste generator of petroleum distillates, waste oils, lubricants, and aliphatic solvents and residues **(PCA-1)**;
    - Fill material seem to have been imported to the Property for the development of the Millcroft Golf Club around 1987 **(PCA-3)**;
    - During the site reconnaissance, one (1) hydraulic hoist, one (1) 22,000L gasoline AST, one (1) 22,000L diesel AST, one (1) ~20,000L waste oil AST, and one (1) barrel of lubricant oil was observed **(PCA-4)**;
    - During the site reconnaissance, one room used for the storage of pesticides was observed **(PCA-5)**;
    - During the site reconnaissance, one (1) transformer was observed **(PCA-6)**;
    - During the site reconnaissance, one pallet holding a bulk of batteries was observed **(PCA-7)**; and
    - During the site reconnaissance, one (1) oil/water separator was observed **(PCA-8)**
- The neighbouring properties within the Phase One Study Area appear to have been used for residential and agricultural purposes prior to 1987, at which point the surrounding properties were developed for residential and commercial purposes.

Based on a review of the information available at this time it is concluded that nine (9) PCAs were identified on the Phase One Property which are considered to be contributing to seven (7) APECs in, on, or under the Phase One Property. A summary of the PCAs identified and the associated APECs is provided in Table E-1 below. Note that the PCA numbers used below are per Table 2, Schedule D of O.Reg. 153/04.

Table E-1: Summary of APECs Identified on Phase One Property

Area of Potential Environmental Concern	Location of APECs on Phase One Property	Potentially Contaminating Activity	Location of PCA (on-site or off-site)	Contaminants of Potential Concern	Media Potentially Impacted (Ground water, soil and/or sediment)
APEC-1	Surroundings of Building A	PCA-1 (# 27: Garages and Maintenance and Repair of Railcars, Marine Vehicles and Aviation Vehicles	On Site	PHC, BTEX VOCs, Metals	Soil and groundwater
APEC-2	Entire Property	PCA-3 (#30): Importation of Fill Material of Unknown Quality	On Site	PHCs, VOCs, BTEX, Metals, As, Sb, Se, B-HWS, CN-, electrical conductivity, Cr (VI), Hg, low or high pH, SAR, PAHs	Soil
APEC-3	Centre portion of the Property	PCA-4 (#28): Gasoline and Associated Products Storage in Fixed Tanks	On Site	PHCs, VOCs, BTEX, Metals,	Soil and ground water
APEC-4	Northeast corner of Building A	PCA-5 (#40): Pesticides (including Herbicides, Fungicides and Anti-Fouling Agents) manufacturing, Processing, Bulk Storage and large-Scale Applications	On Site	OCPs	Soil and ground water
APEC-5	Southwest portion of Building A	PCA-6 (#28): Transformer Manufacturing, Processing and Use	On Site	PCBs	Soil
APEC-6	Surroundings of Building A	PCA-8 (#N/S): Oil/water separator.	On Site	PHC, BTEX VOCs, Metals	Soil and groundwater
APEC-7	Surroundings of Building A	PCA-7 (#6): Battery Manufacturing, Recycling and Bulk Storage	On Site	PHC, BTEX VOCs, Metals	Soil and groundwater

The PCAs identified in Table E-1 above are considered by the Qualified Person (QP) to be contributing to Areas of Potential Environmental Concern on the Phase One Property. The Potential Contaminants of Concern (PCOCs) identified by the QP include PHCs, VOCs, BTEX, Metals, As, Sb, Se, B-HWS, CN-, EC, Cr (VI), Hg, low or high pH, SAR, PAHs, PCBs, and OCPs. Based on the findings of this Phase One ESA, it is concluded that a Phase Two ESA would be required in order to investigate the aforementioned APECs and to assess the environmental soil and groundwater conditions on the

Phase One Property. A Record of Site Condition cannot be filed based on the findings of the Phase One ESA.

Table of Contents

1.0 INTRODUCTION 1
1.1 PHASE ONE PROPERTY INFORMATION 2
1.2 SITE DESCRIPTION 2
2.0 SCOPE OF INVESTIGATION 3
3.0 RECORDS REVIEW 5
3.1 GENERAL 5
3.1.1 Phase One Study Area Determination 5
3.1.2 First Developed Use Determination 5
3.1.3 Fire Insurance Plans 5
3.1.4 Chain of Title 6
3.1.5 Environmental Reports 6
3.1.6 City Directories 6
3.2 ENVIRONMENTAL SOURCE INFORMATION 6
3.2.1 Ecolog Eris Report 6
3.2.2 Ministry of the Environment- Freedom of Information 8
3.2.3 Technical Standards and Safety Authority 9
3.2.4 Areas of Natural and Scientific Interest 9
3.2.5 Conservation Halton 9
3.3 PHYSICAL SETTING SOURCES 9
3.3.1 Aerial Photographs and Historical Mapping 9
3.3.2 Topography, Hydrology, Geology 10
3.3.3 Fill Materials 11
3.3.4 Water Bodies and Areas of Natural Significance 11
3.3.5 Well Records 11
3.4 SITE OPERATING RECORDS 11
4.0 INTERVIEWS 12
4.1 PERSONNEL INTERVIEWED 12
4.2 INTERVIEWEE RATIONALE 12
4.3 RESULTS OF INTERVIEW 12
5.0 SITE RECONNAISSANCE 13
5.1 GENERAL REQUIREMENTS 13
5.2 SPECIFIC OBSERVATIONS AT PHASE ONE PROPERTY 13
5.3 WRITTEN DESCRIPTION OF INVESTIGATION 16
6.0 REVIEW AND EVALUATION OF INFORMATION 17
6.1 CURRENT AND PAST USES 17
6.2 POTENTIALLY CONTAMINATING ACTIVITY 17
6.3 AREAS OF POTENTIAL ENVIRONMENTAL CONCERN 19
6.4 PHASE ONE CONCEPTUAL SITE MODEL 20
6.4.1 Potentially Contaminating Activity Affecting the Phase One Property 21
6.4.2 Contaminants of Potential Concern 21

6.4.3 Underground Utilities and Contaminant Distribution and Transport 22
6.4.4 Geological and Hydrogeological Information 22
6.4.5 Uncertainty and Absence of Information 22
7.0 CONCLUSIONS 23
7.1 PHASE TWO ENVIRONMENTAL SITE ASSESSMENT REQUIREMENT 23
7.2 RSC BASED ON PHASE ONE ENVIRONMENTAL SITE ASSESSMENT 23
7.3 LIMITATIONS 23
7.4 QUALIFICATIONS OF THE ASSESSORS 24
7.5 SIGNATURES 25
8.0 REFERENCES 26

FIGURES

Figure 1 – Site Location Plan
Figure 2 – Phase One Property Site Plan
Figure 3 – Phase One Study Area
Figure 4 – PCA within Phase One Study Area
Figure 5 – APEC Location

APPENDICES

Appendix A – Plan of Survey
Appendix B – City Directory Search
Appendix C – EcoLog ERIS Report
Appendix D – Regulatory Requests
Appendix E – Aerial Photographs
Appendix F – Site Photographs

1.0 Introduction

DS Consultants Ltd. (DS) was retained by Millcroft Greens Corporation (the "Client") to conduct a Phase One Environmental Site Assessment (ESA) of a portion of the Millcroft Golf Club, designated "Block E" located at 4274 Dundas Street in the City of Burlington, Ontario, herein referred to as the "Phase One Property". DS understands that this Phase One ESA may be used to support the filing of a Record of Site Condition (RSC) as part of the proposed redevelopment of the Phase One Property for residential purposes. It is further understood that the proposed development will consist of residential dwellings.

It is the opinion of DS that the intended future property use (residential) constitutes a more sensitive property use, as defined under O.Reg. 153/04 (as amended) than the current commercial land use. Given that the proposed change in property use is to a more sensitive property use, the filing of a Record of Site Condition (RSC) with the Ontario Ministry of Environment, Conservation and Parks (MECP) will be mandated under O.Reg. 153/04 (as amended).

The Phase One ESA was completed to satisfy the intent of the requirements, methodology and practices for a Phase One ESA as described in Ontario Regulation 153/04 (as amended). The objectives of the Phase One ESA is to identify the presence or absence of potentially contaminating activities (PCAs) on the Phase One Property and/or within the Phase One Study Area, and to determine if the PCAs identified within the Phase One Study Area are likely to result in an Area of Potential Environmental Concern (APEC) on the Phase One Property. The information obtained by the Phase One ESA will be used to assess whether further investigation in the form of a Phase Two ESA is merited. It should be noted that this Phase One ESA does not include any sampling or testing and is based solely on a review of readily available data, and observations made during the Phase One Site Reconnaissance.

1.1 Phase One Property Information

The information for the Phase One Property is provided in the following Table.

Table 1-1: Phase One Property Information

Criteria	Information	Source
Legal Description	PT LTS 7 TO 9, CON 1 SDS, PTS 1 TO 10 20R13519 S&E LANDS LAID OUT BY PLANS 20M780, 20M811, 20M868, 20M922, PTS 1 & 2, 20R15846, PIN 07182-2263 & PT 1, 20R16891; BURLINGTON. (NEW REFERENCE PLAN TO BE DEPOSITED FOR DESCRIPTION) S/T EASE H302472. S/T EASE 570228 LYING WITHIN THE LIMITS OF PTS 5 & 6 20R13519. S/T EASE NU39399 OVER PTS 7 &8, 20R13519. S/T EASE NU39398 TRANSFERRED BY 95199. S/T EASE H521403 LYING WITHIN THE LIMITS OF PT 5, 20R13519 & PTS 7 & 9 20R13519. T/W EASE 1499 95 OVER PT 8 20R6131. T/W EASE 153572 OVER PTS 9 & 10, 20R6131. S/T EASE IN FAV OF LTS 1, 16, 117 & 119, PL 20M922 & PT LTS 8& 9, CON 1 SDS PT 2, 20R16282 AS IN HR447696, Burlington	Land Registry Office
Property Identification Number (PIN)	0718-2700	Land Registry Office
Municipal Address	2155 Country Club Drive, Burlington, Ontario	City of Burlington, online information
Zoning	O1 (Open Space)	City of Burlington Zoning By-law 2020
Property Owner	2079610 Ontario Limited	Land Registry office, Client
Property Owner Contact Information	Mr. Ed Liptay	Client
Current Site Occupants	Millcroft Golf Club	Phase One Site Reconnaissance
Site Area	0.61 hectares (1.52 acres)	Client
Centroid UTM Coordinates	Northing: 4805779.27 Easting: 595905.26 Zone: 17T	Google Earth

1.2 Site Description

The Phase One Property is a 0.61-hectare (1.52 acres) parcel of land situated within a residential neighbourhood in the City of Burlington, Ontario. The Phase One Property is located at 4274 Dundas Street, approximately 140 m southwest of the intersection of Dundas St. and Millcroft Park Drive and was occupied by Millcroft Golf Club at the time of this investigation. A Site Location Plan is provided in Figure 1. For the purposes of this report, Dundas Street is assumed to be aligned in an east-west orientation.

The Property currently incudes a one (1) storey rectangular structure made of concrete block and bricks with vertical siding exterior walls (Building A) that is used for maintenance and storage of lawn mowers and golf carts. The building also functions as the changing and lunchroom for the superintendent and maintenance workers of the golf club. A Site Plan depicting the orientation of the buildings on-site is provided in Figure 2.

2.0 Scope of Investigation

The Phase One ESA was completed to satisfy the intent of the requirements, methodology and practices for a Phase One ESA as described in Ontario Regulation 153/04, as amended (Phase One ESA requirements). This included:

- A review of reasonably ascertainable records and reports regarding historical and current use, regulatory information, occupancy, and activities for the Phase One Property, including:
  - Physical setting information such as aerial photographs, topographic mapping, available historical maps and drawings;
  - Company records (e.g., site plans, building plans, permit records, production and maintenance records, asbestos surveys, site utility drawings, emergency response and contingency plans, spill reporting plans and records, inventories of chemicals and their usage (e.g. WHMIS), environmental monitoring data, waste management records, inventory of underground and aboveground tanks, environmental audit reports) provided to DS;
  - Geological and hydrogeological information in published government maps and/or reports;
  - A review of information on file with Ecolog ERIS, a commercial database that provides information from numerous private, provincial, and federal environmental databases/registries;
  - Review of fire insurance plans, municipal directory documentation and available environmental reports that are pertinent to the Phase One Property;
  - Regulatory Information, including such as Permits or Certificates of Approval (pertaining to activities that may impact the condition of the property, orders, control orders, or complaints related to environmental compliance that may impact the condition of the property, and violations of environmental statutes, regulations, by-laws, and permits that may impact the condition of the property;
  - Environmental source information including published and online records from Ministry of Environment, Conservation and Parks (MECP), Environment Canada, Technical Standards and Safety Authority (TSSA), and the City of Toronto; and
  - The Ontario Ministry of Natural Resources (MNR) Natural Heritage Information Centre database and the Conservation Authority website for information specific to natural areas, such as locations of environmentally sensitive areas or species.
- Interviews with available individuals having knowledge of current and/or past site activities;
- An inspection of the Phase One Property, and the activities on the adjacent properties, including and assessment of the following:
  - The site operations, processes, and waste management currently carried out on the Phase One Property.
  - The neighbouring land uses (i.e. identification of environmentally sensitive neighbours, as well as an assessment of potential off-site sources of contamination);

- The source of potable water for the Phase One Property and properties within the Phase One Study Area;
- The potential presence of existing or former above-ground or underground fuel storage tanks (ASTs or USTs);
- Possible cut and fill operations that may resulted in the importation of fill material of unknown quality;
- The presence/absence of floor cracks, hydraulic hoists, elevators, sumps and drains;
- Areas suspected to contain evidence of surficial and sub-surface impacts (e.g. areas of staining);
- The potential presence of various Designated Substances and building materials including:
  - Friable and non-friable asbestos
  - Urea formaldehyde foam insulation (UFFI)
  - Chlorofluorocarbons (CFCs) in air conditioning and refrigeration equipment
  - PCB-containing materials and electrical equipment
  - Lead-based paint
  - Mould
- The presence/absence of wells, pits and lagoons, drainage sumps and floor drains, sewage and wastewater disposal pipelines; and
- General site conditions, including topography and drainage, standing water, right-of-ways, presence of underground utilities, evidence of stained or odorous soils, and stressed vegetation.

- Evaluation of the information and documentation of the results in the form of a Phase One ESA Report.

The objectives of the Phase One ESA are:

1. To assess the environmental condition of the Phase One Property to develop a preliminary determination of the likelihood that one or more contaminants have affected any land or water on, in, or under the Phase One Property;
2. To identify potentially contaminating activities within the Study Area (i.e., areas within 250 m of the Property), and to assess if Areas of Potential Environmental Concern (APECs) exist on the Phase One Property;
3. To identify the Potential Contaminants of Concern associated with the PCAs identified; and
4. To provide a basis for subsequent investigation, if required, based on the findings of the Phase One ESA.

3.0 Records Review

3.1 General

3.1.1 Phase One Study Area Determination

Based on a review of the available historical records and the observations made during the Phase One Site Reconnaissance, no heavy industrial properties or other relevant potentially contaminating activities were observed which were considered to merit expanding the Phase One Study Area. As such the Phase One Study Area was defined by a 250-metre radius around the Phase One Property boundary, in accordance with O.Reg. 153/04 (as amended).

The properties within 250 m of the Phase One Property generally consist of community, residential, and commercial uses. An assessment of the historical and current use of all properties within the Phase One Study Area was conducted in order to assess for the presence/absence of potentially contaminating activities. A summary of the potentially contaminating activities identified within the Phase One Study Area is provided under Section 6.2. A plan depicting the Phase One Study Area limits is presented in Figure 3.

3.1.2 First Developed Use Determination

The first developed use of the Phase One Property is considered under O.Reg. 153/04 (as amended) to be either the first use of the Phase One Property in or after 1875 that resulted in the development of a building or structure on the property, or the first potentially contaminating use or activity on the Phase One Property.

The determination of the first developed use of the Phase One Property was based on a review of available aerial photographs, historical maps, city directories, and interviews. Based on the information obtained, the first developed use of the Phase One Property was circa 2004 for the development of the maintenance department (Building A) of the golf club.

3.1.3 Fire Insurance Plans

Fire insurance plans were prepared between 1875 and 1923 and revised in some areas until the 1970s. A search of Fire Insurance Plans (FIPs) was undertaken at the Metropolitan Toronto Reference Library and City Toronto's online services. FIPs were reviewed to confirm the building construction, occupancy, and potential fire hazardous with details regarding storage tanks, boilers, transformers, electrical room, etc. No FIPs were available for The Phase One Property and the properties located in the Study Area.

3.1.4 Chain of Title

A chain of title search was not prepared as part of this Phase One ESA. It is noted that a chain of title for the Phase One Property from the date of patent to present will be required before an RSC can be filed for the property. Information related to the historical occupants was obtained from other sources (i.e. city directories, interviews).

3.1.5 Environmental Reports

There were no previous environmental reports available to review.

3.1.6 City Directories

City Directories for the years 1998, 1991, 1996, and 2000 were reviewed at the Metropolitan Toronto Reference Library. The Phase One Property was listed at 4252 Dundas Street as Millcroft Golf Club Maintenance Dept in the 1996 directory. The adjacent properties generally appear to have been developed by the late 1980s for residential purposes. After reviewing the directories, it was noted by DS that there are no potential environmental concerns on the Phase One Property and the Phase One Study Area.

After complete summary of the City Directory listings reviewed has been included under Appendix B.

3.2 Environmental Source Information

3.2.1 Ecolog Eris Report

EcoLog Environmental Risk Information Services Ltd. (ERIS) is an organization that maintains and searches various government and private databases for property-related environmental information.

DS contacted EcoLog Environmental Risk Information Services Ltd. (EcoLog ERIS), an environmental database and information service company, to request a search of government and private records for information pertaining to the Phase One Property and Phase One Study Area. EcoLog searched 15 Federal databases, 37 Provincial databases and 10 private databases. A summary of the databases provide by ERIS is provided in the Table below:

Table 3-1: Summary of Environmental Databases Reviewed

Federal Government Source Databases	Private Source Databases
Contaminated Sites on Federal Land; Environmental Effects Monitoring; Environmental Issues Inventory System; Federal Convictions; Fisheries & Oceans Fuel Tanks; Indian & Northern Affairs Fuel Tanks; National Analysis of Trends in Emergencies System (NATES); National Defense & Canadian Forces Fuel Tanks; National Defence & Canadian Forces Spills; National Defence & Canadian Forces Waste Disposal Sites; National Environmental Emergencies System (NEES); National PCB Inventory; National Pollutant Release Inventory; Parks Canada Fuel Storage Tanks; and Transport Canada Fuel Storage Tanks.	Anderson's Storage Tanks; Anderson's Waste Disposal Sites; Automobile Wrecking & Supplies; Canadian Mine Locations; Canadian Pulp and Paper; Chemical Register; ERIS Historical Searches; Oil and Gas Wells; Retail Fuel Storage Tanks; and Scott's Manufacturing Directory.
Provincial Government Source Databases	
Abandoned Aggregate Inventory; Abandoned Mine Information System; Aggregate Inventory; Borehole; Certificates of Approval; Certificates of Property Use; Commercial Fuel Oil Tanks; Compliance and Convictions; Drill Hole Database; Environmental Activity and Sector Registry; Environmental Compliance Approval; Environmental Registry; Fuel Storage Tank; Fuel Storage Tank – Historic; Inventory of Coal Gasification Plants and Coal Tar Sites; TSSA Historic Incidents; TSSA Incidents; TSSA Pipeline Incidents; TSSA Variances for Abandonment of Underground Storage Tanks;	Inventory of PCB Storage Sites; Landfill Inventory Management Ontario; List of TSSA Expired Facilities; Mineral Occurrences; Non-Compliance Reports; Ontario Oil and Gas Wells; Ontario Regulation 347 waste Generators Summary; Ontario Regulation 347 Waste Receivers Summary; Ontario Spills; Orders; Permit to Take Water; Pesticide Register; Private and Retail Fuel Storage Tanks; Record of Site Condition; Waste Disposal Sites – MECP 1991 Historical Approval Inventory; Waste Disposal Sites – MECP CA Inventory; Wastewater Discharger Registration Database; and Water Well Information System

The ERIS report indicated that there were fourteen (14) records for the Phase One Property, and eight (8) records for the remaining properties within the Phase One Study Area. A copy of the ERIS report has been provided under Appendix C. A summary of the pertinent details identified in the ERIS report is provided in the Table below:

Table 3-2: Summary of ERIS Report Findings on Phase One Property and Phase One Study Area

Database/Date	Entry Details	PCA ID No.
Ontario Regulation 347 Waste Generator Summary (GEN)	Fourteen (14) entries were available for the Phase One Property. The Phase One Property was registered as waste generator of: - petroleum distillates, waste oils, and lubricants from 1994 to as of July 2019; - Aliphatic solvents and residues from 1999 to as of July 2019; and - Non-halogenated lean organics from 1999 to 2008.	PCA-1

Table 3-3: Summary of ERIS Report Findings within Phase One Study Area

Database/Date	Entry Details	PCA ID No.
Ontario Regulation 347 Waste Generator Summary (GEN)	Five (5) entries were available for the Phase One Study Area: - Frank J. Hayden Secondary School – Halton District School Board, located at 3040 Tim Dobbie Drive approximately 249 m west of the Phase One Property was listed as a generator of inorganic Laboratory Chemicals, waste oils and lubricants, acid waste- heavy metals, and aliphatic solvents from 2016 to as of July 2019. Waste oil/sludges, and waste crankcase oil and lubricants from 2018 to as of July 2019	PCA-2
TSSA historic Incidents (HINC)	One (1) entry was available at 4400 Millcroft Drive, Unit 9 for the strike of a natural gas pipeline.	No PCA

3.2.2 Ministry of the Environment- Freedom of Information

A request was submitted to the MECP Freedom of Information and Protection of Privacy Office (Appendix D) to determine if there were any environmental incidents or violations associated with the Phase One Property; whether any Control Orders have been issued; whether there have been any other environmental concerns associated with the property such as complaints, inspections, etc.; whether any environmental investigations have been carried out regarding the subject property; and, to determine if the Ministry's Spills Action Centre's (SAC's) files contain any reported spills that had occurred in the site vicinity. Note that the SAC's database dates back only to 1988 and many of the occurrences on file have only been reported voluntarily. In addition, the MECP was requested to search their files (all years) regarding the following parameters: air emissions, water, sewage, wastewater and pesticides.

Files pertinent to this investigation would include, though are not limited to: regulatory permits, records; material safety data sheets; underground utility drawings; inventories of chemicals, chemical usage and chemical storage areas; inventory of aboveground storage tanks and underground storage tanks; monitoring data, including that done at the request of the MECP; historical and current waste management, receiver and generator records; process, production and maintenance documents related to areas of potential environmental concern; spills/discharge

records; emergency and contingency plans; environmental audit reports; site plan of facility showing areas of production and manufacturing.

A response has not yet been received from the MECP. The client will be made aware of any records identified by the MECP file search, when a response is received from the Ministry.

3.2.3 Technical Standards and Safety Authority

The Technical Standards and Safety Authority (TSSA) maintain records related to storage tanks for petroleum related products. The TSSA was contacted to review records related to the Property and Study Area. According to the response received on October 22, 2019 from Ms. Gaya of TSSA, there were no records for the Phase One Property and properties located in the Study Area.

A copy of the correspondence with the TSSA has been appended under Appendix D.

3.2.4 Areas of Natural and Scientific Interest

The Natural Heritage Areas database published by the Ministry of Natural Resources (MNR) was reviewed in order to identify the presence/absence of areas of natural significance including provincial parks, conservation reserves, areas of natural and scientific interest, wetlands, environmentally significant areas, habitats of threatened or endangered species, and wilderness areas. The regional and municipal Official Plans were also reviewed as part of this assessment.

No areas of natural or scientific interest were identified within the Phase One Study Area.

3.2.5 Conservation Halton

According to Conservation Halton online mapping system, no watercourse is presented on the Property, but there are two (2) creeks, Sheldon Creek to the east, and a tributary to Appleby Creek to the west of the Phase One Study Area. The Phase One Property is located in between the Sheldon Creek and Appleby Creek watersheds.

3.3 Physical Setting Sources

3.3.1 Aerial Photographs and Historical Mapping

Aerial Photographs for the years 1995, 2002, 2001, and 2015 were obtained from the City of Burlington Online Mapping and Aerial Photographs for the years 1954, 1962, and 1972 were obtained from ERIS Historical Aerials services, and the photograph from 1987 was obtained from Halton Public Works to be reviewed as part of this assessment. The County Atlas of Halton was reviewed in order to provide a more historical image from the year 1880. A summary of pertinent information obtained from the aerial photographs reviewed is presented in the Table below. The supporting documents have been appended under Appendix E.

Table 3-4: Summary of Aerial Photographs

Year	Phase One Property	Phase One Study Area	PCA Identification No.
1880 County Atlas Map	The county atlas map indicates that the Phase One Property belonged to Ja. McKerlie and appears to be undeveloped. It is inferred that the property was used for agricultural purposes at this time.	The Phase One Study Area appears to be undeveloped agricultural land.	No PCA identified.
1954	The Phase One Property appears to be part of an agricultural field. An access roadway is visible running north-south near the western edge of the Phase One Property.	A rural farmhouse is visible on the north side of Dundas. The remaining lands appear to have been used for agricultural purposes.	No PCA identified.
1962	No significant changes.	No significant chances.	No PCA identified.
1972	No significant changes.	No significant chances.	No PCA identified.
1987	Property appears to have been reworked due to the development of the golf course at the adjacent property. Possible fill material may have been used for grading purposes.	Development of the Millcroft Golf Club appears to be underway.	PCA-3: Importation of fill material of unknown quality.
1995	Property appears to be undeveloped	A hole of the golf course appears to have been completed to the south.	PCA-9: Inferred use of pesticides/herbicides on golf course.
2002	No significant changes	No significant changes.	No PCA
2005	A building has been developed in the Property. The building appears to be in the current configuration, likely used as storage and maintenance.	No significant changes.	PCA-1: storage and maintenance shed
2011	No significant changes	Multiple residential dwelling west adjacent to the Phase One Property has been developed.	No PCA
2017	No significant changes	The football field located to the north in Norton Community Park has been developed.	No PCA
2019	No significant changes	No significant changes	No PCA

3.3.2 Topography, Hydrology, Geology

The topography of the Phase One Property is generally flat, with a surface elevation of 155 metres above sea level (masl). The topography within the Phase One Study Area generally slopes to the east, towards Lake Ontario, located approximately 7 km southeast of the Phase One Property. The nearest water bodies are Sheldon Creek, located to the east, approximately 340 m from the Property, and Appleby Creek, located approximately 330 m west from the Property. The majority of the shallow groundwater flow within the Phase One Study Area is inferred to be southwest towards Appleby Creek.

The Site is situated within a south slope physiographic region. The surficial geology within the Phase One Study area is described as "till plains (drumlinized), and the bedrock is described as shale, limestone, dolostone, and siltstone" of the Queenston Formation. Based on a review of MECP Well Records on the vicinity of the Property, the bedrock in the Phase One Study Area is anticipated to be encountered at an approximate depth of 8 mbgs.

3.3.3 Fill Materials

According to observed aerial photograph fill material may have been imported around 1987 for landscaping and/or grading purposes.

3.3.4 Water Bodies and Areas of Natural Significance

During the site visit, standing water was not observed on the Property. The nearest body of water to the Phase One Property are Sheldon Creek, located approximately 340 m to the east, and Appleby Creek, located approximately 330m to the west. Environmentally Significant Areas are natural areas that have been identified as significant and worthy of protection on three criteria – ecology, hydrology and geology. Municipalities has developed policies to protect natural heritage features. The Region uses Environmentally Significant Areas as a means to protect natural areas like wetlands, fish habitat, woodlands, habitat of rare species, groundwater recharge and discharge areas, and Areas of Natural and Scientific Interest.

The Property includes no Areas of Natural Significance. Additional details are provided in Section 3.2.4.

3.3.5 Well Records

Water well records were also searched as part of the EcoLog ERIS database query. Two (2) records were available for the Phase One Property. One is abandoned (well ID: 7050862), and the second is used as a domestic water supply (well ID: 2803185). Based on a review of the previous reports available for the Site, there are no monitoring wells present on the Phase One Property.

Additional detail regarding the well construction, lithology encountered, and well purpose is included in the ERIS report provided under Appendix C.

3.4 Site Operating Records

The Property has mainly been used for maintenance and storage purposes. No operating records were available.

4.0 Interviews

4.1 Personnel Interviewed

The following persons with the knowledge of the Property were interviewed or provided the required information.

Table 4-1: Summary of Personnel Interviewed

Date	Name	Affiliation	Position	Method of Interview
November 25, 2019	Martin Kastrov	Millcroft Golf Club	Superintendent	In Person

4.2 Interviewee Rationale

Millcroft Golf Club is the current occupant of the Site and has been responsible for site operations since 1987. Mr. Kastrov is the superintendent of the Millcroft Golf Club and is considered to be a knowledgeable person regarding the historical site operations. The Phase One Interview was conducted by Mr. John Gaviria-Ballen, B. Eng., EIT under the supervision of Mr. Patrick Fioravanti, B.Sc., P.Geo., QP_{ESA}.

4.3 Results of Interview

The following summarizes the information that was provided by the site representative, based on their knowledge of site activities.

- The Phase One Property has been developed circa 2004.
- According to Mr. Kastrov the Property has been used as a maintenance building for golf cars and lawnmowers since the building was constructed in 2004.
- One (1) hydraulic hoist was located on the south center portion of Building A **(PCA-1).**
- There were three (3) AST on the property **(PCA-4)**:
    - One (1) 22,000 L diesel UST
    - One (1) 22,000 L gasoline UST
    - One (1) ~20,000 L waste oil UST
- There was one (1) oil/water separator installed underground at the north portion of Building **(PCA-8).**
- A bulk of batteries were store on a pallet at the entrance of the maintenance area **(PCA-7)**.
- No information was available for the Property if cited for violations of any provincial or federal environmental laws or regulations.
- No information for individuals with additional knowledge of the Property was available to interview.

DS compared the information obtained through the Phase One Interview with the information obtained from the historical records for the Site. The information provided by the interviewee was corroborated by the historical records, as such DS has no concern regarding the accuracy of the information provided.

5.0 Site Reconnaissance

5.1 General Requirements

Table 5-1: Site Reconnaissance Notes

Information	Details
Date of Investigation:	November 25, 2019
Time of Investigation:	10:30 am
Weather Conditions:	Cloudy
Duration of Investigation:	1 hour
Facility Operation:	Millcroft Golf Club – Maintenance Department
Name and Qualification of Person(s) conducting the assessment	John Gaviria-Ballen, B. Eng., EIT under the supervision of Mr. Patrick Fioravanti, B. Sc., P. Geo., QP_{ESA}
Limitations	No limitations

5.2 Specific Observations at Phase One Property

The Site Reconnaissance involved a visual assessment of the Phase One Property for the purpose of identifying potential PCAs, and associated APECs. Photographs of the Phase One Property were taken at the time of the Site Reconnaissance, and have been included under Appendix F.

Table 5-2: Summary of Site Reconnaissance Observations

General		
i.	Description of structures and other improvements, including the number and age of buildings	One (1), one-story vertical metal siding exterior walls, with concrete block and drywall interior walls, constructed by 2004
ii.	Description of the number, age and depth of below-ground structures	The building is a slab on grade floor with no basement.
iii.	Details of all tanks, above and below ground at the Phase One Property, including the material and method of construction of the tank, tank age, tank contents, tank volume, and whether in use or not	Three ASTs are present in the Property: - One (1) 22,000L gasoline tank, - One (1) 22,000L diesel tank, - One (1) ~20,000L waste oil tank, and - One (1) barrel of lubricant oil They gasoline, diesel and lubricant tanks were rested on a concrete slab in general good conditions. The waste oil tank was found to be in fair to poor condition and rusted. They were all located east of Building A (**PCA-4**).

iv.	Potable and non-potable water sources	The Phase One Property is serviced by municipal water services.
Underground Utilities and Corridors		
i.	Type and location of underground utility and service corridors, such as sewer, water, electrical or gas lines located on, in or under the Phase One Property.	The Phase One Property has a sewer septic system that is located north of the Property. The exact location of other services is unknown.
Features of Structures and Buildings at the Phase One Property		
i.	Entry and exit points	Present on the north east sides of the Phase One Property.
ii.	Details of existing and former heating systems, including type and fuel source	The building is heated using an HVAC system that uses natural gas as fuel source.
iii.	Details of cooling systems, including type and fuel source, if any	The building does not have a cooling system.
iv.	Details of any drains, pits and sumps, including their current use, if any, and former use	None observed.
v.	Details of any unidentified substances	None observed
vi.	Details, including locations of strains or corrosion on floors other than from water, where located near a drain, pit, sump, crack or other potential discharge location	None observed.
vii.	Details, including locations, of current and former wells, including all wells described or defined in or under the *Ontario Water Resources Act* and the *Oil, Gas and Salt Resources Act*	None observed.
viii.	Details of sewage works, including their location	Building A is connected to a septic tank system that is located north adjacent of the building. The Property does not have connection to the municipal sanitary sewer.
ix.	Details of ground surface, including type of ground cover, such as grass, gravel, soil or pavement	The ground surroundings Site Building A is primarily gravel or fill material. The remaining ground surface was covered by grass and vegetation.
x.	Details of current or former railway lines or spurs and their locations	None observed.
xi.	Areas of stained soil, vegetation or pavement	None observed.
xii.	Stressed vegetation	None observed.
xiii.	Areas where fill and debris materials appear to have been placed or graded	Surrounding Building A and the access point to the Property.

xiv. Potentially contaminating activity	• One (1) hydraulic hoist was observed on Building A, and the building is used for maintenance of golf cars and lawnmowers during the Site reconnaissance (**PCA-1**). • Three ASTs are present in the Property (**PCA-4**),: - One (1) 22,000L gasoline tank - One (1) 22,000L diesel tank, - One (1) ~20,000L waste oil tank, and - One (1) barrel of lubricant oil • One room is used as storage for pesticides during the site reconnaissance (**PCA-5**). • One (1) transformer was located on Building A, located on the salve on grade floor at the west portion of Building A (**PCA-6**). • One pallet with car batteries was observed at the entrance of the maintenance area (**PCA-7**). • One (1) oil/water separator was located on the north of Building A, installed above the slab on grade floor (**PCA-8**).
xv. Details of any unidentified substances found at the Phase One Property	None observed.
Enhanced Investigation Property	
Where subsection 13(3) applies to the Phase One Property, provide the documentation referred to in subsection 13(3)	In order to be classified as an enhanced investigation property, the Phase One Property must be used or have been used in whole or in part for any of the following uses: ◆ Any industrial use ◆ As a garage ◆ As a bulk liquid dispensing facility, including a gasoline outlet ◆ For the operation of dry-cleaning equipment There is no indication in the historical records of the Phase One Property being used for any of the aforementioned uses, and as such the Phase One Property is not considered an enhanced investigation property.
Hazardous Materials	
i. Asbestos containing materials	Asbestos and asbestos-containing materials were used as insulation and construction materials until being phased out in the late 1970s. Based on the age of the site building, which was constructed by 2004, the potential for asbestos insulation and asbestos-containing construction materials to be present in the site building is considered to be low.

ii.	Lead containing materials	The use of lead as a base in paints and plumbing solder was phased out in the late 1970s. Based on the age of the building, there is no potential for lead solder and paint to be present in the site building.
iii.	PCB materials and equipment	Prior to the mid- to late-1970s, PCBs were used in the manufacture of electrical equipment, including fluorescent light ballasts. The Property was constructed after the 1970s; thus, it has low potential for presence of PCBs material. However, a transformer is located on the west portion of Building A (**PCA-6**).
iv.	Urea Formaldehyde Foam Insulation (UFFI)	Urea-Formaldehyde Foam Insulation (UFFI) was introduced in Canada during the 1970s and was banned in 1980. Based on the age of the building, there is no potential for UFFIs to be present within the building.
v.	Ozone Depleting Substances (ODS)	None observed
vi.	Herbicides and Pesticides	During the site reconnaissance, one room located northeast of Building A was allocated for pesticides storage **(PCA-9).**
vii.	Mould	None observed.
viii.	Mercury	Based on the age of the building, there is potential for mercury to be present in fluorescent lights observed in the building. Mercury with small quantity could be present inside the electrical switches or thermostats observed in the units of the building.
ix.	acrylonitrile, arsenic, benzene, coke oven emissions, ethylene oxide, isocyanates, silica, vinyl chloride	These items were not observed at the Property.
x.	Pits and Lagoons	None observed
xi.	Air Emissions	None observed
xii.	Radioactive Materials & Radon Gas	Based on local geological formations in the area, it is unlikely the site is exposed to natural sources of radiation such as radon or uranium. Manmade sources of radioactive materials were not observed during the site inspection. A radiometric survey was not conducted during this investigation.

5.3 Written Description of Investigation

The site reconnaissance included a visual inspection of the Phase One Property to confirm current conditions and identify any current land uses or activities, which may have or may cause environmental impacts. The adjoining and neighbouring properties were observed from the Phase One Property and publicly accessible areas.

At the time of the Site Reconnaissance the land use within the Phase One Study Area was primarily residential, and parkland, as described in the table below:

Table 5-3: Summary of Site Reconnaissance Observations within Phase One Study Area

Observation	Details
Phase One Property	The Phase One Property was occupied by Millcroft Golf Club at the time of the site reconnaissance, the building located on the Property was used for maintenance of equipment and golf carts. The orientation of the Site Building is depicted on Figure 2.
North Adjacent Property	The north adjacent Property was occupied by Norton park at the time of the site reconnaissance.
East Adjacent Property	The east adjacent Property was open vacant space covered by grass at the time of the site reconnaissance.
South Adjacent Property	The south adjacent Property was occupied by Millcroft Golf Club and was used as a golf course (hole 15) at the time of the site reconnaissance (**PCA-9**).
West Adjacent Property	The west adjacent Property was occupied by residential homes at the time of the site reconnaissance.
Water Bodies	Appleby Creek was observed approximately330 m to the west, and Sheldon Creek was observed approximately 340 m to the east of the Phase One Property.
Areas of Natural Significance	None observed.

Photographs illustrating the Phase One Property and adjacent properties are provided under Appendix F. A summary of the potentially contaminating activities observed is provided in Section 6.2. A visual depiction of the PCAs identified within the Phase One Study Area is provided under Figure 4.

6.0 Review and Evaluation of Information

6.1 Current and Past Uses

Current and past uses of the Phase One Property have been inferred based on the information provided in the aerial photographs, chain of title, city directories and conversations with the site representative. Based on the records reviewed, the Phase One Property appears to have been used for agricultural purposes from the late 1800s until 2004, at which point the site was developed with the current maintenance building, serving the Millcroft Golf Club.

6.2 Potentially Contaminating Activity

According to the Table 2, Schedule D, O. Reg. 153/04 as amended, potentially contaminating activities are activities that may be contributing to areas of potential environmental concern on the Phase One Property. The PCAs identified on the Phase One Property and within the Phase One Study Area are summarized in the table below and are illustrated on Figure 4.

Table 6-1: Summary of PCAs

PCA Item.	PCA Description (Per. Table 2, Schedule D of O.Reg. 153/04)	Description	Contributing to APEC (Y/N)
PCA-1	# 27: Garages and Maintenance and Repair of Railcars, Marine Vehicles and Aviation Vehicles	- One (1) hydraulic hoist was observed on Building A, on the building am area is used for maintenance of golf cars and lawnmowers during the Site reconnaissance. - The Phase One Property was registered as a waste generator of petroleum distillates, waste oils, lubricants, and aliphatic solvents and residues.	Yes – APEC-1
PCA-2	#58: Waste Disposal and Waste Management, including thermal treatment, landfill and transfer of waste, other than use of biosolids as soil conditioners.	Frank J. Hayden Secondary School – Halton District School Board, located at 3040 Tim Dobbie Drive approximately 249 m west of the Phase One Property was listed as a generator of inorganic laboratory chemicals, waste oils and lubricants, acid waste- heavy metals, aliphatic solvents, and waste oil/sludges, and waste crankcase oil.	No – Based on source of waste generation, effect to the Property is unlikely
PCA-3	#30: Importation of Fill Material of Unknown Quality	Fill material is inferred to have been placed for grading purposes when the Phase One Property started development around 1987 around Building A, and stockpiles of sand, topsoil and tee mix was observed during the site reconnaissance north of the Property.	Yes – APEC-2
PCA-4	#28: Gasoline and Associated Products Storage in Fixed Tanks	Three ASTs are present in the Property: - One (1) 22,000L gasoline tank, - One (1) 22,000L diesel tank, - One (1) ~20,000L waste oil tank, and - One (1) barrel of lubricant oil	Yes – APEC-3
PCA-5	#40: Pesticides (including Herbicides, Fungicides and Anti-Fouling Agents) manufacturing, Processing, Bulk Storage and large-Scale Applications	One room is used as storage for pesticides during the site reconnaissance.	Yes – APEC-4
PCA-6	#28: Transformer Manufacturing, Processing and Use	One (1) transformer was located on Building A, located on the salve on grade floor at the west portion of Building A.	Yes- APEC-5
PCA-7	#6: Battery Manufacturing, Recycling and Bulk Storage	One pallet with car batteries was observed during the site reconnaissance.	Yes – APEC-7
PCA-8	# N/S: Oil/water separator.	One (1) oil/water separator was located on the north of Building A, installed above the slab on grade floor.	Yes-APEC-6
PCA-9	#40: Pesticides (including Herbicides, Fungicides and Anti-Fouling Agents) manufacturing, Processing,	Inferred application of pesticides/herbicides on Millcroft Golf Club (located to the south of the Phase One Property).	No – based on down/transgradient hydraulic orientation relative

PCA Item.	PCA Description (Per. Table 2, Schedule D of O.Reg. 153/04)	Description	Contributing to APEC (Y/N)
	Bulk Storage and large-Scale Applications		to the Phase One Property.

N/S - not specified in Table 2, Schedule D, of O.Reg. 153/04

6.3 Areas of Potential Environmental Concern

The table of APECs presented in the form as approved by the Director is provided below, in accordance with clause 16(2)(a), Schedule D, O.Reg. 153/04.

Table 6-2: Areas of Potential Environmental Concern

Area of Potential Environmental Concern	Location of APECs on Phase One Property	Potentially Contaminating Activity	Location of PCA (on-site or off-site)	Contaminants of Potential Concern	Media Potentially Impacted (Ground water, soil and/or sediment)
APEC-1	Surroundings of Building A	PCA-1 (# 27: Garages and Maintenance and Repair of Railcars, Marine Vehicles and Aviation Vehicles	On Site	PHC, BTEX VOCs, Metals	Soil and groundwater
APEC-2	Entire Property	PCA-3 (#30): Importation of Fill Material of Unknown Quality	On Site	PHCs, VOCs, BTEX, Metals, As, Sb, Se, B-HWS, CN-, electrical conductivity, Cr (VI), Hg, low or high pH, SAR, PAHs	Soil
APEC-3	Centre portion of the Property	PCA-4 (#28): Gasoline and Associated Products Storage in Fixed Tanks	On Site	PHCs, VOCs, BTEX, Metals,	Soil and ground water
APEC-4	Northeast corner of Building A	PCA-5 (#40): Pesticides (including Herbicides, Fungicides and Anti-Fouling Agents) manufacturing, Processing, Bulk Storage and large-Scale Applications	On Site	OCPs	Soil and ground water
APEC-5	Southwest portion of Building A	PCA-6 (#28): Transformer Manufacturing, Processing and Use	On Site	PCBs	Soil
APEC-6	Surroundings of Building A	PCA-8 (#N/S): Oil/water separator.	On Site	PHC, BTEX VOCs, Metals	Soil and groundwater

Area of Potential Environmental Concern	Location of APECs on Phase One Property	Potentially Contaminating Activity	Location of PCA (on-site or off-site)	Contaminants of Potential Concern	Media Potentially Impacted (Ground water, soil and/or sediment)
APEC-7	Surroundings of Building A	PCA-7 (#6): Battery Manufacturing, Recycling and Bulk Storage	On Site	PHC, BTEX VOCs, Metals	Soil and groundwater

The rationale used by the QP in assessing the information obtained through the course of this investigation to determine whether PCAs exist and/or are contributing to an APEC on the Phase One Property has been provided in the proceeding sections. In general the potential for a PCA to be contributing to an APEC on the Phase One Property was assessed using the likelihood of the source to contaminate the Phase One Property, the possibility of the contaminants to migrate to the Phase One Property based on the hydraulic and geologic conditions, and the inherent properties of the contaminants of concern.

The contaminants of potential concern were determined based on the professional experience of the QP, common industry standards, literature reviews, and the inherent properties of the contaminant.

This investigation was conducted based on the assumption that all information provided to DS was factual and accurate. DS is not aware of any uncertainty factors which would affect the conclusions of this investigation.

6.4 Phase One Conceptual Site Model

A Conceptual Site Model was developed for the Phase One Property, located at "Block E" of the Millcroft Golf Club in Burlington, Ontario. The Phase One Conceptual Site Model is presented in Drawings 3, 4, and 5 and visually depict the following:

- Any existing buildings and structures
- Water bodies located in whole, or in part, on the Phase One Study Area
- Areas of natural significance located in whole, or in part, on the Phase One Study Area
- Water wells at the Phase One Property or within the Phase One Study Area
- Roads, including names, within the Phase One Study Area
- Uses of properties adjacent to the Phase One Property
- Areas where any PCAs have occurred, including location of any tanks
- Areas of Potential Environmental Concern

6.4.1 Potentially Contaminating Activity Affecting the Phase One Property

All PCAs identified within the Phase One Study Area are presented on Figure 4 and discussed in Section 7.2 above. The PCAs which are considered to contribute to APECs on, in or under the Phase One Property are summarized in the table below:

Table 6-3: Summary of PCAs Contributing to APECs

PCA Item.	PCA Description (Per. Table 2, Schedule D of O.Reg. 153/04)	Description	Rationale
PCA-1	# 27: Garages and Maintenance and Repair of Railcars, Marine Vehicles and Aviation Vehicles	The Phase One Property was registered as a waste generator of petroleum distillates, waste oils, lubricants, and aliphatic solvents and residues.	PCA is located on the Phase One Property
PCA-3	# 30: Importation of Fill Material of Unknown Quality	Fill material is inferred to have been placed for grading purposes when the Phase One Property started development around 1987 around Building A, and stockpiles of sand, topsoil and tee mix was observed during the site reconnaissance north of the Property.	PCA is located on the Phase One Property
PCA-4	#28: Gasoline and Associated Products Storage in Fixed Tanks	Three ASTs are present in the Property: - One (1) 22,000L gasoline tank, - One (1) 22,000L diesel tank, - One (1) ~20,000L waste oil tank; and - One (1) barrel of lubricant oil	PCA is located on the Phase One Property
PCA-5	#40: Pesticides (including Herbicides, Fungicides and Anti-Fouling Agents) manufacturing, Processing, Bulk Storage and large-Scale Applications	One room is used as storage for pesticides during the site reconnaissance.	PCA is located on the Phase One Property
PCA-6	#28: Transformer Manufacturing, Processing and Use	One (1) transformer was located on Building A, located on the salve on grade floor at the west portion of Building A.	PCA is located on the Phase One Property
PCA-7	#6: Battery Manufacturing, Recycling and Bulk Storage	One pallet with car batteries was observed during the site reconnaissance.	PCA is located on the Phase One Property
PCA-8	# N/S: Oil/water separator.	One (1) oil/water separator was located on the north of Building A, installed above the slab on grade floor.	PCA is located on the Phase One Property

N/S - not specified in Table 2, Schedule D, of O.Reg. 153/04

6.4.2 Contaminants of Potential Concern

A summary of the contaminants of potential concern identified for each respective APEC is presented in Table 6-3 above. The following contaminants of potential concern were identified for the Phase

One Property: PHCs, VOCs, BTEX, Metals, As, Sb, Se, B-HWS, CN-, EC, Cr (VI), Hg, low or high pH, SAR, PAHs, PCBs, and OCPs.

6.4.3 Underground Utilities and Contaminant Distribution and Transport

Underground utilities can affect contaminant distribution and transport. Trenches excavated to install utility services, and the associated granular backfill may provide preferential pathways for horizontal contaminant migration in the shallow subsurface.

No utility services were identified on the Phase One Property. The depth to groundwater at the Phase One Property is inferred to be approximately 1.5 mbgs; since there is no utilities on the Property there is no corridors that would not act as preferential pathways for contaminant distribution and transport in the event that shallow subsurface contaminants exist at the Phase One Property.

6.4.4 Geological and Hydrogeological Information

The topography of the Phase One Property is generally flat with a surface elevation of 155 masl. The topography within the Phase One Study Area generally slopes to the east, towards Lake Ontario, located approximately 7 km southeast of the Phase One Property. The nearest water bodies are Sheldon Creek, located to the east, approximately 340 m from the Property, and Appleby Creek, located approximately 330 m west from the Property. Based on a review of borehole logs and the MECP well records, the depth to groundwater in the vicinity of the Phase One Property is approximately 1.5 mbgs. The majority of the shallow groundwater flow within the Phase One Study Area is inferred to be southwest towards Appleby Creek.

The Site is situated within a south slope physiographic region. The surficial geology within the Phase One Study area is described as “till plains (drumlinized)”, and the bedrock is described as “shale, limestone, dolostone, and siltstone” of the Queenstone Formation. Based on a review of MOECP Well Records on the vicinity of the Property, the bedrock in the Phase One Study Area is anticipated to be encountered at an approximate depth of 8 mbgs.

6.4.5 Uncertainty and Absence of Information

DS has relied upon information obtained from federal, provincial, municipal, and private databases, in addition to records and summaries provided by EcoLog ERIS. All information obtained was reviewed and assessed for consistency; however, the conclusions drawn by DS are subject to the nature and accuracy of the records reviewed.

All reasonable inquiries were made to obtain reasonably accessible information, as mandated by O.Reg.153/04 (as amended). All responses to database requests were received prior to completion of this report, with the exception of the MECP FOI request. If the MECP FOI request produces information which may alter the conclusions of this report, an addendum will be provided to the

Client. This report reflects the best judgement of DS based on the information available at the time of the investigation.

Information used in this report was evaluated based on proximity to the Phase One Property, anticipated direction of local groundwater flow, and the potential environmental impact on the Phase One Property as a result of potentially contaminating activities.

The QP has determined that the uncertainty dose not affect the validity of the Phase One ESA Conceptual Site Model or the conclusions of this report.

7.0 Conclusions

7.1 Phase Two Environmental Site Assessment Requirement

DS conducted a Phase One ESA for the property referred to as "Block E" located at Millcroft Golf Club, Burlington, Ontario. The Phase One ESA was completed to satisfy the intent of the requirements, methodology and practices for a Phase One ESA as described in Ontario Regulation 153/04 (as amended). The objectives of the Phase One ESA was to identify the presence or absence of potentially contaminating activities (PCAs) on the Phase One Property and/or within the Phase One Study Area, and to determine if the PCAs identified within the Phase One Study Area are likely to result in an Area of Potential Environmental Concern (APEC) on the Phase One Property.

Based on the information obtained as part of this investigation, it is concluded that nine (9) PCAs were identified within the Phase One Study Area which are considered to be contributing to seven (7) APECs on, in or under the Phase One Property. Further investigation in the form of a Phase Two ESA will be required in order to meet the requirements of O.Reg.153/04 (as amended).

7.2 RSC Based on Phase One Environmental Site Assessment

Record of Site Condition cannot be filed on the basis of the Phase One ESA due to the identification of Areas of Potential Environmental Concern on the Phase One Property.

7.3 Limitations

This report was prepared for the sole use of Millcroft Greens Corporation and is intended to provide an assessment of the environmental condition on the property known as Block E, located at Millcroft Golf Club, Burlington, Ontario. The information presented in this report is based on information collected during the completion of the Phase One Environmental Site Assessment by DS Consultants Ltd. The material in this report reflects DS' judgment in light of the information available at the time of report preparation. This report may not be relied upon by any other person or entity without the written authorization of DS Consultants Ltd. The scope of services performed in the execution of this investigation may not be appropriate to satisfy the needs of other users, and any use or reuse of this

documents or findings, conclusions and recommendations represented herein, is at the sole risk of said users.

The information and conclusions presented in this report are professional opinions in accordance with generally accepted engineering and scientific practices based on a cursory historical search, visual observations and limited information provided by persons knowledgeable about past and current activities on this site. The work completed as per the scope of work is considered sufficient in detail to form a reasonable basis for the findings presented in this report. As such, DS Consultants Ltd. cannot be held responsible for environmental conditions at the site that was not apparent from the available information.

7.4 Qualifications of the Assessors

John Gaviria-Ballen, B. Eng., EIT

Mr. Gaviria-Ballen is an environmental technician with DS Consultants Ltd. John holds a bachelor's degree in Environmental Engineering from Carleton University. John has experience in conducting Phase One and Two Environmental Site Assessments.

Mr. Drew Doak, B.Sc.E., P.Eng., QP_{ESA}

Mr. Doak is an Environmental Project Manager with DS Consultants Limited. Drew holds a Bachelor of Science in Engineering from Queen's University, and is a practicing member of the Professional Engineers of Ontario (PEO). Drew has five years of environmental consulting experience and has conducted and/or managed a multitude of projects in his professional experience. Drew has extensive experience conducting Phase One and Phase Two Environmental Site Assessments in support of brownfields redevelopment in urban settings, and been involved in numerous remediation projects, and supported many risk assessments and Records of Site Conditions with the Ministry of Environment, Conservation and Parks. He has also conducted a variety of Hydrogeological investigations within the GTA. Drew is considered a Qualified Person to conduct Environmental Site Assessments as defined by Ontario Regulation 153/04 (as amended).

Mr. Patrick (Rick) Fioravanti, B.Sc., P.Geo., QP_{ESA}

Mr. Fioravanti an Environmental Project Manager with DS Consultants Limited. Patrick holds a Honours Bachelor of Science with distinction in Toxicology from the University of Guelph, and is a practicing member of the Association of Professional Geoscientists of Ontario (APGO). Patrick has over seven years of environmental consulting experience and has conducted and/or managed over 100 projects in his professional experience. Patrick has extensive experience conducting Phase One and Phase Two Environmental Site Assessments in support of brownfields redevelopment in urban settings, and been involved in numerous remediation projects, supported many risk assessments, and successfully filed Records of Site Condition with the Ministry of Environment, Conservation and Parks. He has conducted work across southern and eastern Ontario, and Quebec in his professional

experience. Patrick is considered a Qualified Person to conduct Environmental Site Assessments as defined by Ontario Regulation 153/04 (as amended).

7.5 Signatures

DS Consultants Ltd. conducted this Phase One Environmental Site Assessment and confirms the findings and conclusions contained within this report.

Yours truly,

DS Consultants Ltd.

Prepared by:



John Gaviria-Ballen, B. Eng., EIT
Environmental Technician

Reviewed by:



Drew Doak, B.Sc.E., P.Eng., QP_{ESA}
Environmental Project Manager



Patrick Fioravanti, B.Sc., P.Geo., QP_{ESA}
Manger – Environmental Services




8.0 References

- Ontario Regulation 153/04 Records of Site Condition — Part Xv.1 of The Act
- Natural Resources Canada Toporama http://atlas.gc.ca/toporama/en/index.html
- Environment Canada, National Pollutant Release Inventory
- Ontario Ministry of the Environment Hazardous Waste Information Network https://www.hwin.ca/hwin/
- Ontario Ministry of the Environment, Certificate of Approval search
- Ontario Ministry of the Environment, Brownfields Environmental Site Registry https://www.ontario.ca/page/ministry-environment-and-climate-change
- Ontario Ministry of the Environment, Inventory of Coal Gasification Plan Waste Sites in Ontario, 1987
- Ontario Ministry of the Environment, Inventory of Industrial Sites Producing or Using Coal Tar and Related Tars in Ontario, 1998
- Ontario Ministry of the Environment, Inventory of PCB Storage Sites, 1994-2004
- Waste Disposal Site Inventory, 1991
- Ministry of Environment, Conservation and Parks-Freedom of Information
- Technical Standards and Safety Authority – Fuel Safety Division inquiry
- Ontario Geological Survey, 2013. Quaternary Geology of Ontario. Ontario Geological Survey, scale 1:100,000.
- Ontario Ministry of Northern Development and Ontario Geological Survey, 1991. Bedrock Geology of Ontario, Southern Sheet; Ontario Geological Survey, Map 2544, scale 1:1,000,000.
- Ontario Ministry of Natural Resources. Quaternary Geology of Toronto and Surrounding Area. Scale 1:100,000. Map number 2204.
- Historical Maps, aerial photos and Ontario Base Map
- City Directories from 2001 back to 1900
- City of Toronto online-services
- Environmental Risk Information Services (Ecolog ERIS Report)

Figures

C:\0Sharon\19-199-100 -102 Milcroft Golf Course\1-QGIS\Phase One\102 - Area E\Figure 1- Site Location Plan.qgs



Legend

Approx Site Boundary (Area E)

0 200 400 m

DS CONSULTANTS LTD.
6221 Highway 7, UNIT 16
Vaughan, Ontario L4H 0K8
Telephone: (905) 264-9393
www.dsconsultants.ca

Project: PHASE ONE ENVIRONMENTAL SITE ASSESSMENT
Millcroft Golf Course (Area E), Burlington, ON

Title: **SITE LOCATION PLAN**

N

Client: MILLCROFT GREENS CORPORATION

Size:	Approved By:	Drawn By:	Date:
8.5 x 11	D.D	S.Y	February 2020
Rev: 0	Scale: As Shown	Project No.: 19-199-100	Figure No.: 1

Image/Map Source: *Google Street Map*

C:\0Sharon\19-199-100 -102 Milcroft Golf Course\1-QGIS\Phase One\102 - Area E\Figure 2- Phase One Site Plan.qgs



Legend

- Approx. Site Boundary (Area E)
- ASTs

DS CONSULTANTS LTD.
6221 Highway 7, UNIT 16
Vaughan, Ontario L4H 0K8
Telephone: (905) 264-9393
www.dsconsultants.ca

Project: PHASE ONE ENVIRONMENTAL SITE ASSESSMENT
Millcroft Golf Course (Area E), Burlington, ON

Title: **PHASE ONE PROPERTY SITE PLAN**


N

Client: MILLCROFT GREENS CORPORATION

Size:	Approved By:	Drawn By:	Date:
8.5 x 11	D.D	S.Y	February 2020
Rev: 0	Scale: As Shown	Project No.: 19-199-100	Figure No.: 2

Image/Map Source: *Google Satellite Image*

C:\0Sharon\19-199-100 -102 Milcroft Golf Course\1-QGIS\Phase One\102 - Area E\Figure 3- Phase One Study Area.qgs



Legend

- Approx. Site Boundary (Area E)
- 250m Buffer
- Residential
- Commercial
- Institutional
- Parkland

DS CONSULTANTS LTD.
6221 Highway 7, UNIT 16
Vaughan, Ontario L4H 0K8
Telephone: (905) 264-9393
www.dsconsultants.ca

Project: PHASE ONE ENVIRONMENTAL SITE ASSESSMENT
Millcroft Golf Course (Area E), Burlington, ON

Title: **PHASE ONE STUDY AREA**


N

Client: MILLCROFT GREENS CORPORATION

Size:	Approved By:	Drawn By:	Date:
8.5 x 11	D.D	S.Y	February 2020
Rev: 0	Scale: As Shown	Project No.: 19-199-100	Figure No.: 3

Image/Map Source: *Google Satellite Image*

C:\0Sharon\19-199-100 -102 Milcroft Golf Course\1-QGIS\Phase One\102 - Area E\Figure 4- PCA within Phase One Study Area.qgs



Legend

- Approx. Site Boundary (Area E)
- 250m Buffer
- Registered Water Well (MECP WWR)
- PCA not contributing to APEC
- PCA contributing to APEC
- Inferred Groundwater Flow Direction

DS CONSULTANTS LTD.
6221 Highway 7, UNIT 16
Vaughan, Ontario L4H 0K8
Telephone: (905) 264-9393
www.dsconsultants.ca

Project: PHASE ONE ENVIRONMENTAL SITE ASSESSMENT
Millcroft Golf Course (Area E), Burlington, ON

Title: **PCA WITHIN PHASE ONE STUDY AREA**

Client: MILLCROFT GREENS CORPORATION

Size:	Approved By:	Drawn By:	Date:
8.5 x 11	D.D	S.Y	February 2020
Rev: 0	Scale: As Shown	Project No.: 19-199-100	Figure No.: 4

Image/Map Source: *Google Satellite Image*

C:\0Sharon\19-199-100 -102 Milcroft Golf Course\1-QGIS\Phase One\102 - Area E\Figure 5- Summary of APECs on Phase One Property.qgs



Legend

- Approx. Site Boundary (Area E)
- APEC 1, 6 & 7
- APEC 2
- APEC 3
- APEC 4
- APEC 5
- AST
- Transformer
- Barrel

DS CONSULTANTS LTD.
6221 Highway 7, UNIT 16
Vaughan, Ontario L4H 0K8
Telephone: (905) 264-9393
www.dsconsultants.ca

Project: PHASE ONE ENVIRONMENTAL SITE ASSESSMENT
Millcroft Golf Course (Area E), Burlington, ON

Title: **SUMMARY OF APECs ON PHASE ONE PROPERTY**

N

Client: MILLCROFT GREENS CORPORATION

Size:	Approved By:	Drawn By:	Date:
8.5 x 11	D.D	S.Y	February 2020
Rev: 0	Scale: As Shown	Project No.: 19-199-100	Figure No.: 5

Image/Map Source: *Google Satellite Image*

Appendix A

No survey has been provided at this time.

6221 Highway 7, Unit 16, Vaughan, Ontario, L4H 0K8
www.dsconsultants.ca
Tel: 905-264-9393
Email: office@dsconsultants.ca

Appendix B

Summary of City Directory Search

Address	Location Relative to Phase One Property	Listing	Year(s)	Inferred Property Use
Dundas St				
4167-4385	250 m	Residential	1988-1991, 2000	Residential
4252	Phase One Property	Millcroft Golf Club Maintenance Dept	1996	Commercial

Appendix C

ENVIRONMENTAL RISK INFORMATION SERVICES

DATABASE REPORT

Project Property:	*Millcroft Area 3* *Millcroft Park Dr* *Burlington ON L7M*
Project No:	*19-199-102*
Report Type:	*Standard Report*
Order No:	*20191003106*
Requested by:	*Ds Consultants Ltd.*
Date Completed:	*October 8, 2019*

Environmental Risk Information Services
A division of Glacier Media Inc.
1.866.517.5204 | info@erisinfo.com | erisinfo.com

Table of Contents

Table of Contents.....2
Executive Summary.....3
Executive Summary: Report Summary.....4
Executive Summary: Site Report Summary - Project Property.....6
Executive Summary: Site Report Summary - Surrounding Properties.....7
Executive Summary: Summary By Data Source.....9
Map.....12
Aerial.....13
Topographic Map.....14
Detail Report.....15
Unplottable Summary.....28
Unplottable Report.....30
Appendix: Database Descriptions.....39
Definitions.....48

Notice: IMPORTANT LIMITATIONS and YOUR LIABILITY

Reliance on information in Report: This report DOES NOT replace a full Phase I Environmental Site Assessment but is solely intended to be used as a database review of environmental records.

License for use of information in Report: No page of this report can be used without this cover page, this notice and the project property identifier. The information in Report(s) may not be modified or re-sold.

Your Liability for misuse: Using this Service and/or its reports in a manner contrary to this Notice or your agreement will be in breach of copyright and contract and ERIS may obtain damages for such mis-use, including damages caused to third parties, and gives ERIS the right to terminate your account, rescind your license to any previous reports and to bar you from future use of the Service.

No warranty of Accuracy or Liability for ERIS: The information contained in this report has been produced by ERIS Information Limited Partnership ("ERIS") using various sources of information, including information provided by Federal and Provincial government departments. The report applies only to the address and up to the date specified on the cover of this report, and any alterations or deviation from this description will require a new report. This report and the data contained herein does not purport to be and does not constitute a guarantee of the accuracy of the information contained herein and does not constitute a legal opinion nor medical advice. Although ERIS has endeavored to present you with information that is accurate, ERIS disclaims, any and all liability for any errors, omissions, or inaccuracies in such information and data, whether attributable to inadvertence, negligence or otherwise, and for any consequences arising therefrom. Liability on the part of ERIS is limited to the monetary value paid for this report.

Trademark and Copyright: You may not use the ERIS trademarks or attribute any work to ERIS other than as outlined above. This Service and Report(s) are protected by copyright owned by ERIS Information Limited Partnership. Copyright in data used in the Service or Report(s) (the "Data") is owned by ERIS or its licensors. The Service, Report(s) and Data may not be copied or reproduced in whole or in any substantial part without prior written consent of ERIS.

Executive Summary

Property Information:

Project Property:	*Millcroft Area 3* *Millcroft Park Dr Burlington ON L7M*
Project No:	*19-199-102*

Coordinates:

Latitude:	*43.39885*
Longitude:	*-79.815702*
UTM Northing:	*4,805,789.03*
UTM Easting:	*595,903.83*
UTM Zone:	*UTM Zone 17T*

Elevation:	*508 FT* *154.85 M*

Order Information:

Order No:	*20191003106*
Date Requested:	*October 3, 2019*
Requested by:	*Ds Consultants Ltd.*
Report Type:	*Standard Report*

Historical/Products:

Aerial Photographs	*Aerials - National Collection - .tiff files*
ERIS Xplorer	*ERIS Xplorer*

Executive Summary: Report Summary

Database	Name	Searched	Project Property	Within 0.25 km	Total
AAGR	*Abandoned Aggregate Inventory*	Y	0	0	0
AGR	*Aggregate Inventory*	Y	0	0	0
AMIS	*Abandoned Mine Information System*	Y	0	0	0
ANDR	*Anderson's Waste Disposal Sites*	Y	0	0	0
AST	*Aboveground Storage Tanks*	Y	0	0	0
AUWR	*Automobile Wrecking & Supplies*	Y	0	0	0
BORE	*Borehole*	Y	0	0	0
CA	*Certificates of Approval*	Y	0	0	0
CDRY	*Dry Cleaning Facilities*	Y	0	0	0
CFOT	*Commercial Fuel Oil Tanks*	Y	0	0	0
CHEM	*Chemical Register*	Y	0	0	0
CNG	*Compressed Natural Gas Stations*	Y	0	0	0
COAL	*Inventory of Coal Gasification Plants and Coal Tar Sites*	Y	0	0	0
CONV	*Compliance and Convictions*	Y	0	0	0
CPU	*Certificates of Property Use*	Y	0	0	0
DRL	*Drill Hole Database*	Y	0	0	0
EASR	*Environmental Activity and Sector Registry*	Y	0	0	0
EBR	*Environmental Registry*	Y	0	0	0
ECA	*Environmental Compliance Approval*	Y	0	0	0
EEM	*Environmental Effects Monitoring*	Y	0	0	0
EHS	*ERIS Historical Searches*	Y	0	0	0
EIIS	*Environmental Issues Inventory System*	Y	0	0	0
EMHE	*Emergency Management Historical Event*	Y	0	0	0
EPAR	*Environmental Penalty Annual Report*	Y	0	0	0
EXP	*List of TSSA Expired Facilities*	Y	0	0	0
FCON	*Federal Convictions*	Y	0	0	0
FCS	*Contaminated Sites on Federal Land*	Y	0	0	0
FOFT	*Fisheries & Oceans Fuel Tanks*	Y	0	0	0
FST	*Fuel Storage Tank*	Y	0	0	0
FSTH	*Fuel Storage Tank - Historic*	Y	0	0	0
GEN	*Ontario Regulation 347 Waste Generators Summary*	Y	0	19	19
GHG	*Greenhouse Gas Emissions from Large Facilities*	Y	0	0	0
HINC	*TSSA Historic Incidents*	Y	0	1	1
IAFT	*Indian & Northern Affairs Fuel Tanks*	Y	0	0	0
INC	*TSSA Incidents*	Y	0	0	0
LIMO	*Landfill Inventory Management Ontario*	Y	0	0	0

Database	Name	Searched	Project Property	Within 0.25 km	Total
MINE	Canadian Mine Locations	Y	0	0	0
MNR	Mineral Occurrences	Y	0	0	0
NATE	National Analysis of Trends in Emergencies System (NATES)	Y	0	0	0
NCPL	Non-Compliance Reports	Y	0	0	0
NDFT	National Defense & Canadian Forces Fuel Tanks	Y	0	0	0
NDSP	National Defense & Canadian Forces Spills	Y	0	0	0
NDWD	National Defence & Canadian Forces Waste Disposal Sites	Y	0	0	0
NEBI	National Energy Board Pipeline Incidents	Y	0	0	0
NEBP	National Energy Board Wells	Y	0	0	0
NEES	National Environmental Emergencies System (NEES)	Y	0	0	0
NPCB	National PCB Inventory	Y	0	0	0
NPRI	National Pollutant Release Inventory	Y	0	0	0
OGWE	Oil and Gas Wells	Y	0	0	0
OOGW	Ontario Oil and Gas Wells	Y	0	0	0
OPCB	Inventory of PCB Storage Sites	Y	0	0	0
ORD	Orders	Y	0	0	0
PAP	Canadian Pulp and Paper	Y	0	0	0
PCFT	Parks Canada Fuel Storage Tanks	Y	0	0	0
PES	Pesticide Register	Y	0	0	0
PINC	TSSA Pipeline Incidents	Y	0	0	0
PRT	Private and Retail Fuel Storage Tanks	Y	0	0	0
PTTW	Permit to Take Water	Y	0	0	0
REC	Ontario Regulation 347 Waste Receivers Summary	Y	0	0	0
RSC	Record of Site Condition	Y	0	0	0
RST	Retail Fuel Storage Tanks	Y	0	0	0
SCT	Scott's Manufacturing Directory	Y	0	0	0
SPL	Ontario Spills	Y	0	0	0
SRDS	Wastewater Discharger Registration Database	Y	0	0	0
TANK	Anderson's Storage Tanks	Y	0	0	0
TCFT	Transport Canada Fuel Storage Tanks	Y	0	0	0
VAR	TSSA Variances for Abandonment of Underground Storage Tanks	Y	0	0	0
WDS	Waste Disposal Sites - MOE CA Inventory	Y	0	0	0
WDSH	Waste Disposal Sites - MOE 1991 Historical Approval Inventory	Y	0	0	0
WWIS	Water Well Information System	Y	0	2	2
	Total:		0	22	22

Executive Summary: Site Report Summary - Project Property

Map Key	DB	Company/Site Name	Address	Dir/Dist (m)	Elev diff (m)	Page Number

No records found in the selected databases for the project property.

Executive Summary: Site Report Summary - Surrounding Properties

Map Key	DB	Company/Site Name	Address	Dir/Dist (m)	Elev Diff (m)	Page Number
1	GEN	MILLCROFT GOLF CLUB	MAINTENANCE FACILITY 4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S/29.7	0.00	15
1	GEN	MILLCROFT GOLF CLUB	4252 DUNDAS STREET WEST MAINTENANCE FACILITY BURLINGTON ON L7R 3X4	S/29.7	0.00	15
1	GEN	MILLCROFT GOLF CLUB 26-499	MAINTENANCE FACILITY 4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S/29.7	0.00	15
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S/29.7	0.00	16
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S/29.7	0.00	16
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S/29.7	0.00	16
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S/29.7	0.00	17
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S/29.7	0.00	17
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON	S/29.7	0.00	18
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S/29.7	0.00	18
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S/29.7	0.00	18
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S/29.7	0.00	19

Map Key	DB	Company/Site Name	Address	Dir/Dist (m)	Elev Diff (m)	Page Number
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S/29.7	0.00	19
1	GEN	MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S/29.7	0.00	20
2	WWIS		ON ***Well ID:*** 7050862	N/78.0	0.00	20
3	WWIS		lot 8 con 1 ON ***Well ID:*** 2803185	SW/95.7	0.00	21
4	GEN	HALTON DISTRICT SCHOOL BOARD	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W/247.5	1.05	24
4	GEN	HALTON DISTRICT SCHOOL BOARD	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W/247.5	1.05	25
4	GEN	HALTON DISTRICT SCHOOL BOARD	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W/247.5	1.05	25
4	GEN	HALTON DISTRICT SCHOOL BOARD DR.FRANK J. HAYDEN SECONDARY SCHOOL	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W/247.5	1.05	26
4	GEN	HALTON DISTRICT SCHOOL BOARD DR.FRANK J. HAYDEN SECONDARY SCHOOL	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W/247.5	1.05	26
5	HINC		REAR OF PROPERTY AT 4400 MILLCROFT PARK DRIVE, UNIT 9 BURLINGTON ON	NE/249.1	0.00	27

Executive Summary: Summary By Data Source

GEN - Ontario Regulation 347 Waste Generators Summary

A search of the GEN database, dated 1986-Jul 31, 2019 has found that there are 19 GEN site(s) within approximately 0.25 kilometers of the project property.

Equal/Higher Elevation	Address	Direction	Distance (m)	Map Key
MILLCROFT GOLF CLUB	MAINTENANCE FACILITY 4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF CLUB	4252 DUNDAS STREET WEST MAINTENANCE FACILITY BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF CLUB 26-499	MAINTENANCE FACILITY 4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S	29.69	1

Equal/Higher Elevation	Address	Direction	Distance (m)	Map Key
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S	29.69	1
MILLCROFT GOLF & COUNTY CLUB	4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	S	29.69	1
HALTON DISTRICT SCHOOL BOARD DR.FRANK J. HAYDEN SECONDARY SCHOOL	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W	247.49	4
HALTON DISTRICT SCHOOL BOARD DR.FRANK J. HAYDEN SECONDARY SCHOOL	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W	247.49	4
HALTON DISTRICT SCHOOL BOARD	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W	247.49	4
HALTON DISTRICT SCHOOL BOARD	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W	247.49	4
HALTON DISTRICT SCHOOL BOARD	3040 TIM DOBBIE DRIVE BURLINGTON ON L7M0N6	W	247.49	4

HINC - TSSA Historic Incidents


A search of the HINC database, dated 2006-June 2009* has found that there are 1 HINC site(s) within approximately 0.25 kilometers of the project property.

Equal/Higher Elevation	Address	Direction	Distance (m)	Map Key
	REAR OF PROPERTY AT 4400 MILLCROFT PARK DRIVE, UNIT 9 BURLINGTON ON	NE	249.09	5

WWIS - Water Well Information System

A search of the WWIS database, dated Feb 28, 2019 has found that there are 2 WWIS site(s) within approximately 0.25 kilometers of the project property.

Equal/Higher Elevation	Address	Direction	Distance (m)	Map Key
	ON ***Well ID:*** 7050862	N	77.97	2
	lot 8 con 1 ON ***Well ID:*** 2803185	SW	95.74	3



Map : 0.25 Kilometer Radius

Order No: 20191003106

Address: Millcroft Park Dr, Burlington, ON, L7M

ERIS ENVIRONMENTAL RISK INFORMATION SERVICES


- Project Property
- Buffer Outline
- Eris Sites with Higher Elevation
- Eris Sites with Same Elevation
- Eris Sites with Lower Elevation
- Eris Sites with Unknown Elevation
- Expressway
- Principal Highway
- Secondary Highway
- Major Road
- Local road
- Trail
- Proposed Road
- Ferry Route/Ice Road
- Industrial and Resource - Regions
- Main Line
- Sidetrack
- Transit Line
- Abandoned Line
- National Park
- Provincial or Territorial Park
- Other Park
- Golf Course or Driving Range
- Park or Sports Field
- Other Recreation Area

Source: © 2015 DMTI Spatial Inc.

© ERIS Information Limited Partnership

79°49'30"W

43°24'N



43°24'N

Aerial (2017)


Address: Millcroft Park Dr, Burlington, ON, L7M

Source: ESRI World Imagery

Order No: 20191003106

ERIS
ENVIRONMENTAL RISK INFORMATION SERVICES

© ERIS Information Limited Partnership



Topographic Map

Address: Millcroft Park Dr, Burlington, ON, L7M

Source: ESRI World Topographic Map

Order No: 20191003106

© ERIS Information Limited Partnership

Detail Report

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB
1	1 of 14	S/29.7	154.8 / 0.00	MILLCROFT GOLF CLUB MAINTENANCE FACILITY 4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	GEN

Generator No: ON1403000
Status:
Approval Years: 90
Contam. Facility:
MHSW Facility:
SIC Code: 9651
SIC Description: GOLF COURSES

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB
1	2 of 14	S/29.7	154.8 / 0.00	MILLCROFT GOLF CLUB 4252 DUNDAS STREET WEST MAINTENANCE FACILITY BURLINGTON ON L7R 3X4	GEN

Generator No: ON1403000
Status:
Approval Years: 92,93,97,98
Contam. Facility:
MHSW Facility:
SIC Code: 9651
SIC Description: GOLF COURSES

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB
1	3 of 14	S/29.7	154.8 / 0.00	MILLCROFT GOLF CLUB 26-499 MAINTENANCE FACILITY 4252 DUNDAS STREET WEST BURLINGTON ON L7R 3X4	GEN

Generator No: ON1403000
Status:
Approval Years: 94,95,96
Contam. Facility:
MHSW Facility:
SIC Code: 9651

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB

SIC Description: GOLF COURSES

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

---

1 | ***4 of 14*** | ***S/29.7*** | ***154.8 / 0.00*** | ***MILLCROFT GOLF & COUNTY CLUB***
4252 DUNDAS STREET WEST
BURLINGTON ON L7M 4A8 | ***GEN***

Generator No: ON1403000
Status:
Approval Years: 99,00,01,03,04,05,06,07,08
Contam. Facility:
MHSW Facility:
SIC Code: 9651
SIC Description: GOLF COURSES

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 282
Waste Class Desc: NON-HALOGENATED LEAN ORGANICS

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

---

1 | ***5 of 14*** | ***S/29.7*** | ***154.8 / 0.00*** | ***MILLCROFT GOLF & COUNTY CLUB***
4252 DUNDAS STREET WEST
BURLINGTON ON L7R 3X4 | ***GEN***

Generator No: ON1403000
Status:
Approval Years: 2009
Contam. Facility:
MHSW Facility:
SIC Code: 713910
SIC Description: Golf Courses and Country Clubs

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

---

1 | ***6 of 14*** | ***S/29.7*** | ***154.8 / 0.00*** | ***MILLCROFT GOLF & COUNTY CLUB***
4252 DUNDAS STREET WEST | ***GEN***

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB
				BURLINGTON ON L7R 3X4	

Generator No: ON1403000
Status:
Approval Years: 2010
Contam. Facility:
MHSW Facility:
SIC Code: 713910
SIC Description: Golf Courses and Country Clubs

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

1	***7 of 14***	***S/29.7***	***154.8 / 0.00***	***MILLCROFT GOLF & COUNTY CLUB*** ***4252 DUNDAS STREET WEST*** ***BURLINGTON ON L7R 3X4***	***GEN***

Generator No: ON1403000
Status:
Approval Years: 2011
Contam. Facility:
MHSW Facility:
SIC Code: 713910
SIC Description: Golf Courses and Country Clubs

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

1	***8 of 14***	***S/29.7***	***154.8 / 0.00***	***MILLCROFT GOLF & COUNTY CLUB*** ***4252 DUNDAS STREET WEST*** ***BURLINGTON ON L7R 3X4***	***GEN***

Generator No: ON1403000
Status:
Approval Years: 2012
Contam. Facility:
MHSW Facility:
SIC Code: 713910
SIC Description: Golf Courses and Country Clubs

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

---

1 | **9 of 14** | **S/29.7** | **154.8 / 0.00** | **MILLCROFT GOLF & COUNTY CLUB**
4252 DUNDAS STREET WEST
BURLINGTON ON | **GEN**

Generator No: ON1403000
Status:
Approval Years: 2013
Contam. Facility:
MHSW Facility:
SIC Code: 713910
SIC Description: GOLF COURSES AND COUNTRY CLUBS

PO Box No:
Country:
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

---

1 | **10 of 14** | **S/29.7** | **154.8 / 0.00** | **MILLCROFT GOLF & COUNTY CLUB**
4252 DUNDAS STREET WEST
BURLINGTON ON L7M 4A8 | **GEN**

Generator No: ON1403000
Status:
Approval Years: 2016
Contam. Facility: No
MHSW Facility: No
SIC Code: 713910
SIC Description: GOLF COURSES AND COUNTRY CLUBS

PO Box No:
Country: Canada
Choice of Contact: CO_OFFICIAL
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

---

1 | **11 of 14** | **S/29.7** | **154.8 / 0.00** | **MILLCROFT GOLF & COUNTY CLUB**
4252 DUNDAS STREET WEST
BURLINGTON ON L7M 4A8 | **GEN**

Generator No: ON1403000
Status:
Approval Years: 2015
Contam. Facility: No
MHSW Facility: No
SIC Code: 713910

PO Box No:
Country: Canada
Choice of Contact: CO_OFFICIAL
Co Admin:
Phone No Admin:

SIC Description: GOLF COURSES AND COUNTRY CLUBS

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

---

1 | ***12 of 14*** | ***S/29.7*** | ***154.8 / 0.00*** | ***MILLCROFT GOLF & COUNTY CLUB***
4252 DUNDAS STREET WEST
BURLINGTON ON L7M 4A8 | ***GEN***

Generator No: ON1403000
Status:
Approval Years: 2014
Contam. Facility: No
MHSW Facility: No
SIC Code: 713910
SIC Description: GOLF COURSES AND COUNTRY CLUBS

PO Box No:
Country: Canada
Choice of Contact: CO_OFFICIAL
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213
Waste Class Desc: PETROLEUM DISTILLATES

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

---

1 | ***13 of 14*** | ***S/29.7*** | ***154.8 / 0.00*** | ***MILLCROFT GOLF & COUNTY CLUB***
4252 DUNDAS STREET WEST
BURLINGTON ON L7M 4A8 | ***GEN***

Generator No: ON1403000
Status: Registered
Approval Years: As of Dec 2018
Contam. Facility:
MHSW Facility:
SIC Code:
SIC Description:

PO Box No:
Country: Canada
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213 L
Waste Class Desc: Petroleum distillates

Waste Class: 252 L
Waste Class Desc: Waste crankcase oils and lubricants

Waste Class: 212 L
Waste Class Desc: Aliphatic solvents and residues

Waste Class: 213 I
Waste Class Desc: Petroleum distillates

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB
1	14 of 14	S/29.7	154.8 / 0.00	MILLCROFT GOLF & COUNTY CLUB 4252 DUNDAS STREET WEST BURLINGTON ON L7M 4A8	GEN

Generator No: ON1403000
Status: Registered
Approval Years: As of Jul 2019
Contam. Facility:
MHSW Facility:
SIC Code:
SIC Description:

PO Box No:
Country: Canada
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 213 L
Waste Class Desc: Petroleum distillates

Waste Class: 213 I
Waste Class Desc: Petroleum distillates

Waste Class: 252 L
Waste Class Desc: Waste crankcase oils and lubricants

Waste Class: 212 L
Waste Class Desc: Aliphatic solvents and residues

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB
2	1 of 1	N/78.0	154.8 / 0.00	ON	WWIS

Well ID: 7050862
Construction Date:
Primary Water Use:
Sec. Water Use:
Final Well Status: Abandoned-Other
Water Type:
Casing Material:
Audit No: Z72478
Tag:
Construction Method:
Elevation (m):
Elevation Reliability:
Depth to Bedrock:
Well Depth:
Overburden/Bedrock:
Pump Rate:
Static Water Level:
Flowing (Y/N):
Flow Rate:
Clear/Cloudy:

Data Entry Status:
Data Src:
Date Received: 9/10/2007
Selected Flag: Yes
Abandonment Rec: Yes
Contractor: 6607
Form Version: 3
Owner:
Street Name:
County: HALTON
Municipality: BURLINGTON CITY
Site Info:
Lot:
Concession:
Concession Name:
Easting NAD83:
Northing NAD83:
Zone:
UTM Reliability:

Bore Hole Information

Bore Hole ID: 23050862
DP2BR:
Spatial Status:
Code OB:
Code OB Desc:
Open Hole:
Cluster Kind:
Date Completed: 7/27/2007
Remarks:
Elevrc Desc:

Elevation: 155.629104
Elevrc:
Zone: 17
East83: 595904
North83: 4805867
Org CS: UTM83
UTMRC: 3
UTMRC Desc: margin of error : 10 - 30 m
Location Method: wwr

Location Source Date:
Improvement Location Source:
Improvement Location Method:
Source Revision Comment:
Supplier Comment:

Annular Space/Abandonment Sealing Record

Plug ID: 44006414
Layer: 1
Plug From: 0
Plug To: 1.5
Plug Depth UOM: m

Annular Space/Abandonment Sealing Record

Plug ID: 44006413
Layer: 2
Plug From: 1.5
Plug To: 16.6
Plug Depth UOM: m

Method of Construction & Well Use

Method Construction ID:
Method Construction Code: B
Method Construction: Other Method
Other Method Construction:

Pipe Information

Pipe ID: 29050862
Casing No: 0
Comment:
Alt Name:

Hole Diameter

Hole ID: 46004927
Diameter: 12.5
Depth From: 0
Depth To: 16.6
Hole Depth UOM: m
Hole Diameter UOM: cm

---

3 | ***1 of 1*** | ***SW/95.7*** | ***154.8 / 0.00*** | ***lot 8 con 1 ON*** | ***WWIS***

Well ID: 2803185
Construction Date:
Primary Water Use: Domestic
Sec. Water Use: 0
Final Well Status: Water Supply
Water Type:
Casing Material:
Audit No:
Tag:
Construction Method:

Data Entry Status:
Data Src: 1
Date Received: 9/22/1969
Selected Flag: Yes
Abandonment Rec:
Contractor: 3637
Form Version: 1
Owner:
Street Name:
County: HALTON

Elevation (m):		***Municipality:***	BURLINGTON CITY
Elevation Reliability:		***Site Info:***	
Depth to Bedrock:		***Lot:***	008
Well Depth:		***Concession:***	01
Overburden/Bedrock:		***Concession Name:***	DS S
Pump Rate:		***Easting NAD83:***	
Static Water Level:		***Northing NAD83:***	
Flowing (Y/N):		***Zone:***	
Flow Rate:		***UTM Reliability:***	
Clear/Cloudy:			

Bore Hole Information

Bore Hole ID:	10149727	***Elevation:***	155.762374
DP2BR:	29	***Elevrc:***	
Spatial Status:		***Zone:***	17
Code OB:	r	***East83:***	595834.5
Code OB Desc:	Bedrock	***North83:***	4805723
Open Hole:		***Org CS:***	
Cluster Kind:		***UTMRC:***	4
Date Completed:	8/9/1969	***UTMRC Desc:***	margin of error : 30 m - 100 m
Remarks:		***Location Method:***	p4
Elevrc Desc:			
Location Source Date:			
Improvement Location Source:			
Improvement Location Method:			
Source Revision Comment:			
Supplier Comment:			

Overburden and Bedrock Materials Interval

Formation ID:	931431036
Layer:	3
Color:	7
General Color:	RED
Mat1:	17
Most Common Material:	SHALE
Mat2:	
Other Materials:	
Mat3:	
Other Materials:	
Formation Top Depth:	29
Formation End Depth:	30
Formation End Depth UOM:	ft

Overburden and Bedrock Materials Interval

Formation ID:	931431035
Layer:	2
Color:	6
General Color:	BROWN
Mat1:	05
Most Common Material:	CLAY
Mat2:	06
Other Materials:	SILT
Mat3:	
Other Materials:	
Formation Top Depth:	1
Formation End Depth:	29
Formation End Depth UOM:	ft

Overburden and Bedrock Materials Interval

Formation ID:	931431034
Layer:	1
Color:	6
General Color:	BROWN
Mat1:	02
Most Common Material:	TOPSOIL
Mat2:	
Other Materials:	
Mat3:	
Other Materials:	
Formation Top Depth:	0
Formation End Depth:	1
Formation End Depth UOM:	ft

Method of Construction & Well Use

Method Construction ID:	
Method Construction Code:	6
Method Construction:	Boring
Other Method Construction:	

Pipe Information

Pipe ID:	10698297
Casing No:	1
Comment:	
Alt Name:	

Construction Record - Casing

Casing ID:	930254675
Layer:	1
Material:	3
Open Hole or Material:	CONCRETE
Depth From:	
Depth To:	30
Casing Diameter:	30
Casing Diameter UOM:	inch
Casing Depth UOM:	ft

Results of Well Yield Testing

Pump Test ID:	992803185
Pump Set At:	
Static Level:	8
Final Level After Pumping:	30
Recommended Pump Depth:	26
Pumping Rate:	
Flowing Rate:	
Recommended Pump Rate:	1
Levels UOM:	ft
Rate UOM:	GPM
Water State After Test Code:	1
Water State After Test:	CLEAR
Pumping Test Method:	2
Pumping Duration HR:	
Pumping Duration MIN:	
Flowing:	N

Draw Down & Recovery

Pump Test Detail ID: 934718132
Test Type: Recovery
Test Duration: 45
Test Level: 27
Test Level UOM: ft

Draw Down & Recovery

Pump Test Detail ID: 934450019
Test Type: Recovery
Test Duration: 30
Test Level: 28
Test Level UOM: ft

Draw Down & Recovery

Pump Test Detail ID: 934969101
Test Type: Recovery
Test Duration: 60
Test Level: 26
Test Level UOM: ft

Draw Down & Recovery

Pump Test Detail ID: 934166073
Test Type: Recovery
Test Duration: 15
Test Level: 29
Test Level UOM: ft

Water Details

Water ID: 933605521
Layer: 1
Kind Code: 1
Kind: FRESH
Water Found Depth: 25
Water Found Depth UOM: ft

---

4 ***1 of 5*** ***W/247.5*** ***155.9 / 1.05*** ***HALTON DISTRICT SCHOOL BOARD***
3040 TIM DOBBIE DRIVE
BURLINGTON ON L7M0N6 ***GEN***

Generator No: ON6167524
Status:
Approval Years: 2016
Contam. Facility: No
MHSW Facility: No
SIC Code: 611116
SIC Description: 611116

PO Box No:
Country: Canada
Choice of Contact: CO_OFFICIAL
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 148
Waste Class Desc: INORGANIC LABORATORY CHEMICALS

Waste Class: 263

Waste Class Desc: ORGANIC LABORATORY CHEMICALS

Waste Class: 252
Waste Class Desc: WASTE OILS & LUBRICANTS

Waste Class: 112
Waste Class Desc: ACID WASTE - HEAVY METALS

Waste Class: 331
Waste Class Desc: WASTE COMPRESSED GASES

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

---

4 ***2 of 5*** ***W/247.5*** ***155.9 / 1.05*** ***HALTON DISTRICT SCHOOL BOARD***
3040 TIM DOBBIE DRIVE
BURLINGTON ON L7M0N6 ***GEN***

Generator No: ON6167524
Status:
Approval Years: 2015
Contam. Facility: No
MHSW Facility: No
SIC Code: 611116
SIC Description: 611116

PO Box No:
Country: Canada
Choice of Contact: CO_OFFICIAL
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 331
Waste Class Desc: WASTE COMPRESSED GASES

Waste Class: 148
Waste Class Desc: INORGANIC LABORATORY CHEMICALS

Waste Class: 263
Waste Class Desc: ORGANIC LABORATORY CHEMICALS

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Waste Class: 112
Waste Class Desc: ACID WASTE - HEAVY METALS

---

4 ***3 of 5*** ***W/247.5*** ***155.9 / 1.05*** ***HALTON DISTRICT SCHOOL BOARD***
3040 TIM DOBBIE DRIVE
BURLINGTON ON L7M0N6 ***GEN***

Generator No: ON6167524
Status:
Approval Years: 2014
Contam. Facility: No
MHSW Facility: No
SIC Code: 611116
SIC Description: 611116

PO Box No:
Country: Canada
Choice of Contact: CO_OFFICIAL
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 148
Waste Class Desc: INORGANIC LABORATORY CHEMICALS

Waste Class: 212
Waste Class Desc: ALIPHATIC SOLVENTS

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB

Waste Class: 112
Waste Class Desc: ACID WASTE - HEAVY METALS

Waste Class: 331
Waste Class Desc: WASTE COMPRESSED GASES

Waste Class: 263
Waste Class Desc: ORGANIC LABORATORY CHEMICALS

---

4 **4 of 5** **W/247.5** **155.9 / 1.05** **HALTON DISTRICT SCHOOL BOARD DR.FRANK J. HAYDEN SECONDARY SCHOOL**
3040 TIM DOBBIE DRIVE
BURLINGTON ON L7M0N6 **GEN**

Generator No: ON6167524
Status: Registered
Approval Years: As of Dec 2018
Contam. Facility:
MHSW Facility:
SIC Code:
SIC Description:

PO Box No:
Country: Canada
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Waste Class: 112 C
Waste Class Desc: Acid solutions - containing heavy metals

Waste Class: 148 C
Waste Class Desc: Misc. wastes and inorganic chemicals

Waste Class: 148 R
Waste Class Desc: Misc. wastes and inorganic chemicals

Waste Class: 212 I
Waste Class Desc: Aliphatic solvents and residues

Waste Class: 251 L
Waste Class Desc: Waste oils/sludges (petroleum based)

Waste Class: 252 L
Waste Class Desc: Waste crankcase oils and lubricants

Waste Class: 263 I
Waste Class Desc: Misc. waste organic chemicals

Waste Class: 331 I
Waste Class Desc: Waste compressed gases including cylinders

---

4 **5 of 5** **W/247.5** **155.9 / 1.05** **HALTON DISTRICT SCHOOL BOARD DR.FRANK J. HAYDEN SECONDARY SCHOOL**
3040 TIM DOBBIE DRIVE
BURLINGTON ON L7M0N6 **GEN**

Generator No: ON6167524
Status: Registered
Approval Years: As of Jul 2019
Contam. Facility:
MHSW Facility:
SIC Code:
SIC Description:

PO Box No:
Country: Canada
Choice of Contact:
Co Admin:
Phone No Admin:

Detail(s)

Map Key	Number of Records	Direction/ Distance (m)	Elev/Diff (m)	Site	DB

Waste Class: 331 I
Waste Class Desc: Waste compressed gases including cylinders

Waste Class: 148 R
Waste Class Desc: Misc. wastes and inorganic chemicals

Waste Class: 252 L
Waste Class Desc: Waste crankcase oils and lubricants

Waste Class: 263 I
Waste Class Desc: Misc. waste organic chemicals

Waste Class: 112 C
Waste Class Desc: Acid solutions - containing heavy metals

Waste Class: 251 L
Waste Class Desc: Waste oils/sludges (petroleum based)

Waste Class: 212 I
Waste Class Desc: Aliphatic solvents and residues

Waste Class: 148 C
Waste Class Desc: Misc. wastes and inorganic chemicals

5	1 of 1	NE/249.1	154.8 / 0.00	REAR OF PROPERTY AT 4400 MILLCROFT PARK DRIVE, UNIT 9 BURLINGTON ON	HINC

External File Num: FS INC 0609-02667
Fuel Occurrence Type: Pipeline Strike
Date of Occurrence: 9/12/2006
Fuel Type Involved: Natural Gas
Status Desc: Completed - Causal Analysis(End)
Job Type Desc: Incident/Near-Miss Occurrence (FS)
Oper. Type Involved: Construction Site (pipeline strike)
Service Interruptions: Yes
Property Damage: No
Fuel Life Cycle Stage: Transmission, Distribution and Transportation
Root Cause: Root Cause: Equipment/Material/Component:No Procedures:Yes Maintenance:No Design:No Training:Yes Management:Yes Human Factors:Yes

Reported Details:
Fuel Category: Gaseous Fuel
Occurrence Type: Incident
Affiliation: Industry Stakeholder (Licensee/Registration/Certificate Holder, Facility Owner, etc.)
County Name: Halton
Approx. Quant. Rel:
Nearby body of water:
Enter Drainage Syst.:
Approx. Quant. Unit:
Environmental Impact:

Unplottable Summary

Total: 25 Unplottable sites

DB	Company Name/Site Name	Address	City	Postal
CA	MONARCH CONSTRUCTION LIMITED	PT.LOTS 6&7/C-1,DUNDAS ST.,SWM	BURLINGTON ON	
CA	BURLINGTON CITY - WALKER'S LINE	MILLCROFT PARK DRIVE	BURLINGTON CITY ON	
CA	BURLINGTON CITY - WALKER'S LINE	MILLCROFT PARK DRIVE	BURLINGTON CITY ON	
CA	MONARCH CONSTRUCTION LIMITED	MILLCROFT PARK DR.	BURLINGTON CITY ON	
CA	MONARCH CONSTRUCTION LIMITED	MILLCROFT PARK DR.	BURLINGTON CITY ON	
CA	MONARCH CONSTRUCTION LIMITED	MILLCROFT P.2E/MILLCROFT PK.DR	BURLINGTON CITY ON	
CA	MONARCH CONSTRUCTION LIMITED	MILLCROFT P.2E/MILLCROFT PK.DR	BURLINGTON CITY ON	
CA	The Regional Municipality of Halton	Dundas Street at Westlock Common	Burlington ON	
CA	Millcroft Phase Phase 2E-2b	Part Lots 6 & 7, Concession 1 SDS	Burlington ON	
CA	Millcroft Phase Phase 2E-2b	Part Lots 6 & 7, Concession 1 SDS	Burlington ON	
CA		Part of Lot 9, Concession 1	Burlington ON	
CA		Part of Lot 9, Concession 1	Burlington ON	
CA	Itabashi Way	Part of Lot 9, Concession 2	Burlington ON	
CA	Monarch Corporation	Part of Lots 8 and 9, Concession 1, South of Dundas Street	Burlington ON	
CA	The Corporation of the City of Burlington	Plains Rd W Lots 9 to 13, Concession 1	Burlington ON	
CA	The Regional Municipality of Halton	Dundas Street	Burlington ON	
CA	Hanson Brick Ltd./Briques Hanson Ltee	Concession 1, Former Township of Nelson	Burlington ON	

EBR	Greenflow Environmental Services Inc.	Lot 7, Plan M-192 CITY OF BURLINGTON	ON	
EBR	Greenflow Environmental Services Inc.	Lot 7, Plan M-192 City of Burlington CITY OF BURLINGTON	ON	
ECA	Marble Creek Developments Inc.	Part of Lot 8, Concession 1	Burlington ON	L7L 0A2
ECA	Lloyd Ripani	Part of Lot 9, Concession 1	Burlington ON	L9A 4B2
ECA	Lloyd Ripani	Part of Lot 9, Concession 1	Burlington ON	L9A 4B2
NCPL	Hanson Brick Ltd.	Concession 1, Former Township of Nelson	Burlington ON	
SPL	FARM	NORTH SIDE OF HWY #5 WEST OF GUELPH LINE. EAGLES FIELD DRIVE.	BURLINGTON CITY ON	
WWIS			Burlington ON	

Unplottable Report

Site: ***MONARCH CONSTRUCTION LIMITED***
PT.LOTS 6&7/C-1,DUNDAS ST.,SWM BURLINGTON ON

Database: ***CA***

Certificate #: 3-1207-98-
Application Year: 98
Issue Date: 8/27/1998
Approval Type: Municipal sewage
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***BURLINGTON CITY - WALKER'S LINE***
MILLCROFT PARK DRIVE BURLINGTON CITY ON

Database: ***CA***

Certificate #: 3-1523-91-
Application Year: 91
Issue Date: 10/4/1991
Approval Type: Municipal sewage
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***BURLINGTON CITY - WALKER'S LINE***
MILLCROFT PARK DRIVE BURLINGTON CITY ON

Database: ***CA***

Certificate #: 7-1218-91-
Application Year: 91
Issue Date: 10/4/1991
Approval Type: Municipal water
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***MONARCH CONSTRUCTION LIMITED***
MILLCROFT PARK DR. BURLINGTON CITY ON

Database: ***CA***

Certificate #: 3-0559-88-
Application Year: 88

Issue Date: 4/26/1988
Approval Type: Municipal sewage
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***MONARCH CONSTRUCTION LIMITED***
MILLCROFT PARK DR. BURLINGTON CITY ON

Database: ***CA***

Certificate #: 7-0496-88-
Application Year: 88
Issue Date: 4/26/1988
Approval Type: Municipal water
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***MONARCH CONSTRUCTION LIMITED***
MILLCROFT P.2E/MILLCROFT PK.DR BURLINGTON CITY ON

Database: ***CA***

Certificate #: 7-1196-97-
Application Year: 97
Issue Date: 11/21/1997
Approval Type: Municipal water
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***MONARCH CONSTRUCTION LIMITED***
MILLCROFT P.2E/MILLCROFT PK.DR BURLINGTON CITY ON

Database: ***CA***

Certificate #: 3-1642-97-
Application Year: 97
Issue Date: 11/21/1997
Approval Type: Municipal sewage
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***The Regional Municipality of Halton***
Dundas Street at Westlock Common Burlington ON

Database: ***CA***

Certificate #: 3329-6PUHSR
Application Year: 2006
Issue Date: 5/19/2006
Approval Type: Municipal and Private Sewage Works
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***Millcroft Phase Phase 2E-2b***
Part Lots 6 & 7, Concession 1 SDS Burlington ON

Database: ***CA***

Certificate #: 5005-4FWMY9
Application Year: 00
Issue Date: 1/26/00
Approval Type: Municipal & Private water
Status: Approved
Application Type: New Certificate of Approval
Client Name: Monarch Construction Limited
Client Address: 3584 Jockvale Road
Client City: NEPEAN
Client Postal Code: K2C 3H2
Project Description: Install watermains on Nicklaus Court and Millcroft Park Drive
Contaminants:
Emission Control:

Site: ***Millcroft Phase Phase 2E-2b***
Part Lots 6 & 7, Concession 1 SDS Burlington ON

Database: ***CA***

Certificate #: 5305-4FWLPL
Application Year: 00
Issue Date: 1/26/00
Approval Type: Municipal & Private sewage
Status: Approved
Application Type: New Certificate of Approval
Client Name: Monarch Construction Limited
Client Address: 3584 Jockvale Road
Client City: NEPEAN
Client Postal Code: K2C 3H2
Project Description: Install sanitary & storm sewers on Nicklaus Court and Taywood Drive
Contaminants:
Emission Control:

Site:
Part of Lot 9, Concession 1 Burlington ON

Database: ***CA***

Certificate #: 2785-575JFV
Application Year: 02
Issue Date: 2/13/02
Approval Type: Municipal & Private water
Status: Approved
Application Type: New Certificate of Approval
Client Name: Lloyd Ripani
Client Address: 32 East 14th Street
Client City: Hamilton
Client Postal Code: L9A 4B2
Project Description: Construction of Watermains

Contaminants:
Emission Control:

Site: ***Database:***
Part of Lot 9, Concession 1 Burlington ON ***CA***

Certificate #: 5614-575JL6
Application Year: 02
Issue Date: 2/13/02
Approval Type: Municipal & Private sewage
Status: Approved
Application Type: New Certificate of Approval
Client Name: Lloyd Ripani
Client Address: 32 East 14th Street
Client City: Hamilton
Client Postal Code: L9A 4B2
Project Description: Construction of Storm and Sanitary Sewers
Contaminants:
Emission Control:

Site: ***Itabashi Way*** ***Database:***
Part of Lot 9, Concession 2 Burlington ON ***CA***

Certificate #: 5250-4RXKN4
Application Year: 00
Issue Date: 12/21/00
Approval Type: Municipal & Private water
Status: Approved
Application Type: New Certificate of Approval
Client Name: Oakwood Retirement Communities Inc.
Client Address: 460 Frederick Street
Client City: Kitchener
Client Postal Code: N2H 2P5
Project Description: Watermain to be constructed on Itabashi Way in the City of Burlington.
Contaminants:
Emission Control:

Site: ***Monarch Corporation*** ***Database:***
Part of Lots 8 and 9, Concession 1, South of Dundas Street Burlington ON ***CA***

Certificate #: 4817-6EPKWF
Application Year: 2005
Issue Date: 7/28/2005
Approval Type: Municipal and Private Sewage Works
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***The Corporation of the City of Burlington*** ***Database:***
Plains Rd W Lots 9 to 13, Concession 1 Burlington ON ***CA***

Certificate #: 1895-7H4N9P
Application Year: 2008
Issue Date: 8/8/2008
Approval Type: Municipal and Private Sewage Works
Status: Approved
Application Type:

Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***The Regional Municipality of Halton***
Dundas Street Burlington ON

Database: ***CA***

Certificate #: 3064-5NDRHZ
Application Year: 2003
Issue Date: 6/11/2003
Approval Type: Municipal and Private Sewage Works
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***Hanson Brick Ltd./Briques Hanson Ltee***
Concession 1, Former Township of Nelson Burlington ON

Database: ***CA***

Certificate #: 5414-8ETKBD
Application Year: 2011
Issue Date: 4/1/2011
Approval Type: Air
Status: Approved
Application Type:
Client Name:
Client Address:
Client City:
Client Postal Code:
Project Description:
Contaminants:
Emission Control:

Site: ***Greenflow Environmental Services Inc.***
Lot 7, Plan M-192 CITY OF BURLINGTON ON

Database: ***EBR***

EBR Registry No: IA8E0344
Ministry Ref No: A680198
Notice Type: Instrument Decision
Notice Stage: 800475738
Notice Date: February 21, 2000
Proposal Date: March 16, 1998
Year: 1998
Decision Posted:
Exception Posted:
Section:
Act 1:
Act 2:
Site Location Map:
Instrument Type: (EPA s. 27) - Approval for a waste disposal site.
Off Instrument Name:
Posted By:
Company Name: Greenflow Environmental Services Inc.
Site Address:
Location Other:
Proponent Name:
Proponent Address: Unit 2 and 3, 4151 Morris Drive,, Burlington Ontario, L7L 5L5
Comment Period:
URL:

Site Location Details:

Lot 7, Plan M-192 CITY OF BURLINGTON

Site: ***Greenflow Environmental Services Inc.*** ***Database:*** ***EBR***
Lot 7, Plan M-192 City of Burlington CITY OF BURLINGTON ON

EBR Registry No:	IA7E1718	***Decision Posted:***	
Ministry Ref No:	B680198	***Exception Posted:***	
Notice Type:	Instrument Decision	***Section:***	
Notice Stage:	800475712	***Act 1:***	
Notice Date:	February 18, 2000	***Act 2:***	
Proposal Date:	November 24, 1997	***Site Location Map:***	
Year:	1997		
Instrument Type:	(EPA s. 27) - Approval for a waste disposal site.		
Off Instrument Name:			
Posted By:			
Company Name:	Greenflow Environmental Services Inc.		
Site Address:			
Location Other:			
Proponent Name:			
Proponent Address:	4151 Morris Drive, Unit 4, Burlington Ontario, L7L 5L5		
Comment Period:			
URL:			

Site Location Details:

Lot 7, Plan M-192 City of Burlington CITY OF BURLINGTON

Site: ***Marble Creek Developments Inc.*** ***Database:*** ***ECA***
Part of Lot 8, Concession 1 Burlington ON L7L 0A2

Approval No:	3261-9CKQZY	***MOE District:***	
Approval Date:	2013-10-30	***City:***	
Status:	Approved	***Longitude:***	
Record Type:	ECA	***Latitude:***	
Link Source:	IDS	***Geometry X:***	
SWP Area Name:		***Geometry Y:***	
Approval Type:	ECA-MUNICIPAL AND PRIVATE SEWAGE WORKS		
Project Type:	MUNICIPAL AND PRIVATE SEWAGE WORKS		
Address:	Part of Lot 8, Concession 1		
Full Address:			
Full PDF Link:	https://www.accessenvironment.ene.gov.on.ca/instruments/9709-9CHSHJ-14.pdf		

Site: ***Lloyd Ripani*** ***Database:*** ***ECA***
Part of Lot 9, Concession 1 Burlington ON L9A 4B2

Approval No:	2785-575JFV	***MOE District:***	
Approval Date:	2002-02-13	***City:***	
Status:	Approved	***Longitude:***	
Record Type:	ECA	***Latitude:***	
Link Source:	IDS	***Geometry X:***	
SWP Area Name:		***Geometry Y:***	
Approval Type:	ECA-Municipal and Private Water Works		
Project Type:	Municipal and Private Water Works		
Address:	Part of Lot 9, Concession 1		
Full Address:			
Full PDF Link:			

Site: ***Lloyd Ripani*** ***Database:*** ***ECA***
Part of Lot 9, Concession 1 Burlington ON L9A 4B2

Approval No:	5614-575JL6	***MOE District:***	
Approval Date:	2002-02-13	***City:***	

Status:	Approved	***Longitude:***	
Record Type:	ECA	***Latitude:***	
Link Source:	IDS	***Geometry X:***	
SWP Area Name:		***Geometry Y:***	

Approval Type: ECA-MUNICIPAL AND PRIVATE SEWAGE WORKS
Project Type: MUNICIPAL AND PRIVATE SEWAGE WORKS
Address: Part of Lot 9, Concession 1
Full Address:
Full PDF Link: https://www.accessenvironment.ene.gov.on.ca/instruments/9424-55BJSR-14.pdf

---

Site: ***Hanson Brick Ltd.***
Concession 1, Former Township of Nelson Burlington ON

Database: ***NCPL***

Year: 2010
Site Name:
Facility Owner:
Discharge Type: Industrial Sewage
Sector: Miscellaneous Industrial
District Area: Halton-Peel
Type of Concern: CofA/Permit Non-Compliance
Contaminant: OIL & GREASE
Status Report:

Details

Incident Date: 11/30/2010
Exceedance Start Date: 11/1/2010
Exceedance End Date: 11/30/2010
Limit/Unit/Freq: 10 mg/L / /mon
Quantity Min/Max: 14/14
Facility Action: Other
Ministry Action: Assessment Complete - Incident Resolved

Details

Incident Date: 9/30/2010
Exceedance Start Date: 9/1/2010
Exceedance End Date: 9/30/2010
Limit/Unit/Freq: 10 mg/L / /mon
Quantity Min/Max: 10.1/10.1
Facility Action: Other
Ministry Action: Assessment Complete - Incident Resolved

Details

Incident Date: 5/31/2010
Exceedance Start Date: 5/1/2010
Exceedance End Date: 5/31/2010
Limit/Unit/Freq: 10 mg/L / /mon
Quantity Min/Max: 11/11
Facility Action: Other
Ministry Action: Assessment Complete - Incident Resolved

Site: ***FARM***
NORTH SIDE OF HWY #5 WEST OF GUELPH LINE. EAGLES FIELD DRIVE. BURLINGTON CITY ON

Database: ***SPL***

Ref No:	107387	***Discharger Report:***	
Site No:		***Material Group:***	
Incident Dt:	11/15/1994	***Health/Env Conseq:***	
Year:		***Client Type:***	
Incident Cause:	UNDERGROUND TANK LEAK	***Sector Type:***	
Incident Event:		***Agency Involved:***	
Contaminant Code:		***Nearest Watercourse:***	
Contaminant Name:		***Site Address:***	
Contaminant Limit 1:		***Site District Office:***	

Contam Limit Freq 1:		***Site Postal Code:***	
Contaminant UN No 1:		***Site Region:***	
Environment Impact:	POSSIBLE	***Site Municipality:***	14101
Nature of Impact:	Soil contamination	***Site Lot:***	
Receiving Medium:	LAND	***Site Conc:***	
Receiving Env:		***Northing:***	
MOE Response:		***Easting:***	R.M.,CITY WORKS
Dt MOE Arvl on Scn:		***Site Geo Ref Accu:***	
MOE Reported Dt:	11/15/1994	***Site Map Datum:***	
Dt Document Closed:		***SAC Action Class:***	
Incident Reason:	NEGLIGENCE (APPARENT)	***Source Type:***	
Site Name:			
Site County/District:			
Site Geo Ref Meth:			
Incident Summary:	FISHER FARMS: FUEL OIL TODITCH DURING EXCAVATION OF OLD TANK.		
Contaminant Qty:			

Site:

Burlington ON

Database:
WWIS

Well ID:	7180048	***Data Entry Status:***	
Construction Date:		***Data Src:***	
Primary Water Use:		***Date Received:***	4/26/2012
Sec. Water Use:		***Selected Flag:***	Yes
Final Well Status:	Abandoned-Other	***Abandonment Rec:***	Yes
Water Type:		***Contractor:***	7501
Casing Material:		***Form Version:***	7
Audit No:	Z136056	***Owner:***	
Tag:	A109107	***Street Name:***	DUNDAS ST
Construction Method:		***County:***	
Elevation (m):		***Municipality:***	
Elevation Reliability:		***Site Info:***	
Depth to Bedrock:		***Lot:***	
Well Depth:		***Concession:***	
Overburden/Bedrock:		***Concession Name:***	
Pump Rate:		***Easting NAD83:***	
Static Water Level:		***Northing NAD83:***	
Flowing (Y/N):		***Zone:***	
Flow Rate:		***UTM Reliability:***	
Clear/Cloudy:			

Bore Hole Information

Bore Hole ID:	1003714835	***Elevation:***	
DP2BR:		***Elevrc:***	
Spatial Status:		***Zone:***	
Code OB:		***East83:***	
Code OB Desc:		***North83:***	
Open Hole:		***Org CS:***	UTM83
Cluster Kind:		***UTMRC:***	9
Date Completed:	4/25/2012	***UTMRC Desc:***	unknown UTM
Remarks:		***Location Method:***	wwr
Elevrc Desc:			
Location Source Date:			
Improvement Location Source:			
Improvement Location Method:			
Source Revision Comment:			
Supplier Comment:			

Annular Space/Abandonment Sealing Record

Plug ID:	1004291029
Layer:	1
Plug From:	0
Plug To:	30
Plug Depth UOM:	ft

Pipe Information

Pipe ID: 1004291022
Casing No: 0
Comment:
Alt Name:

Construction Record - Casing

Casing ID: 1004291026
Layer:
Material:
Open Hole or Material:
Depth From:
Depth To:
Casing Diameter:
Casing Diameter UOM: inch
Casing Depth UOM: ft

Construction Record - Screen

Screen ID: 1004291027
Layer:
Slot:
Screen Top Depth:
Screen End Depth:
Screen Material:
Screen Depth UOM: ft
Screen Diameter UOM: inch
Screen Diameter:

Hole Diameter

Hole ID: 1004291024
Diameter:
Depth From:
Depth To:
Hole Depth UOM: ft
Hole Diameter UOM: inch

Appendix: Database Descriptions

Environmental Risk Information Services (ERIS) can search the following databases. The extent of historical information varies with each database and current information is determined by what is publicly available to ERIS at the time of update. ***Note:*** *Databases denoted with " * " indicates that the database will no longer be updated. See the individual database description for more information.*

Abandoned Aggregate Inventory: Provincial AAGR

The MAAP Program maintains a database of abandoned pits and quarries. Please note that the database is only referenced by lot and concession and city/town location. The database provides information regarding the location, type, size, land use, status and general comments.*

Government Publication Date: Sept 2002*

Aggregate Inventory: Provincial AGR

The Ontario Ministry of Natural Resources maintains a database of all active pits and quarries. The database provides information regarding the registered owner/operator, location name, operation type, approval type, and maximum annual tonnage.

Government Publication Date: Up to Sep 2018

Abandoned Mine Information System: Provincial AMIS

The Abandoned Mines Information System contains data on known abandoned and inactive mines located on both Crown and privately held lands. The information was provided by the Ministry of Northern Development and Mines (MNDM), with the following disclaimer: "the database provided has been compiled from various sources, and the Ministry of Northern Development and Mines makes no representation and takes no responsibility that such information is accurate, current or complete". Reported information includes official mine name, status, background information, mine start/end date, primary commodity, mine features, hazards and remediation.

Government Publication Date: 1800-Oct 2018

Anderson's Waste Disposal Sites: Private ANDR

The information provided in this database was collected by examining various historical documents which aimed to characterize the likely position of former waste disposal sites from 1860 to present. The research initiative behind the creation of this database was to identify those sites that are missing from the Ontario MOE Waste Disposal Site Inventory, as well as to provide revisions and corrections to the positions and descriptions of sites currently listed in the MOE inventory. In addition to historic waste disposal facilities, the database also identifies certain auto wreckers and scrap yards that have been extrapolated from documentary sources. Please note that the data is not warranted to be complete, exhaustive or authoritative. The information was collected for research purposes only.

Government Publication Date: 1860s-Present

Aboveground Storage Tanks: Provincial AST

Historical listing of aboveground storage tanks made available by the Department of Natural Resources and Forestry. Includes tanks used to hold water or petroleum. This dataset has been retired as of September 25, 2014 and will no longer be updated.

Government Publication Date: May 31, 2014

Automobile Wrecking & Supplies: Private AUWR

This database provides an inventory of known locations that are involved in the scrap metal, automobile wrecking/recycling, and automobile parts & supplies industry. Information is provided on the company name, location and business type.

Government Publication Date: 1999-Jul 31, 2019

Borehole: Provincial BORE

A borehole is the generalized term for any narrow shaft drilled in the ground, either vertically or horizontally. The information here includes geotechnical investigations or environmental site assessments, mineral exploration, or as a pilot hole for installing piers or underground utilities. Information is from many sources such as the Ministry of Transportation (MTO) boreholes from engineering reports and projects from the 1950 to 1990's in Southern Ontario. Boreholes from the Ontario Geological Survey (OGS) including The Urban Geology Analysis Information System (UGAIS) and the York Peel Durham Toronto (YPDT) database of the Conservation Authority Moraine Coalition. This database will include fields such as location, stratigraphy, depth, elevation, year drilled, etc. For all water well data or oil and gas well data for Ontario please refer to WWIS and OOGW.

Government Publication Date: 1875-Jul 2018

Certificates of Approval: Provincial CA

This database contains the following types of approvals: Air & Noise, Industrial Sewage, Municipal & Private Sewage, Waste Management Systems and Renewable Energy Approvals. The MOE in Ontario states that any facility that releases emissions to the atmosphere, discharges contaminants to ground or surface water, provides potable water supplies, or stores, transports or disposes of waste, must have a Certificate of Approval before it can operate lawfully. Fields include approval number, business name, address, approval date, approval type and status. This database will no longer be updated, as CofA's have been replaced by either Environmental Activity and Sector Registry (EASR) or Environmental Compliance Approval (ECA). Please refer to those individual databases for any information after Oct.31, 2011.

Government Publication Date: 1985-Oct 30, 2011*

Dry Cleaning Facilities: Federal CDRY

List of dry cleaning facilities made available by Environment and Climate Change Canada. Environment and Climate Change Canada's Tetrachloroethylene (Use in Dry Cleaning and Reporting Requirements) Regulations (SOR/2003-79) are intended to reduce releases of tetrachloroethylene to the environment from dry cleaning facilities.

Government Publication Date: Jan 2004-Dec 2017

Commercial Fuel Oil Tanks: Provincial CFOT

List of commercial underground fuel oil tanks made available by the Fuels Safety Program of the Technical Standards & Safety Authority (TSSA). Ontario Regulation 213/01 of the Technical Standards and Safety Act (2000) requires that all underground tanks be registered with the TSSA. Note: the Fuels Safety Division does not register waste oil tanks in apartments, office buildings, residences, etc., or aboveground gas or diesel tanks. Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of commercial fuel tanks in the province. The TSSA updates information in its system on an ongoing basis; this listing is a copy of the data captured at one moment in time and is hence limited by the record date provided here.

Government Publication Date: Feb 28, 2017

Chemical Register: Private CHEM

This database includes information from both a one time study conducted in 1992 and private source and is a listing of facilities that manufacture or distribute chemicals. The production of these chemical substances may involve one or more chemical reactions and/or chemical separation processes (i.e. fractionation, solvent extraction, crystallization, etc.).

Government Publication Date: 1999-Jul 31, 2019

Compressed Natural Gas Stations: Private CNG

Canada has a network of public access compressed natural gas (CNG) refuelling stations. These stations dispense natural gas in compressed form at 3,000 pounds per square inch (psi), the pressure which is allowed within the current Canadian codes and standards. The majority of natural gas refuelling is located at existing retail gasoline that have a separate refuelling island for natural gas. This list of stations is made available by the Canadian Natural Gas Vehicle Alliance.

Government Publication Date: Dec 2012 - Jun 2019

Inventory of Coal Gasification Plants and Coal Tar Sites: Provincial COAL

This inventory includes both the "Inventory of Coal Gasification Plant Waste Sites in Ontario-April 1987" and the Inventory of Industrial Sites Producing or Using Coal Tar and Related Tars in Ontario-November 1988) collected by the MOE. It identifies industrial sites that produced and continue to produce or use coal tar and other related tars. Detailed information is available and includes: facility type, size, land use, information on adjoining properties, soil condition, site operators/occupants, site description, potential environmental impacts and historic maps available. This was a one-time inventory.*

Government Publication Date: Apr 1987 and Nov 1988*

Compliance and Convictions: Provincial CONV

This database summarizes the fines and convictions handed down by the Ontario courts beginning in 1989. Companies and individuals named here have been found guilty of environmental offenses in Ontario courts of law.

Government Publication Date: 1989-Jul 2019

Certificates of Property Use: Provincial CPU

This is a subset taken from Ontario's Environmental Registry (EBR) database. It will include all CPU's on the registry such as (EPA s. 168.6) - Certificate of Property Use.

Government Publication Date: 1994-Aug 31, 2019

Drill Hole Database: Provincial DRL

The Ontario Drill Hole Database contains information on more than 113,000 percussion, overburden, sonic and diamond drill holes from assessment files on record with the department of Mines and Minerals. Please note that limited data is available for southern Ontario, as it was the last area to be completed. The database was created when surveys submitted to the Ministry were converted in the Assessment File Research Image Database (AFRI) project. However, the degree of accuracy (coordinates) as to the exact location of drill holes is dependent upon the source document submitted to the MNDM. Levels of accuracy used to locate holes are: centering on the mining claim; a sketch of the mining claim; a 1:50,000 map; a detailed company map; or from submitted a "Report of Work".

Government Publication Date: 1886 - Oct 2018

Environmental Activity and Sector Registry: Provincial EASR

On October 31, 2011, a smarter, faster environmental approvals system came into effect in Ontario. The EASR allows businesses to register certain activities with the ministry, rather than apply for an approval. The registry is available for common systems and processes, to which preset rules of operation can be applied. The EASR is currently available for: heating systems, standby power systems and automotive refinishing. Businesses whose activities aren't subject to the EASR may apply for an ECA (Environmental Compliance Approval), Please see our ECA database.

Government Publication Date: Oct 2011-Aug 31, 2019

Environmental Registry: Provincial EBR

The Environmental Registry lists proposals, decisions and exceptions regarding policies, Acts, instruments, or regulations that could significantly affect the environment. Through the Registry, thirteen provincial ministries notify the public of upcoming proposals and invite their comments. For example, if a local business is requesting a permit, license, or certificate of approval to release substances into the air or water; these are notified on the registry. Data includes: Approval for discharge into the natural environment other than water (i.e. Air) - EPA s. 9, Approval for sewage works - OWRA s. 53(1), and EPA s. 27 - Approval for a waste disposal site. For information regarding Permit to Take Water (PTTW), Certificate of Property Use (CPU) and (ORD) Orders please refer to those individual databases.

Government Publication Date: 1994-Aug 31, 2019

Environmental Compliance Approval: Provincial ECA

On October 31, 2011, a smarter, faster environmental approvals system came into effect in Ontario. In the past, a business had to apply for multiple approvals (known as certificates of approval) for individual processes and pieces of equipment. Today, a business either registers itself, or applies for a single approval, depending on the types of activities it conducts. Businesses whose activities aren't subject to the EASR may apply for an ECA. A single ECA addresses all of a business's emissions, discharges and wastes. Separate approvals for air, noise and waste are no longer required. This database will also include Renewable Energy Approvals. For certificates of approval prior to Nov 1st, 2011, please refer to the CA database. For all Waste Disposal Sites please refer to the WDS database.

Government Publication Date: Oct 2011-Aug 31, 2019

Environmental Effects Monitoring: Federal EEM

The Environmental Effects Monitoring program assesses the effects of effluent from industrial or other sources on fish, fish habitat and human usage of fisheries resources. Since 1992, pulp and paper mills have been required to conduct EEM studies under the Pulp and Paper Effluent Regulations. This database provides information on the mill name, geographical location and sub-lethal toxicity data.

Government Publication Date: 1992-2007*

ERIS Historical Searches: Private EHS

ERIS has compiled a database of all environmental risk reports completed since March 1999. Available fields for this database include: site location, date of report, type of report, and search radius. As per all other databases, the ERIS database can be referenced on both the map and "Statistical Profile" page.

Government Publication Date: 1999-Jul 31, 2019

Environmental Issues Inventory System: Federal EIIS

The Environmental Issues Inventory System was developed through the implementation of the Environmental Issues and Remediation Plan. This plan was established to determine the location and severity of contaminated sites on inhabited First Nation reserves, and where necessary, to remediate those that posed a risk to health and safety; and to prevent future environmental problems. The EIIS provides information on the reserve under investigation, inventory number, name of site, environmental issue, site action (Remediation, Site Assessment), and date investigation completed.

Government Publication Date: 1992-2001*

Emergency Management Historical Event: Provincial EMHE

List of locations of historical occurrences of emergency events, including those assigned to the Ministry of Natural Resources by Order-In-Council (OIC) under the Emergency Management and Civil Protection Act, as well as events where MNR provided requested emergency response assistance. Many of these events will have involved community evacuations, significant structural loss, and/or involvement of MNR emergency response staff. These events fall into one of ten (10) type categories: Dam Failure; Drought / Low Water; Erosion; Flood; Forest Fire; Soil and Bedrock Instability; Petroleum Resource Center Event, EMO Requested Assistance, Continuity of Operations Event, Other Requested Assistance. EMHE record details are reproduced by ERIS under License with the Ontario Ministry of Natural Resources © Queen's Printer for Ontario, 2017.

Government Publication Date: Dec 31, 2016

Environmental Penalty Annual Report: Provincial EPAR

This database contains data from Ontario's annual environmental penalty report published by the Ministry of the Environment and Climate Change. These reports provide information on environmental penalties for land or water violations issued to companies in one of the nine industrial sectors covered by the Municipal Industrial Strategy for Abatement (MISA) regulations.

Government Publication Date: Jan 1, 2011 - Dec 31, 2018

List of TSSA Expired Facilities: Provincial EXP

List of facilities and tanks - for which there was once a registration - no longer registered with the Fuels Safety Program of the Technical Standards and Safety Authority (TSSA). Includes private fuel outlets, bulk plants, fuel oil tanks, gasoline stations, marinas, propane filling stations, liquid fuel tanks, piping systems, etc. Tanks which have been removed from the ground are included in the expired facilities inventory held by the TSSA. Notes: the Fuels Safety Division did not register private fuel underground/aboveground storage tanks prior to January of 1990, or furnace oil tanks prior to May 1, 2002; nor does the Division register waste oil tanks in apartments, office buildings, residences, etc., or aboveground gas or diesel tanks. Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of expired tanks/tank facilities in the province. The TSSA updates information in its system on an ongoing basis; this listing is hence limited by the record date provided here.

Government Publication Date: Feb 28, 2017

Federal Convictions: Federal FCON

Environment Canada maintains a database referred to as the "Environmental Registry" that details prosecutions under the Canadian Environmental Protection Act (CEPA) and the Fisheries Act (FA). Information is provided on the company name, location, charge date, offence and penalty.

Government Publication Date: 1988-Jun 2007*

Contaminated Sites on Federal Land: Federal FCS

The Federal Contaminated Sites Inventory includes information on known federal contaminated sites under the custodianship of departments, agencies and consolidated Crown corporations as well as those that are being or have been investigated to determine whether they have contamination arising from past use that could pose a risk to human health or the environment. The inventory also includes non-federal contaminated sites for which the Government of Canada has accepted some or all financial responsibility. It does not include sites where contamination has been caused by, and which are under the control of, enterprise Crown corporations, private individuals, firms or other levels of government.

Government Publication Date: Jun 2000-May 2019

Fisheries & Oceans Fuel Tanks: Federal FOFT

Fisheries & Oceans Canada maintains an inventory of aboveground & underground fuel storage tanks located on Fisheries & Oceans property or controlled by DFO. Our inventory provides information on the site name, location, tank owner, tank operator, facility type, storage tank location, tank contents & capacity, and date of tank installation.

Government Publication Date: 1964-Sep 2018

Fuel Storage Tank: Provincial FST

List of registered private and retail fuel storage tanks made available by the Fuels Safety Program of the Technical Standards & Safety Authority (TSSA). Ontario Regulation 213/01 of the Technical Standards and Safety Act (2000) requires that all underground tanks be registered with the TSSA. Notes: the Fuels Safety Division did not register private fuel underground/aboveground storage tanks prior to January of 1990, or furnace oil tanks prior to May 1, 2002; nor does the Division register waste oil tanks in apartments, office buildings, residences, etc., or aboveground gas or diesel tanks. Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of fuel storage tanks/tank facilities in the province. The TSSA updates information in its system on an ongoing basis; this listing is hence limited by the record date provided here.

Government Publication Date: Feb 28, 2017

Fuel Storage Tank - Historic: Provincial FSTH

The Fuels Safety Branch of the Ontario Ministry of Consumer and Commercial Relations maintained a database of all registered private fuel storage tanks. Public records of private fuel storage tanks are only available since the registration became effective in September 1989. This information is now collected by the Technical Standards and Safety Authority.

Government Publication Date: Pre-Jan 2010*

Ontario Regulation 347 Waste Generators Summary: Provincial GEN

Regulation 347 of the Ontario EPA defines a waste generation site as any site, equipment and/or operation involved in the production, collection, handling and/or storage of regulated wastes. A generator of regulated waste is required to register the waste generation site and each waste produced, collected, handled, or stored at the site. This database contains the registration number, company name and address of registered generators including the types of hazardous wastes generated. It includes data on waste generating facilities such as: drycleaners, waste treatment and disposal facilities, machine shops, electric power distribution etc. This information is a summary of all years from 1986 including the most currently available data. Some records may contain, within the company name, the phrase "See & Use..." followed by a series of letters and numbers. This occurs when one company is amalgamated with or taken over by another registered company. The number listed as "See & Use", refers to the new ownership and the other identification number refers to the original ownership. This phrase serves as a link between the 2 companies until operations have been fully transferred.

Government Publication Date: 1986-Jul 31, 2019

Greenhouse Gas Emissions from Large Facilities: Federal GHG

List of greenhouse gas emissions from large facilities made available by Environment Canada. Greenhouse gas emissions in kilotonnes of carbon dioxide equivalents (kt CO2 eq).

Government Publication Date: 2013-Dec 2017

TSSA Historic Incidents: Provincial HINC

List of historic incidences of spills and leaks of diesel, fuel oil, gasoline, natural gas, propane, and hydrogen recorded by the TSSA in their previous incident tracking system. The TSSA's Fuels Safety Program administers the Technical Standards & Safety Act 2000, providing fuel-related safety services associated with the safe transportation, storage, handling and use of fuels such as gasoline, diesel, propane, natural gas and hydrogen. Under this Act, the TSSA regulates fuel suppliers, storage facilities, transport trucks, pipelines, contractors and equipment or appliances that use fuels. Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of historical fuel spills and leaks in the province. This listing is a copy of the data captured at one moment in time and is hence limited by the record date provided here.

Government Publication Date: 2006-June 2009*

Indian & Northern Affairs Fuel Tanks: Federal IAFT

The Department of Indian & Northern Affairs Canada (INAC) maintains an inventory of aboveground & underground fuel storage tanks located on both federal and crown land. Our inventory provides information on the reserve name, location, facility type, site/facility name, tank type, material & ID number, tank contents & capacity, and date of tank installation.

Government Publication Date: 1950-Aug 2003*

TSSA Incidents: Provincial INC

List of spills and leaks of diesel, fuel oil, gasoline, natural gas, propane, and hydrogen reported to the Spills Action Centre (SAC) and made available by the Technical Standards and Safety Authority (TSSA). Under the Technical Standards & Safety Act (2000), the TSSA regulates fuel suppliers, storage facilities, transport trucks, pipelines, contractors, and equipment or appliances that use fuels. Includes incidents from fuel-related hazards such as spills, fires, and explosions. Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of fuel-related leaks, spills, and incidents in the province. The TSSA updates information in its system on an ongoing basis; this listing is hence limited by the record date provided here.

Government Publication Date: Feb 28, 2017

Landfill Inventory Management Ontario: Provincial LIMO

The Landfill Inventory Management Ontario (LIMO) database is updated every year, as the ministry compiles new and updated information. The inventory will include small and large landfills. Additionally, each year the ministry will request operators of the larger landfills complete a landfill data collection form that will be used to update LIMO and will include the following information from the previous operating year. This will include additional information such as estimated amount of total waste received, landfill capacity, estimated total remaining landfill capacity, fill rates, engineering designs, reporting and monitoring details, size of location, service area, approved waste types, leachate of site treatment, contaminant attenuation zone and more. The small landfills will include information such as site owner, site location and certificate of approval # and status.

Government Publication Date: Feb 28, 2019

Canadian Mine Locations: Private MINE

This information is collected from the Canadian & American Mines Handbook. The Mines database is a national database that provides over 290 listings on mines (listed as public companies) dealing primarily with precious metals and hard rocks. Listed are mines that are currently in operation, closed, suspended, or are still being developed (advanced projects). Their locations are provided as geographic coordinates (x, y and/or longitude, latitude). As of 2002, data pertaining to Canadian smelters and refineries has been appended to this database.

Government Publication Date: 1998-2009*

Mineral Occurrences: Provincial MNR

In the early 70's, the Ministry of Northern Development and Mines created an inventory of approximately 19,000 mineral occurrences in Ontario, in regard to metallic and industrial minerals, as well as some information on building stones and aggregate deposits. Please note that the "Horizontal Positional Accuracy" is approximately +/- 200 m. Many reference elements for each record were derived from field sketches using pace or chain/tape measurements against claim posts or topographic features in the area. The primary limiting factor for the level of positional accuracy is the scale of the source material. The testing of horizontal accuracy of the source materials was accomplished by comparing the plan metric (X and Y) coordinates of that point with the coordinates of the same point as defined from a source of higher accuracy.

Government Publication Date: 1846-Jan 2019

National Analysis of Trends in Emergencies System (NATES): Federal NATE

In 1974 Environment Canada established the National Analysis of Trends in Emergencies System (NATES) database, for the voluntary reporting of significant spill incidents. The data was to be used to assist in directing the work of the emergencies program. NATES ran from 1974 to 1994. Extensive information is available within this database including company names, place where the spill occurred, date of spill, cause, reason and source of spill, damage incurred, and amount, concentration, and volume of materials released.

Government Publication Date: 1974-1994*

Non-Compliance Reports: Provincial NCPL

The Ministry of the Environment provides information about non-compliant discharges of contaminants to air and water that exceed legal allowable limits, from regulated industrial and municipal facilities. A reported non-compliance failure may be in regard to a Control Order, Certificate of Approval, Sectoral Regulation or specific regulation/act.

Government Publication Date: Dec 31, 2017

National Defense & Canadian Forces Fuel Tanks: Federal NDFT

The Department of National Defense and the Canadian Forces maintains an inventory of all aboveground & underground fuel storage tanks located on DND lands. Our inventory provides information on the base name, location, tank type & capacity, tank contents, tank class, date of tank installation, date tank last used, and status of tank as of May 2001. This database will no longer be updated due to the new National Security protocols which have prohibited any release of this database.

Government Publication Date: Up to May 2001*

National Defense & Canadian Forces Spills: Federal NDSP

The Department of National Defense and the Canadian Forces maintains an inventory of spills to land and water. All spill sites have been classified under the "Transportation of Dangerous Goods Act - 1992". Our inventory provides information on the facility name, location, spill ID #, spill date, type of spill, as well as the quantity of substance spilled & recovered.

Government Publication Date: Mar 1999-Apr 2018

National Defence & Canadian Forces Waste Disposal Sites: Federal NDWD

The Department of National Defence and the Canadian Forces maintains an inventory of waste disposal sites located on DND lands. Where available, our inventory provides information on the base name, location, type of waste received, area of site, depth of site, year site opened/closed and status.

Government Publication Date: 2001-Apr 2007*

National Energy Board Pipeline Incidents: Federal NEBI

Locations of pipeline incidents from 2008 to present, made available by the Canada Energy Regulator (CER) - previously the National Energy Board (NEB). Includes incidents reported under the Onshore Pipeline Regulations and the Processing Plant Regulations related to pipelines under federal jurisdiction, does not include incident data related to pipelines under provincial or territorial jurisdiction.

Government Publication Date: 2008-Jun 30, 2019

National Energy Board Wells: Federal NEBP

The NEBW database contains information on onshore & offshore oil and gas wells that are outside provincial jurisdiction(s) and are thereby regulated by the National Energy Board. Data is provided regarding the operator, well name, well ID No./UWI, status, classification, well depth, spud and release date.

Government Publication Date: 1920-Feb 2003*

National Environmental Emergencies System (NEES): Federal NEES

In 2000, the Emergencies program implemented NEES, a reporting system for spills of hazardous substances. For the most part, this system only captured data from the Atlantic Provinces, some from Quebec and Ontario and a portion from British Columbia. Data for Alberta, Saskatchewan, Manitoba and the Territories was not captured. However, NEES is also a repository for previous Environment Canada spill datasets. NEES is composed of the historic datasets ' or Trends ' which dates from approximately 1974 to present. NEES Trends is a compilation of historic databases, which were merged and includes data from NATES (National Analysis of Trends in Emergencies System), ARTS (Atlantic Regional Trends System), and NEES. In 2001, the Emergencies Program determined that variations in reporting regimes and requirements between federal and provincial agencies made national spill reporting and trend analysis difficult to achieve. As a consequence, the department has focused efforts on capturing data on spills of substances which fall under its legislative authority only (CEPA and FA). As such, the NEES database will be decommissioned in December 2004.

Government Publication Date: 1974-2003*

National PCB Inventory: Federal NPCB

Environment Canada's National PCB inventory includes information on in-use PCB containing equipment in Canada including federal, provincial and private facilities. Federal out-of-service PCB containing equipment and PCB waste owned by the federal government or by federally regulated industries such as airlines, railway companies, broadcasting companies, telephone and telecommunications companies, pipeline companies, etc. are also listed. Although it is not Environment Canada's mandate to collect data on non-federal PCB waste, the National PCB inventory includes some information on provincial and private PCB waste and storage sites. Some addresses provided may be Head Office addresses and are not necessarily the location of where the waste is being used or stored.

Government Publication Date: 1988-2008*

National Pollutant Release Inventory: Federal NPRI

Environment Canada has defined the National Pollutant Release Inventory ("NPRI") as a federal government initiative designed to collect comprehensive national data regarding releases to air, water, or land, and waste transfers for recycling for more than 300 listed substances.

Government Publication Date: 1993-May 2017

Oil and Gas Wells: Private OGWE

The Nickle's Energy Group (publisher of the Daily Oil Bulletin) collects information on drilling activity including operator and well statistics. The well information database includes name, location, class, status and depth. The main Nickle's database is updated on a daily basis, however, this database is updated on a monthly basis. More information is available at www.nickles.com.

Government Publication Date: 1988-Aug 31, 2019

Ontario Oil and Gas Wells: Provincial OOGW

In 1998, the MNR handed over to the Ontario Oil, Gas and Salt Resources Corporation, the responsibility of maintaining a database of oil and gas wells drilled in Ontario. The OGSR Library has over 20,000+ wells in their database. Information available for all wells in the ERIS database include well owner/operator, location, permit issue date, and well cap date, license No., status, depth and the primary target (rock unit) of the well being drilled. All geology/stratigraphy table information, plus all water table information is also provide for each well record.

Government Publication Date: 1800-Jun 2019

Inventory of PCB Storage Sites: Provincial OPCB

The Ontario Ministry of Environment, Waste Management Branch, maintains an inventory of PCB storage sites within the province. Ontario Regulation 11/82 (Waste Management - PCB) and Regulation 347 (Generator Waste Management) under the Ontario EPA requires the registration of inactive PCB storage equipment and/or disposal sites of PCB waste with the Ontario Ministry of Environment. This database contains information on: 1) waste quantities; 2) major and minor sites storing liquid or solid waste; and 3) a waste storage inventory.

Government Publication Date: 1987-Oct 2004; 2012-Dec 2013

Orders: Provincial ORD

This is a subset taken from Ontario's Environmental Registry (EBR) database. It will include all Orders on the registry such as (EPA s. 17) - Order for remedial work, (EPA s. 18) - Order for preventative measures, (EPA s. 43) - Order for removal of waste and restoration of site, (EPA s. 44) - Order for conformity with Act for waste disposal sites, (EPA s. 136) - Order for performance of environmental measures.

Government Publication Date: 1994-Aug 31, 2019

Canadian Pulp and Paper: Private PAP

This information is part of the Pulp and Paper Canada Directory. The Directory provides a comprehensive listing of the locations of pulp and paper mills and the products that they produce.

Government Publication Date: 1999, 2002, 2004, 2005, 2009-2014

Parks Canada Fuel Storage Tanks: Federal PCFT

Canadian Heritage maintains an inventory of known fuel storage tanks operated by Parks Canada, in both National Parks and at National Historic Sites. The database details information on site name, location, tank install/removal date, capacity, fuel type, facility type, tank design and owner/operator.

Government Publication Date: 1920-Jan 2005*

Pesticide Register: Provincial PES

The Ontario Ministry of the Environment and Climate Change maintains a database of licensed operators and vendors of registered pesticides.

Government Publication Date: 1988-Mar 2019

TSSA Pipeline Incidents: Provincial PINC

List of pipeline incidents (strikes, leaks, spills) made available by the Technical Standards and Safety Authority (TSSA). Under the Technical Standards & Safety Act (2000), the TSSA regulates fuel suppliers, storage facilities, transport trucks, pipelines, contractors, and equipment or appliances that use fuels. Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of pipeline incidents in the province. The TSSA updates information in its system on an ongoing basis; this listing is hence limited by the record date provided here.

Government Publication Date: Feb 28, 2017

Private and Retail Fuel Storage Tanks: Provincial PRT

The Fuels Safety Branch of the Ontario Ministry of Consumer and Commercial Relations maintained a database of all registered private fuel storage tanks and licensed retail fuel outlets. This database includes an inventory of locations that have gasoline, oil, waste oil, natural gas and/or propane storage tanks on their property. The MCCR no longer collects this information. This information is now collected by the Technical Standards and Safety Authority (TSSA).

Government Publication Date: 1989-1996*

Permit to Take Water: Provincial PTTW

This is a subset taken from Ontario's Environmental Registry (EBR) database. It will include all PTTW's on the registry such as OWRA s. 34 - Permit to take water.

Government Publication Date: 1994-Aug 31, 2019

Ontario Regulation 347 Waste Receivers Summary: Provincial REC

Part V of the Ontario Environmental Protection Act ("EPA") regulates the disposal of regulated waste through an operating waste management system or a waste disposal site operated or used pursuant to the terms and conditions of a Certificate of Approval or a Provisional Certificate of Approval. Regulation 347 of the Ontario EPA defines a waste receiving site as any site or facility to which waste is transferred by a waste carrier. A receiver of regulated waste is required to register the waste receiving facility. This database represents registered receivers of regulated wastes, identified by registration number, company name and address, and includes receivers of waste such as: landfills, incinerators, transfer stations, PCB storage sites, sludge farms and water pollution control plants. This information is a summary of all years from 1986 including the most currently available data.

Government Publication Date: 1986-2016

Record of Site Condition: Provincial RSC

The Record of Site Condition (RSC) is part of the Ministry of the Environment's Brownfields Environmental Site Registry. Protection from environmental cleanup orders for property owners is contingent upon documentation known as a record of site condition (RSC) being filed in the Environmental Site Registry. In order to file an RSC, the property must have been properly assessed and shown to meet the soil, sediment and groundwater standards appropriate for the use (such as residential) proposed to take place on the property. The Record of Site Condition Regulation (O. Reg. 153/04) details requirements related to site assessment and clean up.
RSCs filed after July 1, 2011 will also be included as part of the new (O.Reg. 511/09).

Government Publication Date: 1997-Sept 2001, Oct 2004-Jul 2019

Retail Fuel Storage Tanks: Private RST

This database includes an inventory of retail fuel outlet locations (including marinas) that have on their property gasoline, oil, waste oil, natural gas and / or propane storage tanks.

Government Publication Date: 1999-Jul 31, 2019

Scott's Manufacturing Directory: Private SCT

Scott's Directories is a data bank containing information on over 200,000 manufacturers across Canada. Even though Scott's listings are voluntary, it is the most comprehensive database of Canadian manufacturers available. Information concerning a company's address, plant size, and main products are included in this database.

Government Publication Date: 1992-Mar 2011*

Ontario Spills: Provincial SPL

This database identifies information such as location (approximate), type and quantity of contaminant, date of spill, environmental impact, cause, nature of impact, etc. Information from 1988-2002 was part of the ORIS (Occurrence Reporting Information System). The SAC (Spills Action Centre) handles all spills reported in Ontario. Regulations for spills in Ontario are part of the MOE's Environmental Protection Act, Part X.

Government Publication Date: 1988-Feb 2019

Wastewater Discharger Registration Database: Provincial SRDS

Information under this heading is combination of the following 2 programs. The Municipal/Industrial Strategy for Abatement (MISA) division of the Ontario Ministry of Environment maintained a database of all direct dischargers of toxic pollutants within nine sectors including: Electric Power Generation; Mining; Petroleum Refining; Organic Chemicals; Inorganic Chemicals; Pulp & Paper; Metal Casting; Iron & Steel; and Quarries. All sampling information is now collected and stored within the Sample Result Data Store (SRDS).

Government Publication Date: 1990-Dec 31, 2017

Anderson's Storage Tanks: Private TANK

The information provided in this database was collected by examining various historical documents, which identified the location of former storage tanks, containing substances such as fuel, water, gas, oil, and other various types of miscellaneous products. Information is available in regard to business operating at tank site, tank location, permit year, permit & installation type, no. of tanks installed & configuration and tank capacity. Data contained within this database pertains only to the city of Toronto and is not warranted to be complete, exhaustive or authoritative. The information was collected for research purposes only.

Government Publication Date: 1915-1953*

Transport Canada Fuel Storage Tanks: Federal TCFT

List of fuel storage tanks currently or previously owned or operated by Transport Canada. This inventory also includes tanks on The Pickering Lands, which refers to 7,530 hectares (18,600 acres) of land in Pickering, Markham, and Uxbridge owned by the Government of Canada since 1972; properties on this land has been leased by the government since 1975, and falls under the Site Management Policy of Transport Canada, but is administered by Public Works and Government Services Canada. This inventory provides information on the site name, location, tank age, capacity and fuel type.

Government Publication Date: 1970-Aug 2018

TSSA Variances for Abandonment of Underground Storage Tanks: Provincial VAR

List of variances granted for abandoned tanks. Under the Technical Standards and Safety Authority (TSSA) Liquid Fuels Handling Code and Fuel Oil Code, all underground storage tanks must be removed within two years of disuse. If removal of a tank is not feasible, an application may be sought for a variance from this code requirement.
Records are not verified for accuracy or completeness. This is not a comprehensive or complete inventory of tank variances in the province. The TSSA updates information in its system on an ongoing basis; this listing is hence limited by the record date provided here.

Government Publication Date: Feb 28, 2017

Waste Disposal Sites - MOE CA Inventory: Provincial WDS

The Ontario Ministry of Environment, Waste Management Branch, maintains an inventory of known open (active or inactive) and closed disposal sites in the Province of Ontario. Active sites maintain a Certificate of Approval, are approved to receive and are receiving waste. Inactive sites maintain Certificate(s) of Approval but are not receiving waste. Closed sites are not receiving waste. The data contained within this database was compiled from the MOE's Certificate of Approval database. Locations of these sites may be cross-referenced to the Anderson database described under ERIS's Private Source Database section, by the CA number. All new Environmental Compliance Approvals handed out after Oct 31, 2011 for Waste Disposal Sites will still be found in this database.

Government Publication Date: Oct 2011-Aug 31, 2019

Waste Disposal Sites - MOE 1991 Historical Approval Inventory: Provincial WDSH

In June 1991, the Ontario Ministry of Environment, Waste Management Branch, published the "June 1991 Waste Disposal Site Inventory", of all known active and closed waste disposal sites as of October 30st, 1990. For each "active" site as of October 31st 1990, information is provided on site location, site/CA number, waste type, site status and site classification. For each "closed" site as of October 31st 1990, information is provided on site location, site/CA number, closure date and site classification. Locations of these sites may be cross-referenced to the Anderson database described under ERIS's Private Source Database section, by the CA number.

Government Publication Date: Up to Oct 1990*

Water Well Information System: Provincial WWIS

This database describes locations and characteristics of water wells found within Ontario in accordance with Regulation 903. It includes such information as coordinates, construction date, well depth, primary and secondary use, pump rate, static water level, well status, etc. Also included are detailed stratigraphy information, approximate depth to bedrock and the approximate depth to the water table.

Government Publication Date: Feb 28, 2019

Definitions

Database Descriptions: This section provides a detailed explanation for each database including: source, information available, time coverage, and acronyms used. They are listed in alphabetic order.

Detail Report: This is the section of the report which provides the most detail for each individual record. Records are summarized by location, starting with the project property followed by records in closest proximity.

Distance: The distance value is the distance between plotted points, not necessarily the distance between the sites' boundaries. All values are an approximation.

Direction: The direction value is the compass direction of the site in respect to the project property and/or center point of the report.

Elevation: The elevation value is taken from the location at which the records for the site address have been plotted. All values are an approximation. Source: Google Elevation API.

Executive Summary: This portion of the report is divided into 3 sections:

'Report Summary'- Displays a chart indicating how many records fall on the project property and, within the report search radii.

'Site Report Summary'-Project Property'- This section lists all the records which fall on the project property. For more details, see the 'Detail Report' section.

'Site Report Summary-Surrounding Properties'- This section summarizes all records on adjacent properties, listing them in order of proximity from the project property. For more details, see the 'Detail Report' section.

Map Key: The map key number is assigned according to closest proximity from the project property. Map Key numbers always start at #1. The project property will always have a map key of '1' if records are available. If there is a number in brackets beside the main number, this will indicate the number of records on that specific property. If there is no number in brackets, there is only one record for that property.

The symbol and colour used indicates 'elevation': the red inverted triangle will dictate 'ERIS Sites with Lower Elevation', the yellow triangle will dictate 'ERIS Sites with Higher Elevation' and the orange square will dictate 'ERIS Sites with Same Elevation.'

Unplottables: These are records that could not be mapped due to various reasons, including limited geographic information. These records may or may not be in your study area, and are included as reference.

Appendix D

Ministry of the Environment, Conservation and Parks

Access and Privacy Office

12th Floor
40 St. Clair Avenue West
Toronto ON M4V 1M2
Tel: (416) 314-4075
Fax: (416) 314-4285

Ministère de l'Environnement, de la Protection de la nature et des Parcs

Bureau de l'accès à l'information et de la protection de la vie privée

12e étage
40, avenue St. Clair ouest
Toronto ON M4V 1M2
Tél. : (416) 314-4075
Téléc.: (416) 314-4285

Ontario

October 29, 2019

John Gaviria_Ballen
DS Consultants
6221 Highway 7 Unit 16
Vaughan, ON L4H OK8

Dear John Gaviria_Ballen:

RE: ***Freedom of Information and Protection of Privacy Act* Request**
Our File # A-2019-07400, Your Reference 19-199-100

The Ministry is in receipt of your request made pursuant to the *Freedom of Information and Protection of Privacy Act* and has received your payment in the amount of $5.00 (non-refundable application fee), along with your $30.00 deposit.

The search is being conducted on the following: 2155 Country Club Dr, Burlington. If there is any discrepancy please contact us immediately.

You may expect a reply or additional communication as your request is processed. For your information, the Ministry charges for search, copying and preparation time.

If you have any questions regarding this matter, please contact Dany Briollais at dany.briollais@ontario.ca.

Yours truly,

Janet Dadufalza
Manager, Access and Privacy

71.00

Ministry of the Environment, Conservation and Parks

Access and Privacy Office

12th Floor
40 St. Clair Avenue West
Toronto ON M4V 1M2
Tel: (416) 314-4075
Fax: (416) 314-4285

Ministère de l'Environnement, de la Protection de la nature et des Parcs

Bureau de l'accès à l'information et de la protection de la vie privée

12e étage
40, avenue St. Clair ouest
Toronto ON M4V 1M2
Tél. : (416) 314-4075

Ontario

December 17, 2019

John Gaviria-Ballen
DS Consultants Ltd.
6221 Highway 7, Unit 16
Vaughan, ON L4H OK8

Dear John Gaviria-Ballen:

RE: *Freedom of Information and Protection of Privacy Act* Request
Our File #: A-2019-07400, Your Reference #: 19-199-100

This letter is in response to your request made pursuant to the *Freedom of Information and Protection of Privacy Act* relating to 2155 Country Club Dr, Burlington.

After a thorough search of the Ministry's Halton Peel District Office, Investigations and Enforcement Branch, Environmental Assessment and Permissions Branch, Environmental Monitoring and Reporting Branch, Sector Compliance Branch and Safe Drinking Water Branch, records were located in response to your request. It is my preliminary decision to provide partial access to the information as the identity of complainants will be removed to protect privacy (Section 21(1)(f) of the Act).

In accordance with Section 57 of the *Freedom of Information and Protection of Privacy Act*, the estimated fee is:

• Search Time 1 hour @ $30/hour	$30.00
• CD	10.00
• Preparation Time approx. 0.10 hour @ $30/hour	$3.00
• Delivery	3.00
• **Total**	**$ 46.00**
• Deposit Received	-$30.00
• **Balance Due**	**$16.00**

Due to the volume, the records will be provided to you electronically on a CD. The Ministry has relied on Order PO-3621 by the Office of the Information and Privacy Commission (IPC) in order to calculate the estimated fees. Order PO-3621 states that the Ministry may charge a preparation fee of $30.00 per hour for every 1,200 pages of scanned records. The breakdown of the approximate preparation fee is as follows: an estimated 0.10 hours to convert approximately 120 pages to electronic format. Please note, that upon completion of the Ministry's review, additional preparation charges may be applied to account for any severances made to the records in accordance with the exemptions under the Act. These severances will be charged at a rate of $30.00 per hour, calculated at a rate of two minutes per page.

In order to receive a copy of the records please forward this amount to our office. You may pay by money order or cheque (made payable to the "Minister of Finance (FOI)") or by credit card. Credit card forms are available on the Ministry's website http://www.ontario.ca/environment-and-energy/freedom-information-request-form. Please do not mail cash.

If payment has not been received within 45 days this file will be closed. When remitting payment, please quote our file number or attach a copy of this letter.

The District Office has advised that there may be records in the Records Centre, Mississauga. To retrieve these files there is a charge of $60.00 with no guarantee that any records will be located responsive to your request. If you would like us to retrieve these files, $60.00 in addition to the above amount is required.

Please note, a request for records must usually be answered within 30 calendar days, however Section 27 allows for time extensions under certain circumstances. If you choose to have the search conducted at the Environmental Assessment and Permissions Branch and/or the files retrieved from the Records Centre, the time for answering your request will be extended for an additional 30 days.

You may request a review of my decision by contacting the Information and Privacy Commissioner/Ontario, 2 Bloor Street East, Suite 1400, Toronto, ON M4W 1A8 (800-387-0073 or 416-326-3333). Please note that there is a $25.00 fee and you only have 30 days from receipt of this letter to request a review.

If you have any questions regarding this matter, please contact Dany Briollais at 416-314-4075.

Yours truly,

Dalia Bouganim
Manager, Access and Privacy

Monika Orwin

From: Public Information Services <publicinformationservices@tssa.org>
Sent: Tuesday, October 22, 2019 8:11 AM
To: John.gaviriaballen
Subject: RE: Fuel Tank Records Review

NO RECORD FOUND (FUEL STORAGE TANKS ONLY)

Hello. Thank you for your request for confirmation of public information.

We confirm that there are no records in our database of any fuel storage tanks at the subject addresses.

For a further search in our archives please complete our release of public information form found at https://www.tssa.org/en/about-tssa/release-of-public-information.aspx?_mid_=392 and email the completed form to publicinformationservices@tssa.org or through mail along with a fee of $56.50 (including HST) per location. The fee is payable with credit card (Visa or MasterCard) or with a Cheque made payable to TSSA.

Although TSSA believes the information provided pursuant to your request is accurate, please note that TSSA does not warrant this information in any way whatsoever.

Kind regards,

Gaya

From: John.gaviriaballen <John.gaviriaballen@dsconsultants.ca>
Sent: October 21, 2019 4:48 PM
To: Public Information Services <publicinformationservices@tssa.org>
Subject: Fuel Tank Records Review

To whom may concern,

I want to check if the following location have records:
4274 Dundas St.
3040 Tim Dobbie Dr.
3035 Tim Dobbie Dr.

Burlington, ON
Thanks,

John Gaviria-Ballen, EIT
Environmental Technician
DS Consultants Ltd
6221 Highway 7, Unit 16, Vaughan, ON, L4H 0K8
Tel: (905) 264-9393
Cell: (613) 618-8815
www.dsconsultants.ca

Appendix E



© County Atlas Project

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

HALTON COUNTY ATLAS: 1880		
Scale: NTS	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT** **Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-1**




© NAPL

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 1954

Scale: ~1:4800	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT** **Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-2**



© NAPL

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 1962

Scale: ~1:4700	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-3**



© NAPL

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 1972

Scale: ~1:4800	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-4**



© Halton Public Works

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 1987

Scale: ~1:4000	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-5**



© City of Burlington

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 1995

Scale: ~1:3300	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-6**



© Google Earth

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 2002

Scale: ~1:4800	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-7**



© Google Earth

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 2005

Scale: ~1:3800	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-8**



© City of Burlington

	AERIAL PHOTOGRAPH: 2011	
Scale: ~1:2800	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT** **Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-9**

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685



© Google Earth

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 2015

Scale: ~1:3700	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-10**



© Google Earth

6221 Highway 7
Vaughan, ON L4H 0K8
T: 905-264-9393 F: 905-264-2685

AERIAL PHOTOGRAPH: 2019

Scale: ~1:2900	**PHASE ONE ENVIRONMENTAL SITE ASSESSMENT Millcroft Golf Club (Area 3), Burlington, Ontario**	Prepared By: JGB
Date: Jan-20		Reviewed By: DD
Project: 19-199-102	Prepared For: Argo (Millcroft) Limited	Drawing No. **D-11**

Appendix F



Picture 1: View of the maintenance building present on the Phase One Property, facing west.



Picture 2: View of adjacent properties northwest of the Phase One Property, facing northwest.



Picture 2: View of adjacent properties northeast of the Phase One Property, facing northeast.



Picture 4: View of the south adjacent properties to the Phase One Property, facing south.



Picture 5: View of the east portion of the Phase One Property, facing east.



Picture 6: View of the west end of the Phase One Property, facing west.



Picture 7: View of one (1) waste oil AST, and one (1) drum of lubricant oil, east to the maintenance building, facing northwest.



Picture 8: View of one (1) diesel AST east to the maintenance building, facing northwest.



Picture 9: View of one (1) gasoline AST east to the maintenance building, facing northeast.



Picture 10: View of the stockpiles of topsoil, sand and tee mix on the northcentral portion of the Phase One property, facing northeast.



Picture 11: View of the septic tank system located north adjacent of the maintenance building, facing south.




Picture 12: Miscellaneous lawnmowers (no oil staining in soil observed) to the south of the Property, facing south..



Picture 13: View of inside maintenance building, area allocated to fixed lawnmowers and golf carts, facing south.




Picture 14: One (1) hydraulic hoist was observed inside, to the south end of the maintenance building, facing west.



Picture 15: Compressed gas tanks were observed inside the maintenance work area, facing west.



Picture 16: One (1) transformer was observed on the west section of the building, facing south.



Picture 17: View of the pesticide storage room, at the northeast corner of the building, facing north.



Picture 18: View of the oil/water separator located at the north of the building, facing north.