The Odan/Detech Group Inc.
P: (905) 632-3811
F: (905) 632-3363
5230, SOUTH SERVICE ROAD, UNIT 107
BURLINGTON, ONTARIO, L7L 5K2
www.odandetech.com

PROPOSED RESIDENTIAL
APARTMENT BUILDING DEVELOPMENT
284-292 PLAINS ROAD EAST
CITY OF BURLINGTON

PROJECT No.: 20223

FUNCTIONAL SERVICING & STORMWATER MANAGEMENT REPORT

Prepared For:

BROOKLYN CONTRACTING

Prepared By:

The Odan/Detech Group Inc.

Original:	December 23rd, 2020
Revised:	April 16th, 2021
Revised:	April 22nd, 2021
Revised:	September 17th, 2021
Revised:	September 1st, 2022
Revised:	October 12th, 2022

TABLE OF CONTENTS

DESCRIPTION page

1.0 INTRODUCTION....3
2.0 SCOPE OF WORK....3
3.0 WATER DISTRIBUTION ASSESSMENT....4
i) Existing Infrastructure....4
ii) Proposed Servicing....4
4.0 SANITARY SEWERS....8
i) Existing Infrastructure & Drainage....8
ii) Proposed Servicing....8
iii) Receiving Downstream Sanitary Sewer Capacity....10
5.0 STORM WATER MANAGEMENT....14
i) Existing Infrastructure & Drainage....14
ii) Stormwater Quantity Control Criteria....16
iii) Allowable Discharge Flow Rate....16
iv) Post Development Flow Analysis....17
v) Water Budget/Stormwater Retention....22
vi) Water Quality....23
6.0 GROUNDWATER....26
i) Introduction....26
ii) Long-Term Groundwater....26
iii) Short-Term (Construction) Groundwater....26
7.0 CONCLUSIONS....27
8.0 REFERENCES....28

LIST OF FIGURES

Figure 1 - Visual OTTHYMO Model (Showing Flows in 100-Year Storm) 20
Figure 2 - Excerpt from CETV Verification Statement for Stormceptor OGS 24
Figure 3 - Excerpt from CETV Verification Statement for Jellyfish Filter 25

LIST OF TABLES

TABLE 1 – Total Water Demand for Proposed Building 4
TABLE 2 – Post-Development Sanitary Flow 8
TABLE 3 – Allowable Flows (Pre-Development 5-year storm runoff) 16
TABLE 4 - Catchment Characteristics for the site Post-Development 18
TABLE 5 – Stage/Storage/Discharge Relationship for Orifice Control 20
TABLE 6 – Stormwater Management Summary 21
TABLE 7 - Summary 27

APPENDIX A

Existing Site	Aerial view of Site and surrounding area
Site Plan & Statistics	by SRM Architects

APPENDIX B

Visual OTTHYMO Model Output (2-Year & 100-Year storms)
CETV Verification Statement – Imbrium Systems Inc. Stormceptor OGS
CETV Verification Statement – Imbrium Systems Inc. Jellyfish Filter

APPENDIX C

Email Correspondence from Regional Engineering Staff regarding Watermains and hydrant tests thereof

APPENDIX D

Functional Servicing Plan
Functional Grading Plan

1.0 INTRODUCTION

The subject of this report is a 0.31 Ha (0.77 acres) parcel of land bound by the following:

- To the east: an existing house of commercial use
- To the south: detached houses
- To the west: existing houses of commercial use
- To the north: Plains Road East

Presently the site comprises two houses, one of which has been converted to commercial use.

Refer to the Key Plan in Appendix A for the site's layout and adjacent properties.

It is proposed to construct a 6-Storey (plus mechanical penthouse) residential tower. The building will be constructed ontop of a below-grade parking structure.

Refer to the architectural site plan in Appendix A for the proposed development's layout.

The municipal addresses of the site comprise 284-292 Plains Road East.

For detailed topography of the existing site conditions, as of February 2018, refer to the topographic survey prepared by David B. Searles Surveying Ltd.

This report evaluates the serviceability of the site with respect to sanitary waste water, water and storm water management (SWM) and will implement the City of Burlington's SWM requirements.

2.0 SCOPE OF WORK

THE ODAN/DETECH GROUP INC. was retained by **Brooklyn Contracting** to review the Site, collect data, evaluate the Site for the proposed use and present the findings in a Functional Servicing and Storm Water Management Report in support of a Rezoning application. The scope of work in brief involves the following:

a) Collecting existing servicing drawings from the CITY in order to establish availability and feasibility of Site servicing;
b) Meetings/conversations with CITY Engineers and Design Team.
c) Evaluation of the data and presentation of the findings in a Functional Servicing and Storm Water Management Report in support of the Rezoning application.

3.0 WATER DISTRIBUTION ASSESSMENT

i) Existing Infrastructure

The following watermains presently exist beneath the streets bordering the site. Refer to the Functional Servicing Plan.

- Plains Road East, south side: 400mm watermain
- Plains Road East, north side: 300mm watermain
- Plains Road East, beneath road centreline: 600mm watermain

ii) Proposed Servicing

The proposed building is proposed to be serviced by a 200mm fire service connection from the 400mm watermain beneath the south side of Plans Road with branch 150mm domestic water service.

The 600mm watermain is a trunk watermain and it is assumed it would thus not be permitted to connect-to.

It was feasible to conduct a hydrant flow test on the 300mm watermain on the north side of the street (provided below) – but not the 400mm watermain within the south side of Plains Rd., due to unavailability of hydrants. Regional engineering staff confirmed that conclusions may be drawn regarding system adequacy from the test on the 300mm watermain, nonetheless, as per the email correspondence provided here in Appendix C.

The building will be less than 85m in height, therefore OBC 2006 3.2.9.7 (4) does not require a second fire service

Refer to the Functional Servicing Plan for proposed service connections.

The water demand for the proposed building is as follows.

a) Average Day domestic demand - As per average sanitary flow 0.8 L/sec

b) Peak day demand - 2.25 x average demand 1.8 L/sec

c) Fire flow as per FUS 1999 manual calculation, below 133 L/sec

TABLE 1 – Total Water Demand for Proposed Building

	L/sec	USGM
Peak Day Demand	1.8	28
Fire Flow Demand	133	2113
Total Water Demand	135	2141
Available Flow at 20 PSI (Plains Rd. E. 300mm WM)	201	3182

Hydrant flow test results as stated above are provided below.

The following assumptions are made in the following Fire Underwriters' Survey fire flow calculation.

- The proposed building is of fire-resistive construction (reinforced concrete)
- The building will be sprinklered for fire protection and the sprinklers will be fully monitored according to NFPA 13
- The building's contents (residences) will be non-combustible in nature
- The building's areas in the calculation are as per the architectural floor areas provided in Appendix A

The hydrant flow test was conducted as per the NFPA 291 hydrant testing standard on a hydrant adjacent to 305 Plains Rd. E. Refer to the test report, below.

The available flow at 20 psi in the Plains Rd. E. 300mm watermain is 3182 USGM which is greater than the proposed development's total water demand (2141 USGM), therefore the existing watermain infrastructure is sufficient to service the proposed development and no watermain infrastructure upgrades are required.

WATER SUPPLY FOR PUBLIC FIRE PROTECTION , FIRE UNDERWRITERS SURVEY GUIDE
FOR DETERMINATION OF REQUIRED FIRE FLOWS

$F = 220 \times C \times \sqrt{A}$

Where:

F = required fire flow in liters per minute
C= Coefficient related to the type of construction
A = the total floor area in square meters (excluding basements) in the building considered

Coefficient related to type of construction	
1.5	Wood Frame
1	Ordinary
0.8	Non combustible
0.6	Fire Resistive

LOCATION: 284-292 Plains Rd. E., Burlington

OBC OCCUPANCY: Residential Apartment

BUILDING FOOT PRINT (m2): 1378

OF STOREYS: 6

PROJECT: 284-292 Plains Rd. E., Burlington

PROJECT No: 20223

Contents	Charge
Non-Combustible	-25%
limited Combustible	-15%
Combustible	0%
Free Burning	15%
Rapid Buring	25%

CONSTRUCTION CLASS: Fire Resistive

AUTOMATED SPRINKLER PROTECTION

		Credit	Total
NFPA 13 sprinkler standard	yes	10%	
Standard Water Supply	yes	30%	50%
Fully Supervised System	yes	10%	
		50%	

CONTENTS FACTOR: Non Combustible — CHARGE: -20%

EXPOSURE 1 (south) Ex. House	Distance to Exposure Building (m) / Length - Height	22	10%
EXPOSURE 2 (east) Ex. House	Distance to Exposure Building (m) / Length - Height	21	20%
EXPOSURE 3 (west) Ex House	Distance to Exposure Building (m) / Length - Height	16	15%
EXPOSURE 4 (north) Ex. Church	Distance to Exposure Building (m) / Length - Height	>45	0%
		Total:	45%

no more than 75%

Separation	Charge
0-3 m	25%
3.1 -10 m	20%
10.1 - 20 m	15%
20.1 - 30 m	10%
30.1 - 45	5%
> 45 m	0%

ARE BUILDINGS CONTIGUOUS: NO

FIRE RESISTANT BUILDING — Are vertical openings and exterior vertical communications protected with a minimum one (1) hr rating? No

CALCULATIONS

	C =	0.6		
	A =	5951	m2	(2 largest floors + 50% floors above)
	F =	10183	L/min	
Round to Nearest 1000 L/min	F =	10000	L/min	must be > 2000 L/min

STOREY AREAS m2	
1314	L1
1564	L2
1537	L3
1484	L4
1378	L5
1272	L6
475	Mech

CORRECTION FACTORS:

OCCUPANCY	-2000	L/min
FIRE FLOW ADJUSTED FOR OCCUPANCY	8000	L/min
REDUCTION FOR SPRINKLER	-4000	L/min
EXPOSURE CHARGE	3600	L/min

REQUIRED FIRE FLOW

	F =	7600	L/min	
Round to Nearest 1000 L/min	**F =**	8000	L/min	2113 usgm
	F =	133	L/sec	

FLOWMETRIX
INDU-TECH
PROCESS
WESTCAN

Fire Flow Testing Report

Residual Hydrant # **HY212735**
NFPA Colour Code **BLUE**

DATE	April 20, 2021
TIME	9:50 AM
ADDRESS	305 Plains Rd E
	Burlington, ON
	L7T 2C7
SIZE-inches/mm	12 300
MATERIAL	CI
CONTACT INFO	Brooklyn Contracting Inc.
	Marko A. Juricic
	P : 289-337-2707 ext: 210
	E : marko@brooklyncontract.com

RESIDUAL HYDRANT INFO.


HYDRANT #	HY212735	
N.F.P.A. COLOUR CODE	BLUE	
STATIC PRESSURE	53.2	psi
RESIDUAL PRESSURE	46.7	psi
PRESSURE DROP	6.5	psi
% PRESSURE DROP	12.2	% psi

Flow on Water Main At Test Hydrant - 20 psi 7674 USGPM

FLOW HYDRANT(S) INFO.

HYDRANT ASSET ID	HYD. # PORTS	OUTLET DIAMETER (INCHES)	NOZZLE COEFFICIENT	DIFFUSER TYPE	DIFFUSER COEFFICIENT	PITOT READING (psi)	PITOT FLOW (USGPM)	FLOW METER (USGPM)
HY5748	2	2.5	Round	Swivel	1.00	**22.5**	1591	0
		2.5	Round	Swivel	1.00	**22.5**	1591	0
					Total Flow (USGPM)		3182	0
					Total Flow (USGPM)		3182	

FIRE FLOW CHART



COMMENTS

OPERATOR	FMX	Jordan Whitlock
OPERATOR	FMX	Denis Kriventsev
OPERATOR		Halton Region

Copy of Copy of Fire Flow Testing Report - Plains Rd

"If we don't measure it, how do you manage it?"

4.0 SANITARY SEWERS

i) Existing Infrastructure & Drainage

The following sanitary sewers are located within the streets bordering the subject site. Refer to the Functional Servicing Plan, for the layout of the existing sanitary sewers adjacent to the subject site.

- Plains Road East, south side: there is a 250mm sanitary sewer which commences near the site's northeast corner and flows westerly before continuing southerly beneath Shadeland Avenue to the west.

- Plains Road East, north side: there is a 250mm sanitary sewer flowing easterly.

ii) Proposed Servicing

It is proposed to service the proposed building using a proposed 200mm sanitary service connection to the 250mm sanitary sewer beneath Plains Rd. E.

Refer to the Functional Servicing Plan for the proposed sanitary service connection. Sanitary flows are calculated as follows.

The sanitary sewer design criteria and unit flow is provided in the Regional Municipality of Halton's *Water and Wastewater Linear Design Manual* (April 2019), as follows. The following information is provided in Tables 3-1 and 3-2 of the foregoing manual.

- Unit flow: q = average daily residential per capita dry weather unit flow = 0.275 m^3/cap/day
- I/I = Unit of peak inflow/infiltration = 0. 286 L/s/ha
- Apartment (over 6-storey): 285 p/Ha and 0.275 m^3/p/day or 0.003183 x 10^{-3} m^3/p/s
- Apartment (6-storeys or less): 135 p/Ha and 0.275 m^3/p/day or 0.003183 x 10^{-3} m^3/p/s
- Notwithstanding the above unit population, however, a unit population of 2.7 P/unit is assumed for the proposed apartment tower development because the Region standard 285 P/Ha unit population (apartments <6-storeys) would result in a unit population of approximately 0.3 Person/unit for the foregoing proposed statistics, which is unrealistic

The proposed sanitary flows are as follows. Refer to the detailed calculation on the following pages.

TABLE 2 – Post-Development Sanitary Flow

Component	Population (P)	Sanitary Flow (l/s)	Groundwater Discharge (l/s)	Inflow & Infiltration (l/s)	Total Flow (l/s)
Residential Flows	289	3.28	N/A	0.09	3.4

The 3.4 L/s total sanitary flow for the proposed building will be conveyed to the existing 250mm sanitary sewer beneath Plains Rd. E. by a proposed 200mm at 2.0% (43 L/s capacity) sewer connection. This sewer connection is adequately sized to convey the above flow. This connection is deliberately oversized anticipating that the mechanical engineer's OBC criteria for the mechanical pipe leaving the building will require a larger-size pipe than municipal criteria would require.

SANITARY & WATER FLOW CALCULATIONS — **SCENARIO:** PROPOSED DEVELOPMENT

This program calculates the sanitary discharge from various land use

FILL IN COLOURED CELLS AS REQUIRED

COMMERCIAL SITE AREA (ha) =

NOTE:

RESIDENTIAL SITE AREA (ha) = 0.31

TOTAL SITE AREA (ha) = 0.31

LAND USE	NUMBER OF UNITS	SITE AREA, (ha)	GROSS FLOOR AREA, m2	TOTAL POPULATION	TOTAL DAILY FLOW (LITERS)	AVERAGE DAILY FLOW l/sec	PEAKING FACTOR, M	TOTAL FLOW FROM LAND USE, l/sec
RESIDENTIAL Detached, using 55 person/site area				0	0	0.00	4.50	0.00
RESIDENTIAL Semi Houses, using 100 persons/site area				0	0	0.00	4.50	0.00
RESIDENTIAL Apartments (<6 st), using 135 persons/site area				0	0	0.00	4.50	0.00
RESIDENTIAL Apartments (>6 st), using 285 persons/site area				0	0	0.00	4.50	0.00
RESIDENTIAL Density 3, using 2.7 persons/unit	107			289	69336	0.80	4.09	3.28
COMMERCIAL, Using 90 persons/ha (Floor Ha)				0	0	0.00	3.60	0.00
COMMERCIAL, Using 0.60 L/sec per ha				0	0	0.00	2.50	0.00

TOTAL V1= 69336 Q1= 3.28

Q2= 0.00

Q = (MqP/86400) + A * I (L/sec) Qinfil 0.09

Qtot 3.37

Q1= total flow from Residential Land Use (L/sec)

Q2= total flow from Commercial Land Use (L/sec)

Qinfil = total flow from infiltration (L/sec)

Qtot = total flow (Land use + infiltration)

V1= Total Volume from Land Use in liters

where : P is population

q = 0.275 m3/d/p = 0.004 L/sec/person for residential and

q = 0.60 L/sec/ha for commercial and offices

A = gross site area

i = 0.286 L/sec/ha (infiltration rate)

Peaking Factor M = 1 + [14 / (4 + (P/1000,1/2)) (for residential)

Peaking Factor M = 0.8* {1 + [14 / (4 + (P/1000,1/2))]} (for Commercial)

iii) Receiving Downstream Sanitary Sewer Capacity

The proposed development is proposed to discharge into the existing 250mm sanitary sewer flowing westerly beneath Plains Rd. E. as discussed above. Consideration is required for this sewer's capacity to receive the proposed flows.


Region engineering staff have stated in the *Halton Region Servicing Comments* section of the preconsultation checklist dated March 10, 2021 that the FSR should incorporate a hydraulic analysis of the receiving wastewater mains. That memo states that this analysis should be based on either the Region's model or an original analysis prepared by the consultant in reference to the Region's latest Linear Infrastructure Design Manual. An original analysis is therefore provided herein in reference to the latest Linear Design Manual.

The analysis is provided on the following pages. The analysis comprises a catchment plan identifying the tributary catchment areas and statistics, on the following page, and two conventional sewer analysis sheets: pre-development and post-development.

This analysis has considered two downstream segments, until the outlet to a 450mm sanitary sewer flowing southerly beneath Shadeland Ave. to the west.

The following discussion and conclusions are drawn from the analysis on the following pages.

- In pre-development conditions the downstream pipes are flowing within capacity (less than 4% of the pipes' capacity)
- In post-development conditions, with the additional flows from the subject Development, the downstream pipes are flowing within capacity, up to 17% of the pipes' capacity
- Given that the downstream pipes are flowing well within their respective capacities – no downstream sanitary sewer system upgrades are necessary to accommodate the proposed development



LEGEND

CATCHMENT BOUNDARY – EXISTING BUILDING

TOTAL TRIBUTARY AREA (HA) — 1 / 0.03 50 — TRIBUTARY AREA ID / POPULATION DENSITY (P/Ha)

FIGURE 4

DATE:	PROJ. NO.:	SCALE:
APRIL 2020	20223	1 : 600

DRAWING : DOWNSTREAM SANITARY SEWER CATCHMENT PLAN

PROJECT : 284–292 PLAINS RD. E. PROPOSED RESIDENTIAL DEVELOPMENT

ODAN·DETECH CONSULTING ENGINEERS
The Odan/Detech Group Inc. P: (905) 632-3811 F: (905) 632-3363
5230 SOUTH SERVICE ROAD, BURLINGTON, ONTARIO, L7L 5K2

SANITARY SEWER DESIGN SHEET - Existing Plains Rd. E. Sewer - Pre-Development Scenario

Site location: 284-292 Plains Road East, Burlington

Ref# PN 20223

Location				Inlet Flow																	Pipe						
				Industrial/Commercial					Residential Population				Inflow/ Infiltration	K(av) Factor	Industrial & Commercial P/F	Peak Industrial & Commercial Flow	Residential P/F	Peak Residential Sanitary Flow	Unit Inflow/ Infiltration	Segment Inflow/ Infiltration	Accumulative Inflow/ Infiltration	Accumulative Sanitary Flow	Length	Size	Slope	Shape	Full Flow Capacity	Full Flow Velocity	% Full
	Street Name	US Node	DS Node	Industrial (ha)	Commercial (ha)	Acc've Area (ha)	Population (Person)	Acc've Pop'n (Person)	Apartments (Ha)	SFD (Ha)	Population (Person)	Acc've Pop'n (Person)	Area (ha)	Kav	M	Q(p) (L/s)	M	Q(p) (275 L/c/d) (L/s)	I/I (0.28 L/Sec/ha)	Q(i) (L/s)	Q(i) (L/s)	Q(d) (L/s)	L (m)	D (mm)	S (%)		Qcap (L/s)	V (m/s)	Q(d)/Qcap
1 & 2 & 3	Plains Rd. E.	EX SAN MH 1	EX SAN MH 2	-	0.340	0.340	30.60	30.60	-	0.110	6.05	6.05	0.62	0.85	3.70	0.36	3.76	0.07	0.280	0.17	0.17	0.61	95.65	250	0.43	circle	39.00	0.79	1.55%
4 & 5	Plains Rd. E.	EX SAN MH 2	EX SAN MH 5	-	0.190	0.53	17.10	47.70	-	0.440	24.20	30.25	0.80	0.90	3.89	0.59	3.93	0.38	0.280	0.22	0.40	1.37	101.84	250	0.42	circle	38.54	0.79	3.55%

Flow Calculation Criteria
(Unit Flowfrom Table 3-1 and 3-2, Regional Municipality of Halton, Water and Wastewater Linear Design Manual, April 2019)
q = average daily residential per capita dry weather unit flow = 0.275 m3/cap/d
q = average daily commercial dry weather unit flow = 24.750m3/ha/d or 0.28646 L/ha/s
I/I = Unit of peak inflow/infiltration allowance = 0.286 (L/s/ha)
Q(p) = peak population flow (L/s)
Q(I) = peak extraneous flow (L/s)
Q(d) = peak design flow (L/s)

Mannings Equation:

Qcap=(D/1000)^2.667*(S/100)^0.5/(3.211*n)*1000(L/s)
D: pipe size (mm)
S: slope (grade) of pipe (%)
n = Manning roughness coefficient = 0.013

(Unit Population from Table 3-1 and 3-2, Regional Municipality of Halton, Water and Wastewater Linear Design Manual, April 2019)

Single Family Population Density	55 P/ha
Semi-detached/duplex/4-plex	100 P/ha
Townhouse, Maisonette	135 P/ha
Apartment (Over 6 Stories High)	285 P/ha
Commercial	90 P/ha

(Peaking Factor from Section 3.2.3., Regional Municipality of Halton, Water and Wastewater Linear Design Manual, April 2019)

PEAKING FACTOR (All Land Uses)	M =Kav*[1 + 14/(4+(P/1000^0.5))]
K(av) factor	Kav=(Ar + 0.80x(Ai+Ac))/(Ar+Ai+Ac)
PEAK DESIGN FLOW,	Q(d) = Q(p) + Q(i) L / Sec.
PIPE ROUGHGNESS,	n = 0.013 For Manning's Equation

Vmin. = 0.6m/s and Vmax. = 3m/s

SANITARY SEWER DESIGN SHEET - Existing Plains Rd. E. Sewer - Post-Development Scenario

Site location: 284-292 Plains Road East, Burlington

Ref# PN 20223

Location				Inlet Flow																		Pipe						
				Industrial/Commercial					Residential Population				Inflow/ Infiltration	K(av) Factor	Industrial & Commercial P/F	Peak Industrial & Commercial Flow	Residential P/F	Peak Residential Sanitary Flow	Unit Inflow/ Infiltration	Segment Inflow/ Infiltration	Accumulative Inflow/ Infiltration	Pumped Groundwater/ Foundation	Accumulative Sanitary Flow	Length	Size	Slope	Shape	Full Flow Capacity	Full Flow Velocity	% Full
	Street Name	US Node	DS Node	Industrial (ha)	Commercial (ha)	Acc've Area (ha)	Population (Person)	Acc've Pop'n (Person)	Apartments (Ha)	SFD (Ha)	Population (Person)	Acc've Pop'n (Person)	Area (ha)	Kav	M	Q(p) (L/s)	M	Q(p) (275 L/c/d) (L/s)	I/I (0.28 L/Sec/ha)	Q(i) (L/s)	Q(i) (L/s)	Q (gw) (L/s)	Q(d) (L/s)	L (m)	D (mm)	S (%)		Qcap (L/s)	V (m/s)	Q(d)/Qcap
1 & 2 & 3	Plains Rd. E.	EX SAN MH 1	EX SAN MH 2	-	0.140	0.140	12.60	12.60	0.310	-	316.00	316.00	0.62	0.94	4.13	0.17	3.82	3.84	0.280	0.17	0.17	2.00	6.18	95.65	250	0.43	circle	39.00	0.79	15.84%
4 & 5	Plains Rd. E.	EX SAN MH 2	EX SAN MH 5	-	0.190	0.33	17.10	29.70	-	0.440	24.20	340.20	0.80	0.90	3.91	0.37	3.64	3.94	0.280	0.22	0.40	-	6.70	101.84	250	0.42	circle	38.54	0.79	17.40%

Flow Calculation Criteria
(Unit Flowfrom Table 3-1 and 3-2, Regional Municipality of Halton, Water and Wastewater Linear Design Manual, April 2019)
q = average daily residential per capita dry weather unit flow = 0.275 m3/cap/d
q = average daily commercial dry weather unit flow = 24.750m3/ha/d or 0.28646 L/ha/s
I/I = Unit of peak inflow/infiltration allowance = 0.286 (L/s/ha)
Q(p) = peak population flow (L/s)
Q(I) = peak extraneous flow (L/s)
Q(d) = peak design flow (L/s)

Mannings Equation:

Qcap=(D/1000)^2.667*(S/100)^0.5/(3.211*n)*1000(L/s)
D: pipe size (mm)
S: slope (grade) of pipe (%)
n = Manning roughness coefficient = 0.013

(Unit Population from Table 3-1 and 3-2, Regional Municipality of Halton, Water and Wastewater Linear Design Manual, April 2019)

Single Family Population Density	55 P/ha
Semi-detached/duplex/4-plex	100 P/ha
Townhouse, Maisonette	135 P/ha
Apartment (Over 6 Stories High)	285 P/ha
Apartment (per unit)	2.7 P/unit
Commercial	90 P/ha

(Peaking Factor from Section 3.2.3., Regional Municipality of Halton, Water and Wastewater Linear Design Manual, April 2019)

PEAKING FACTOR (All Land Uses)	M =Kav*[1 + 14/(4+(P/1000^0.5))]
K(av) factor	Kav=(Ar + 0.80x(Ai+Ac))/(Ar+Ai+Ac)
PEAK DESIGN FLOW,	Q(d) = Q(p) + Q(i) L / Sec.
PIPE ROUGHGNESS,	n = 0.013 For Manning's Equation

Vmin. = 0.6m/s and Vmax. = 3m/s

5.0 STORM WATER MANAGEMENT

i) Existing Infrastructure & Drainage


The following storm sewers presently existing beneath the streets adjacent to the site

- Plains Road East, south side: there is an existing 600mm storm sewer flowing easterly, which continues southerly beneath Filmandale Road to the east.

- Plains Road East, north side: there is an existing 1050mm storm sewer flowing easterly which continues southerly beneath Filmandale Road to the east, where there is a confluence with the above sewer.

Refer to the Pre-Development Drainage Plan on the following page for existing drainage patterns and outlets.

Presently the north-east portion of the existing site (Catchment Areas EX-A and EX-B) drains northerly by overland sheet flow towards Plains Road, where it then drains to the existing 600mm storm sewer. The portion of the existing site which does not drain to Plains Road – Catchment Areas EX-C and EX-D – drains southerly offsite towards the adjacent private properties to the south. A portion of the rear yard of 294 Plains drains towards an existing catchbasin, however inspection of this catchbasin showed that it's outlet is to the south and it is presently clogged with debris and is therefore not providing drainage outlet, therefore stormwater from this area drained southerly.



DRAWING :

PRE-DEVELOPMENT
DRAINAGE PLAN

DATE:	PROJ. NO.:	SCALE:
DEC 2020	20223	1:500

PROJECT :

PROPOSED RESIDENTIAL DEVELOPMENT
284-292 PLAINS RD. E.
BURLINGTON, ON

ODAN•DETECH
CONSULTING ENGINEERS
The Odan/Detech Group Inc. P: (905) 632-3811 F: (905) 632-3363
5230 SOUTH SERVICE ROAD, BURLINGTON, ONTARIO, L7L 5K2

ii) Stormwater Quantity Control Criteria

Storm water management criteria is given in the City of Burlington's manual *Stormwater Management Design Guidelines* (May 21, 2020). Section 6.1 therein provides site-level stormwater management criteria, which applies to site developments such as this.

Section 6.1.1.1 *Design Criteria* states that where an 'end-of-pipe' stormwater management facility is not present and where a site discharges to a storm sewer, the criteria is to control the 100-year return period post-development storm to the allotted capacity of the storm sewer. The manual further states that where the capacity of the storm sewer is unknown, that the 100-year post-development storm should be controlled to the 5-year pre-development storm flow.

The above criteria (control 100-year post-development to 5-year pre-development flows) applies to this development, given that it is proposed to discharge to a storm sewer – the Plains Road East 600mm storm sewer - and that the capacity of this storm sewer is unknown.

City of Burlington IDF curves are provided in Appendix B of the above manual. They are provided as follows and will be used in the below Visual OTTHYMO hydraulic model.

IDF-Curve	***Intensity when t, time of concentration, is 10 minutes:***
$I_2 = 681.52 / (6 + t)^{0.780}$	$I_2 = 78.4$ mm/hr
$I_5 = 802.04 / (5 + t)^{0.764}$	$I_5 = 101.3$ mm/hr
$I_{10} = 918.28 / (5 + t)^{0.763}$	$I_{10} = 116.3$ mm/hr
$I_{25} = 1065.95 / (5 + t)^{0.762}$	$I_{25} = 135.4$ mm/hr
$I_{50} = 1172.34 / (5 + t)^{0.761}$	$I_{50} = 149.3$ mm/hr
$I_{100} = 1281.34 / (5 + t)^{0.761}$	$I_{100} = 163.2$ mm/hr

iii) Allowable Discharge Flow Rate

Allowable discharge flow rate is calculated to be 7.0 L/s as follows based on the above criteria.

TABLE 3 – Allowable Flows (Pre-Development 5-year storm runoff)

Location	Run-off Coefficient	Rainfall Intensity (mm/hr)	Area of Development (ha)	Site Allowable (L/s)
Pre-Development 5-Year Storm Runoff to Plains Rd. E. 600mm Storm Sewer Catchment EX-A & EX-B	0.5 *(Actual Composite C=0.67)*	101.3	0.05 Ha	***7.0***
Pre-Development 5-Year Storm Runoff to Adjacent Properties to South Catchment EX-C, EX-D	0.5 *(Actual Composite C=0.55)*	101.3	0.11 Ha + 0.15 Ha = 0.26 Ha	***36.6***

iv) Post Development Flow Analysis

The proposed development will control the post development flows to the allowable flow rate calculated above; on-site storage will be required.

The adjacent properties have self-contained storm drainage and runoff from the adjacent properties do not enter the subject development based on pre-development drainage patterns. Refer to the Pre-Development Drainage Plan for pre-development drainage patterns.

- ***To the West:*** There is an existing commercial building which appears to drain to internal catchbasins and does not drain into the subject site.
- ***To the East:*** There an existing house/commercial building which appears to drain to internal catchbasins and does not drain into the subject site
- ***To the North:*** There is Plains Road East which drains to the above-described existing storm sewers.
- ***To the South:*** There are existing detached houses and the topography is away from the subject site to the south.

The proposed development is almost entirely underlain by the proposed below-grade parking structure from property-line to property-line, therefore all private storm conveyances will be by mechanical storm piping. Storm area drains on the roofs and ground-levels of the development will drain uncontrolled by mechanical piping to a stormwater detention tank to be constructed in the below-grade parking levels. The stormwater detention tank will be of cast-in-place concrete construction, installed in the below-grade parking structure at the P1 level. An orifice device will be installed at the storm tank's outlet to attenuate runoff to the allowable release rate, thereby causing storage in the stormwater detention tank.

The 100-year stormwater detention tank will be sized, based on the following SWM quantity control analysis, to provide adequate storage to the 100-year post-development storm event below-grade – such that there is no surface ponding.

The smallest permissible orifice tube, 75mm, would produce too-large a controlled release rate given the 8 L/s allowable flow (a 75mm tube gives 16 L/s at 1.0m head – greater than the allowable flow rate). A Hydrovex Vortex flow regulator is proposed instead, as this device can control flows to a sufficiently small flow rate to accommodate the criteria.

Foundation drainage water will be pumped into the storm control maintenance hole (on a long-term basis) at a maximum flow rate of 2.0 L/s. The site's controlled stormwater release rate is revised accordingly such that the total discharge from the site remains less than allowable, despite the foundation drainage flows. This is considered in Table 6, below, where it is shown that the controlled storm flows are no greater than allowable, considering the foundation drain flows.

Note that the site is graded such that the site's major overland flow route is directed towards Plains Rd. E. via the site's driveway apron. This requires a retaining wall at the site's rear, such that the grade at the site's rear (south) side is marginally higher than the grade at Plains Rd. E., with a minimum freeboard of 0.30m. This is in accordance with Section 5.1.1 *Site Grading* of the City of Burlington's manual which states that sites should be graded to direct runoff to an acceptable receiver. Given that the neighbouring private properties to the south are not an acceptable receiver, the site is graded to direct the major overland flow route to Plains Rd. E.


There are existing trees on or near the site's south, west and east boundaries with required Tree Protection Zones (TPZ) around them. It is not permitted to alter the grading/topography within or at the boundary of the TPZ's. Refer to the Grading Plan. As a result, the landscaped areas at the south, west and east sides of the site, which are largely in TPZ areas, must drain out of the site, as existing, following existing topography. It is not possible to install drainage measures in these areas because the topography is lower than that of the driveway areas of the site and because of the TPZ's. The allowable release rate criteria is nonetheless satisfied, because the pre-development 5-year storm flow rate from these areas (36.6 L/s – Table 3), is greater than the post-development 100-year storm flow rate from these areas (Catchment D) (8 L/s – Table 6).

Visual OTTHYMO 2.3.2. will be used to model and determine the detention volume required. For drainage areas with significant imperviousness the calculation of effective rainfall in Visual OTTHYMO is accomplished using the "Standhyd" method. This method is used in urban watersheds to simulate runoff by combining two parallel standard unit hydrographs resulting from the effective rainfall intensity over the pervious and impervious surfaces. For pervious surfaces, losses are calculated using the SCS modified CN method.

The following table summarizes the parameters used in Visual OTTHYMO to characterize the post development catchment areas. Refer to the Post-Development Visual OTTHYMO Model in Appendix B. The catchment areas appear in the Post-Development Catchment Plan, below.

TABLE 4 - Catchment Characteristics for the site Post-Development

Area I.D.	Area (ha)	Hydrograph Method	% impervious	imperviousness directly connected %	Loss Method for Pervious Area	CN for Pervious Area	Initial Abstraction for Pervious (mm)	Time to peak (T_p)
Catchment A: Building Roof Drains to Tank	0.167	StandHyd	99	99	SCS	80	1	-
Catchment B: Impervious paved surfaces & Landscape on-top of parking structure	0.069	StandHyd	99	99	SCS	80	1	-
Catchment C: Pervious Surfaces Drains to Tank	0.011	StandHyd	25	25	SCS	80	5	-
Catchment D: Pervious Surfaces Drains Offsite to South	0.066	StandHyd	25	25	SCS	80	1	-



DRAWING :

POST–DEVELOPMENT
STORM DRAINAGE PLAN


DATE:	PROJ. NO.:	SCALE:
DEC 2020	20223	1:500

PROJECT :

PROPOSED RESIDENTIAL DEVELOPMENT
284–292 PLAINS RD. E.
BURLINGTON, ON

ODAN·DETECH
CONSULTING ENGINEERS
The Odan/Detech Group Inc. P: (905) 632-3811 F: (905) 632-3363
5230 SOUTH SERVICE ROAD, BURLINGTON, ONTARIO, L7L 5K2

Figure 1 - Visual OTTHYMO Model (Showing Flows in 100-Year Storm)



The controlled discharge is thus provided as follows.

The stage-storage-discharge relationship for the proposed storm tank with Hydrovex Vortex 50SVHV-1 orifice control is as follows. The tank is a proposed 108m^2 footprint.


TABLE 5 – Stage/Storage/Discharge Relationship for Orifice Control

Head (m)	Elevation (m)	Provided Volume (m^3)	Discharge (l/s)	Description
0.00	97.20	0	0	Invert of orifice control
0.30	97.50	32	1.5	Tank
0.50	97.70	54	2.0	Tank
1.00	98.20	108	2.8	Tank
1.50	98.70	162	3.3	Tank
2.00	99.20	216	4.0	Tank Roof

Actual 100-year Discharge from orifice:
100 Year = 4 l/sec which is less than the allowable 7 l/sec including Ground Water Discharge.

HYDROVEX®

SVHV Vertical Vortex Flow Regulator



The following is a summary of the Visual OTTHYMO results.

TABLE 6 – Stormwater Management Summary

	2 Yr. Storm	5 Yr. Storm	10 Yr. Storm	25 Hr. Storm	50 Yr. Storm	100 Yr. Storm
Total Flows Attenuated by Orifice Device	2 L/s	3 L/s	3 L/s	3 L/s	3 L/s	4 L/s
Max. Pumped Foundation Drain Flows	2 L/s	2 L/s	2 L/s	2 L/s	2 L/s	2 L/s
Total Flows	4 L/s	5 L/s	5 L/s	5 L/s	5 L/s	6 L/s
Allowable Flow Rate (to Plains Rd. – Table 3)	***7 L/s***					
Required 100-Year Volume	74 m^3	100 m^3	118 m^3	143 m^3	161 m^3	179 m^3
Provided Tank Volume	***216 m^3***					
Catchment D – Uncontrolled Flows	4 L/s	5 L/s	5 L/s	6 L/s	7 L/s	8 L/s
Allowable Flow Rate (to External Properties to South – Table 3)	***36 L/s***					

The proposed stormwater quantity control is such that the controlled discharge in a 100-year storm is equal to the allowable release rate. The stormwater storage is provided such that the volume provided is greater than the required 100-year storm volume. Stormwater quantity control criteria is therefore satisfied.

v) Water Budget/Stormwater Retention

The primary objective of the Water Balance/Budget Targets/Criteria is to capture and manage annual rainfall on the development site itself to preserve the pre-development hydrology (or "water balance", which typically consists of three components: runoff, infiltration, and evapotranspiration) through a combination of infiltration, evapotranspiration, landscaping, rainwater reuse and/or other low impact development practices.

Storm water management water budget/retention criteria is given in the City of Burlington's manual *Stormwater Management Design Guidelines* (May 21, 2020). Section 6.1.3 therein provides site-level stormwater management stormwater retention/water budget criteria, which would apply to this development. That section states that proponents are required to maintain the water budget in accordance with a SWS, MDP or MESP that encompasses the subject site, or where not available, maintain pre-development water budget in the proposed development.

We are not aware of a SWS, MDP or MESP which would apply to this site, therefore the criteria given in the third paragraph of Section 6.1.3 has been adopted.

The third paragraph of Section 6.1.3 provides criteria for analysis of the water budget, stating that the proponent should retain runoff up to the 27mm event, or at a minimum, the 5mm event. We assume the criteria at this time is to retain the 5mm event.

The water balance target volume is as follows.

	Initial Abstraction (mm)	Area (m^2)	Volume (m^3)
5mm Volume Whole Site	5	3131	15.7
Less Impervious Surfaces initial abstraction – Catchment A & B	1	1670 + 690 = 2360	2.4
Less Pervious Surfaces initial abstraction Catchment C	5	771	3.9
Required Retention Volume			***9.4***

A cistern of minimum volume 10.0m^3 will be designed at the SPA Stage to retain the required volume of stormwater. The cistern will function such that in minor storm events, runoff draining from the site's mechanical drains will first drain into the cistern for storage and reuse.

In storm events greater than 5mm, the cistern will fill-up and stormwater will occupy the larger storage area allocated for 100-year storm storage before draining via the site's orifice control. This will be detailed on SPA drawings.

Various alternatives are considered by which the foregoing water balance target might be achieved on this site, as follows.

1) ***Infiltration Gallery (Percolation)***: The proposed development is entirely comprised of the proposed below-grade parking structure below-grade. Infiltration is not feasible because the design criteria – *MOE Stormwater Management Planning & Design* Manual, 2003, as well as the OBC – requires such an infiltration gallery to be located with a minimum 4.00m horizontal separation from proposed buildings. There is no such location on this site in which to locate an infiltration gallery. Further, on a small site such as this it is generally not feasible to install an infiltration gallery because if the infiltration gallery were provided with the required horizontal setback from the building (min. 5m) and the footprint required to retain the volume of water (say, approx. 20m^2 with conservative percolation rate assumptions), the infiltration gallery would take up an impracticably large portion of the lot footprint which would otherwise be used for the below-grade parking structure.

2) ***Irrigation***: Irrigation shall be explored in future as there are landscaped surfaces including trees at-grade – the capacity to uptake water by irrigation will be determined at the SPA stage. It is anticipated that irrigation alone will not consume the required volume, therefore greywater reuse is also investigated as follows.

3) ***Greywater reuse***: Greywater reuse is feasible, and may be required depending on the volume of water that can be reused by irrigation. Greywater reuse may be feasible as toilet flushing in the commercial or amenity areas of the proposed tower.

vi) Water Quality

Storm water management quality control criteria is given in the City of Burlington's manual *Stormwater Management Design Guidelines* (May 21, 2020). Section 6.1.4 *Quality Control* provides criteria which would apply to developments. That section states that a 'treatment train' approach to stormwater quality is required comprising at least two forms of water quality treatment in series to achieve 80% TSS removal, or satisfying the MECP 'Enhanced' criteria.

The site was divided according to surface conditions and the effective TSS removal for each surface condition was considered based on the treatment it would receive. The general basis of the effective TSS removal rates are as follows:

1. Rooftop areas are subject only to airborne particles and insignificant amounts of sediment transported by foot traffic. As such, an effective removal efficiency of 80% is utilized on a conventional roof to reflect the inherent runoff quality from a conventional roof.

2. Balconies and sodded areas are subject to insignificant amounts of sediment transport by foot traffic. An effective removal rate of 80% is used as it is the City limit for roofs.

3. Driving and ground-level pedestrian surfaces which are open-to-above will be subject to winter maintenance, therefore they are assumed to have an effective removal efficiency of 0% and stormwater quality treatment is thus required.

It is proposed to provide a Jellyfish Stormwater filter to satisfy the 80% TSS removal criteria. We appreciate that this is a single-stage stormwater quality solution, rather than treatment-train approach as per the manual, however we provide the following rationale as to why this should be acceptable for this development and request City consideration.

The Burlington manual recognizes conventional Oil-Grit Separators as providing 50% TSS Removal. Section 6.1.4.4 of the City's manual states that the Canadian Environmental Technology Verification (CA-ETV) is the governing authority for storm filters/quality devices.

The CETV certification for the *Stormceptor STC*-model conventional Oil-Grit Separator by Imbrium Systems Inc. concurs with the town manual that the conventional OGS provides 50% TSS removal. Figure 2, as follows, is an excerpt from the CETV *Verification Statement – Imbrium Systems Inc. Stormceptor … Oil-Grit Separators* (November 2017).

Figure 2 shows that the Stormceptor conventional OGS provides typically 50-70% TSS removal, therefore the conclusion holds that a conventional OGS does not satisfactorily address the stormwater quality criteria for this site because it does not provide 80% TSS.

Figure 2 - Excerpt from CETV Verification Statement for Stormceptor OGS

Table 1. Removal efficiencies (%) of the EF4 at specified surface loading rates

Particle size fraction (µm)	Surface loading rate (L/min/m²)						
	40	80	200	400	600	1000	1400
>500	90	58	58	100*	86	72	100*
250 - 500	100*	100*	100	100*	100*	100*	100*
150 - 250	90	82	26	100*	100*	67	90
105 - 150	100*	100*	100*	100*	100*	100*	100
75 - 105	100*	92	74	82	77	68	76
53 - 75	Undefined [a]	56	100*	72	69	50	80
20 - 53	54	100*	54	33	36	40	31
8 - 20	67	52	25	21	17	20	20
5 – 8	33	29	11	12	9	7	19
<5	13	0	0	0	0	0	4
All particle sizes by mass balance	**70.4**	**63.8**	**53.9**	**47.5**	**46.0**	**43.7**	**49.0**

TSS Removal efficiency is ~50%

[a] An outlier in the feed sample sieve data resulted in a negative removal efficiency for this size fraction.
* Removal efficiencies were calculated to be above 100%. Calculated values ranged between 101 and 171% (average 128%).
See text and Bulletin # CETV 2016-11-0001 for more information.

The CETV also provides certification for stormwater quality filters that provide TSS removal by mechanical filtration through a filter media. One such model is the Jellyfish Filter by Imbrium Systems. The CETV verification statement for the Jelllyfish Filter by Imbrium Systems states that it provides a minimum 80% TSS Removal. Figure 3, as follows, is an excerpt from the CETV *Verification Statement – Imbrium Systems Inc. Jellyfish Filter …* (August 2017).

Figure 3 shows that the Jellyfish Filter provides 80% TSS Removal, therefore it addresses the City criteria for 80% TSS Removal. The entire Jellyfish Filter CETV Verification Statement is provided here in Appendix B.

It is accordingly proposed to provide a Jellyfish Filter by Imbrium to address City criteria for 80% TSS Removal. This is lieu of providing a conventional OGS with a treatment-train approach to providing 80% TSSR. This strategy of using a manufactured treatment device/filter is more practical on a development like this because it is not feasible to install permeable pavers/bioswales etc. in small infill developments such as this which are entirely underlain by the underground parking structure.

A Jellyfish Filter will be specified to provide 80% TSS Removal at the SPA stage. Refer to Appendix B for the design report for the Jellyfish Filter

Figure 3 - Excerpt from CETV Verification Statement for Jellyfish Filter

Table 4. Summary statistics for influent and effluent event mean concentrations for selected constituents

Water Quality Variable	Sampling Location	Min	Max	Median	Range	Mean	SD	Load based removal efficiency (%)
TSS	Influent (mg/L)	16.30	261.00	79.30	244.70	86.26	51.37	87.2
	Effluent (mg/L)	3.20	21.70	11.80	18.50	10.99	4.79	
SSC	Influent (mg/L)	78.20	1401.70	444.50	1323.50	482.26	338.34	98.6
	Effluent (mg/L)	2.80	18.10	7.30	15.30	7.88	3.77	
TP	Influent (µg/L)	887.00	8793.00	3063.00	7906.00	3550.20	1914.50	64.2
	Effluent (µg/L)	472.00	4769.00	1480.00	4297.00	1688.08	1059.98	
TN	Influent (µg/L)	1170.00	10479.00	3110.00	9309.00	3519.32	2161.47	46.3
	Effluent (µg/L)	553.00	6579.00	1610.00	6026.00	2091.76	1613.61	
Zn	Influent (µg/L)	0.005	7600.00	1500.00	7600.00	1792.00	1852.91	76.1
	Effluent (µg/L)	0.005	2760.00	450.00	2760.00	561.64	594.70	
Cu	Influent (µg/L)	0.001	880.40	79.50	880.40	171.28	229.33	92.1
	Effluent (µg/L)	0.001	51.30	6.90	51.30	14.36	17.22	
Oil and Grease	Influent (mg/L)	0.20	4.06	0.93	3.86	1.07	0.82	46.4
	Effluent (mg/L)	0.00	2.32	0.35	2.32	0.50	0.60	

.

6.0 GROUNDWATER

i) Introduction

It is proposed to discharge any water collected by the building's foundation drains into the storm control maintenance hole as discussed in Section 5.0, above.

A *Hydrogeological Investigation* (dated August 24, 2022) has been prepared for this development by Exp Services to qualitatively and quantitatively characterize the groundwater with respect to City of Burlington and Halton Region guidelines.

The report concludes in Table 4-4 that the short-term construction dewatering volume will be up to 576,000 L/day (including storm flows) at the start of construction, decreasing to 237,000 L/day.

The report concludes in Table 5-1 that the long-term flows into the building's foundation drains will be 112,000 L/day (including peaking factor).

The report concludes in Table 3-4 that the groundwater quality complies with the criteria for discharge into Halton Region's sanitary sewer/wastewater main and that there are two quality exceedances for discharge into the City of Burlington's storm sewers.

ii) Long-Term Groundwater

The hydrogeological investigation states as above that the peak daily volume entering the foundation drains will be 112,000 L/day, which equates to flows of 1.3 L/s. It is intended to collect this water in a sump installed in the proposed buildings below-grade levels and pump it into the proposed Building's storm control maintenance hole, thereby draining to the storm sewer connection. It is assumed that a peaking factor will be applied in the design of the pump such that the pumped groundwater discharge rate is 2.0 L/s. This is considered in the controlled storm flows compliance, as outlined in Table 6, above.

The owner intends to review, in future, the feasibility of filtering the water to address the two noted exceedances for storm sewer discharge, relative to the City criteria. If, pending consideration, it is unfeasible to filter the water to address such criteria, the building's foundations may then instead be 'bathtubbed' such that there is no groundwater discharge.

iii) Short-Term (Construction) Groundwater

Groundwater collected during the site's excavation and construction by either sumps or wellpoints will need to be discharged to facilitate the excavation-for and construction-of the proposed building.

The short-term groundwater flow rate identified by the Hydrogeological Assessment totals up to 576,000 L/d (6.7 L/s), above, but will typically be 237,000 L/day (2.7 L/s). It is proposed to discharge this flow rate into the existing Plains Road storm sewer. This temporary groundwater flow rate is less than the allowable storm flow rate (7.0 L/s, as per Table 3), therefore short-term/construction groundwater flows are within the allowable flow rate.

7.0 CONCLUSIONS

From the foregoing investigation, the site is serviceable utilizing existing sanitary/wastewater sewers and watermain infrastructure adjacent to the site. Storm water management can be accommodated with on-site storage as described in this report.

The following table summarizes the SWM and Servicing components of the proposed development.

TABLE 7 - Summary

	Proposed Building
Peak Sanitary Discharge (L/s)	3.4 L/s
Proposed Sanitary Service	200mm @ 2.0%
Receiving Sanitary Sewer	Plains Rd. E. 250mm sanitary sewer (south side)
Development Water Demand (Fire + Domestic)	2141 USGM
Available Flow Rate	3182 USGM
Proposed Fire Service	200mm
Proposed Domestic Service	Branch 150mm
Allowable release rate from site (L/s)	7.0 L/s
Proposed release rate from site (L/s) (100 year storm)	6.0 L/s
Stormwater Quality	Jellyfish Stormwater Filter
Quantity Control	To be designed at SPA stage

8.0 REFERENCES

1. City of Burlington *Stormwater Management Design Guidelines* (May 21, 2020).

2. Storm water Management Planning and Design Manual, Ontario Ministry of the Environment, March 2003.

3. Halton Region *Water and Wastewater Linear Design Manual* (April 2019)

4. New Jersey Storm Water Best Management Practices Manual, April 2004.

5. Visual OTTHYMO v2.0 Reference Manual, July 2002

Respectfully Submitted;
The Odan Detech Group Inc.



Oct 12, 2022

Mark Harris

Digitally signed by Mark Harris
DN: cn=Mark Harris, o=The Odan/Detech Group Inc., ou, email=mark@odandetech.com, c=CA
Date: 2022.10.14 13:37:45 -04'00'

Paul Hecimovic, P.Eng.

Mark Harris, Dipl.Tech.
Senior Project Manager

APPENDIX A

Existing Site	Aerial view of Site and surrounding area
Site Plan & Statistics	by SRM Architects Inc.



LEGEND

PROPERTY LINE

DRAWING :


KEY PLAN

DATE:	PROJ. NO.:	SCALE:
DEC 2020	20223	N.T.S.

PROJECT :

PROPOSED RESIDENTIAL DEVELOPMENT
284-292 PLAINS RD. E.
BURLINGTON, ON

ODAN·DETECH
CONSULTING ENGINEERS
The Odan/Detech Group Inc. P: (905) 632-3811 F: (905) 632-3363
5230 SOUTH SERVICE ROAD, BURLINGTON, ONTARIO, L7L 5K2



SITE DATA

284-292 Plains Rd. E, Burlington, Ontario

DATA		REQUIRED	PROVIDED
ZONING		ZONING - MXG	
PROPERTY ZONE		RM1-346	
LOT AREA (m²)		--	3,131.4 m²
PROPOSED FLOOR AREA RATIO (FAR)		--	3.00
SETBACKS	FRONT YARD (m)	3 m	3 m
	INTERIOR SIDE YARD (m) East	3 m	3 m
	AT GRADE (EDGE OF PARKING)		4.5 m
	INTERIOR SIDE YARD (m) West	3 m	3.6 m
	AT GRADE		4.8 m
	REAR YARD (m)	FLOORS 1-3 = 12 m	12.6 m
	REAR YARD (m)	FLOORS 4-5 = 15 m	15.9 m
	REAR YARD (m)	FLOORS 6 = 18 m	21.9 m

BUILDING DATA

DATA	REQUIRED	PROVIDED
TOTAL DENSITY (# of units)	--	107 units
1 BEDROOM		64 units
1 BEDROOM+DEN		8 units
2 BEDROOM		13 units
2 BEDROOM+DEN		1 units
2 BED TOWNHOUSES		6 units
3 BED		12 units
3 BED TOWNHOUSES		3 units
BUILDING AREA (m²)	--	1,040m² (11,194sf)
+ COVERED RAMP (m²)		167m² (1,798sf)
GROSS FLOOR AREA (m²) U/G common areas incl.	--	9,416m² (101,353sf)
GROSS CONSTRUCTION AREA (m²) -incl. parking	--	13,578m² (146,152sf)
NET LEASABLE AREA (m²)	--	6,862m² (73,862 sf)
NUMBER OF STOREYS	6 MAX.	7 STOREYS
BUILDING HEIGHT (m)	--	24.75 m OVERALL + Penthouse Height
AMENITY AREA (m²) (15m² for 1B unit <60m², 20m² for 1B >60m², 35m² for 2B+)	1B < 60m² = 59 (15m²) = 885 m² 1B > 60m² = 5 (20m²) = 100 m² 2B+ = 37 (35m²) = 1,295 m² TOTAL = 2,280 m²	EXTERIOR = 1,310 m² INTERIOR = 490 m² TOTAL =1,800 m² = 17.31 m² / unit

LANDSCAPING DATA

DATA	REQUIRED	PROVIDED
LANDSCAPE AREA (area)	--	904 m²
LANDSCAPE AREA (percentage)	--	29%
LANDSCAPE BUFFER (m)	3m (Front) 6m (Rear and sides abutting res	-- --
HARDSCAPE AREA (area)	--	317 m²
HARDSCAPE AREA (percentage)	--	10%
TOTAL LANDSCAPE+HARDSCAPE	--	1,221 m² (39%)
ASPHALT AREA (area)	--	702 m²
ASPHALT AREA (percentage)	--	22%

VEHICLE PARKING DATA

DATA	REQUIRED (BY-LAW 2020)	REQUIRED (PARKING STRD REVIEW)	PROVIDED
RESIDENTIAL PARKING	1.25x (72) 1 BED = 90 1.5 x (20) 2 BED = 30 1.75 x (15) 3 BED =27 0.35 x 107 = 38 VISITOR 2 MAINTENANCE	1x (72) 1 BED = 72 1 x (35) 2+ BED = 35 0.08 x 107 = 8.56 VISITOR	LEVEL P2: 56 Stalls LEVEL P1: 48 Stalls LEVEL 1: 12 Surface
B.F. PARKING		3% OF STALLS = 4	4 (includ. in above)
TOTAL	185	115.56	116

BICYCLE PARKING DATA

DATA	REQUIRED	PROVIDED
RESIDENTIAL BICYCLE PARKING		
SHORT TERM	0.05 x (107) = 5.35	12 (ST)
LONG TERM	0.5 x (107) = 53.5	91 (LT)
	TOTAL	107

Project North

True North

GENERAL NOTES

1. **DO NOT SCALE DRAWINGS**. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.
2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.
3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.
4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.
5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.
6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE RESPONSIBILITY OF SUCH THIRD PARTIES.
7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.



No.	Date	Revision
4	2022-09-15	ISSUED FOR REZONING APPLICATION No. 2
3	2022-05-27	CLIENT REVISIONS
2	2022-05-04	CLIENT REVISIONS
1	2021-09-14	ISSUED FOR REZONING APPLICATION

srm ARCHITECTS INC.

Project No: 20042
Project Date: 2021-04-22
Drawn by: SDF
Checked by: MES
Plot Date / Time: 10/6/2022 2:32:25 PM

284-292 PLAINS RD. E, BURLINGTON

SITE PLAN

Drawing Scale: As indicated
Status: ISSUED FOR REZONING APPLICATION NO. 2
Drawing No.: D1.01
Revision No.: - r4

Do not scale drawings. Contractors must check and verify all dimensions and report any discrepancies to the Architect before proceeding with the work. All documents remain the property of the Architect. Unauthorized use, modification, and/or reproduction of these documents is prohibited without written permission. The Contract Documents were prepared by the Consultant for the account of the Owner.
The material contained herein reflects the Consultants best judgment in light of the information available to him at the time of preparation Any use which a third party makes of the Contract Documents, or any reliance on or decisions to be made based on them are the responsibility of such third parties. The Consultant accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on the Contract Documents.

C:\Users\eetmanskie\Documents\20042 - 284-292 Plains Rd E, Burlington - V13_eetmanskie.rvt



1 FLOOR PLAN - LEVEL 1
1 : 150

Gross Construction Area	
Level	**Area**
PARKING P2	2275.12 m²
PARKING P1	2275.37 m²
LEVEL 1	1040.34 m²
MEZZANINE	273.86 m²
LEVEL 2	1564.43 m²
LEVEL 3	1537.27 m²
LEVEL 4	1484.63 m²
LEVEL 5	1378.59 m²
LEVEL 6	1272.83 m²
MECH. PENTHOUSE	475.38 m²
	13577.81 m²

Project North

True North

GENERAL NOTES

1. **DO NOT SCALE DRAWINGS**. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.
2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.
3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.
4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.
5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.
6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE RESPONSIBILITY OF SUCH THIRD PARTIES.
7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.

No.	Date	Revision
4	2022-09-15	ISSUED FOR REZONING APPLICATION No. 2
3	2022-05-27	CLIENT REVISIONS
2	2022-05-04	CLIENT REVISIONS
1	2021-09-14	ISSUED FOR REZONING APPLICATION

srm ARCHITECTS INC.

Project No 20042

Project Date 2021-04-22

Drawn by SDF

Checked by MES

Plot Date / Time 10/6/2022 2:32:28 PM

284-292 PLAINS RD. E, BURLINGTON

LEVEL 1

Drawing Scale 1 : 150

Status ISSUED FOR REZONING APPLICATION NO. 2

Drawing No. D2.2 - r4

Revision No.

Do not scale drawings. Contractors must check and verify all dimensions and report any discrepancies to the Architect before proceeding with the work. All documents remain the property of the Architect. Unauthorized use, modification, and/or reproduction of these documents is prohibited without written permission. The material contained herein reflects the Consultants best judgement in light of the information available to him at the time of preparation Any use which a third party makes of the Contract Documents, or any reliance on or decisions to be made based on them are the responsibility of such third parties. The Consultant accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on the Contract Documents.

C:\Users\eetmanskie\Documents\20042 - 284-292 Plains Rd E, Burlington - V13_eetmanskie.rvt

APPENDIX B

Visual OTTHYMO Model Output (2-Year & 100-Year storms)

CETV Verification Statement – Imbrium Systems Inc. Stormceptor OGS

CETV Verification Statement – Imbrium Systems Inc. Jellyfish Filter

Visual OTTHYMO Output (2, 5, 10, 25, 50 & 100-year storm)

```
==========================================================================================================================

       V    V   I    SSSSS  U   U    A    L
       V    V   I    SS     U   U   A A   L
        V  V    I     SS    U   U  AAAAA  L
        V  V    I      SS   U   U  A   A  L
         VV     I    SSSSS  UUUUU  A   A  LLLLL

        OOO   TTTTT  TTTTT  H   H  Y   Y  M   M   OOO
       O   O    T      T    H   H   Y Y   MM MM  O   O
       O   O    T      T    H   H    Y    M   M  O   O
        OOO     T      T    H   H    Y    M   M   OOO

Developed and Distributed by Clarifica Inc.
Copyright 1996, 2007 Clarifica Inc.
All rights reserved.


                  *****  D E T A I L E D   O U T P U T *****


  Input   filename: C:\Program Files (x86)\Visual OTTHYMO 2.3.3\voin.dat
  Output  filename: C:\Users\DKneblewski\Desktop\Rev1.0 PN 223\VO2\Post-Development.out
  Summary filename: C:\Users\DKneblewski\Desktop\Rev1.0 PN 223\VO2\Post-Development.sum


DATE: 16-Apr-21                           TIME: 1:26:46 PM

USER:


COMMENTS: _____________________________________________________

--------------------------------------------------------------------------------------------------------------------------
  ****************************
  ** SIMULATION NUMBER:   1 **
  ****************************

--------------------
| CHICAGO STORM    |    IDF curve parameters: A= 681.520
| Ptotal= 37.19 mm |                          B=   6.000
--------------------                          C=    .780
                       used in:   INTENSITY =  A / (t + B)^C

                       Duration of storm  =  4.00 hrs
                       Storm time step    = 10.00 min
                       Time to peak ratio =   .33

                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                 .17    2.54 |  1.17   19.72 |  2.17    5.98 |  3.17    3.02
                 .33    2.91 |  1.33   78.39 |  2.33    5.09 |  3.33    2.81
                 .50    3.42 |  1.50   25.74 |  2.50    4.45 |  3.50    2.62
                 .67    4.20 |  1.67   13.74 |  2.67    3.96 |  3.67    2.46
                 .83    5.53 |  1.83    9.48 |  2.83    3.58 |  3.83    2.33
                1.00    8.38 |  2.00    7.31 |  3.00    3.27 |  4.00    2.21


--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0001) |   Area    (ha)=    .24
|ID= 1 DT= 5.0 min |   Total Imp(%)=  99.00   Dir. Conn.(%)=  99.00
--------------------
                              IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .24          .00
     Dep. Storage     (mm)=       1.00         1.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      40.00        40.00
     Mannings n             =     .013         .250

         NOTE:  RAINFALL WAS TRANSFORMED TO   5.0 MIN. TIME STEP.


                          ---- TRANSFORMED HYETOGRAPH ----
                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
```

```
                .083    2.54 | 1.083   19.72 | 2.083    5.98 |  3.08    3.02
                .167    2.54 | 1.167   19.72 | 2.167    5.98 |  3.17    3.02
                .250    2.91 | 1.250   78.39 | 2.250    5.09 |  3.25    2.81
                .333    2.91 | 1.333   78.39 | 2.333    5.09 |  3.33    2.81
                .417    3.42 | 1.417   25.74 | 2.417    4.45 |  3.42    2.62
                .500    3.42 | 1.500   25.74 | 2.500    4.45 |  3.50    2.62
                .583    4.20 | 1.583   13.74 | 2.583    3.96 |  3.58    2.46
                .667    4.20 | 1.667   13.74 | 2.667    3.96 |  3.67    2.46
                .750    5.53 | 1.750    9.48 | 2.750    3.58 |  3.75    2.33
                .833    5.53 | 1.833    9.48 | 2.833    3.58 |  3.83    2.33
                .917    8.38 | 1.917    7.31 | 2.917    3.27 |  3.92    2.21
               1.000    8.38 | 2.000    7.31 | 3.000    3.27 |  4.00    2.21

     Max.Eff.Inten.(mm/hr)=      78.39        24.44
                over (min)        5.00         5.00
     Storage Coeff.  (min)=       1.63 (ii)    2.86 (ii)
     Unit Hyd. Tpeak (min)=       5.00         5.00
     Unit Hyd. peak  (cms)=        .32          .28
                                                        *TOTALS*
     PEAK FLOW       (cms)=        .05          .00          .052 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.33         1.33
     RUNOFF VOLUME    (mm)=      36.19        13.14        35.95
     TOTAL RAINFALL   (mm)=      37.19        37.19        37.19
     RUNOFF COEFFICIENT   =        .97          .35          .97

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0003) |   Area    (ha)=    .07
|ID= 1 DT= 5.0 min |   Total Imp(%)=  50.00   Dir. Conn.(%)=  50.00
--------------------
                              IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .04          .04
     Dep. Storage     (mm)=       1.00         5.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      21.60        40.00
     Mannings n           =       .013         .250

     Max.Eff.Inten.(mm/hr)=      78.39        15.43
                over (min)        5.00        20.00
     Storage Coeff.  (min)=       1.12 (ii)   16.03 (ii)
     Unit Hyd. Tpeak (min)=       5.00        20.00
     Unit Hyd. peak  (cms)=        .34          .06
                                                        *TOTALS*
     PEAK FLOW       (cms)=        .01          .00          .008 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.58         1.33
     RUNOFF VOLUME    (mm)=      36.19        10.83        23.37
     TOTAL RAINFALL   (mm)=      37.19        37.19        37.19
     RUNOFF COEFFICIENT   =        .97          .29          .63

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------

--------------------
| ADD HYD   (0005) |
|   1 +  2 =  3    |          AREA    QPEAK    TPEAK     R.V.
--------------------          (ha)    (cms)    (hrs)     (mm)
          ID1= 1 (0001):       .24     .052     1.33    35.95
        + ID2= 2 (0003):       .07     .008     1.33    23.37
          ================================================
          ID = 3 (0005):       .31     .060     1.33    33.11

     NOTE:  PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

--------------------------------------------------------------------------------
```

```
--------------------
| RESERVOIR (0006) |
| IN= 2---> OUT= 1 |
| DT=  5.0 min     |     OUTFLOW    STORAGE   |  OUTFLOW    STORAGE
--------------------      (cms)     (ha.m.)   |   (cms)     (ha.m.)
                           .0000      .0000   |    .0070       .0110
                           .0050      .0055   |    .0080       .0160

                                 AREA      QPEAK       TPEAK       R.V.
                                 (ha)      (cms)       (hrs)       (mm)
     INFLOW : ID= 2 (0005)       .310       .060        1.33       33.11
     OUTFLOW: ID= 1 (0006)       .310       .005        2.08       32.24

                  PEAK   FLOW   REDUCTION [Qout/Qin](%)=  9.03
                  TIME SHIFT OF PEAK FLOW         (min)= 45.00
                  MAXIMUM  STORAGE   USED       (ha.m.)=   .0066

--------------------------------------------------------------------------------
  ****************************
  ** SIMULATION NUMBER:   2 **
  ****************************

--------------------
| CHICAGO STORM    |    IDF curve parameters: A= 802.040
| Ptotal= 47.95 mm |                          B=   5.000
--------------------                          C=    .764
                        used in:   INTENSITY =  A / (t + B)^C

                        Duration of storm  =  4.00 hrs
                        Storm time step    = 10.00 min
                        Time to peak ratio =   .33

                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                 .17    3.43 |  1.17   24.57 |  2.17    7.80 |  3.17    4.05
                 .33    3.91 |  1.33  101.31 |  2.33    6.69 |  3.33    3.77
                 .50    4.57 |  1.50   31.90 |  2.50    5.88 |  3.50    3.54
                 .67    5.56 |  1.67   17.28 |  2.67    5.26 |  3.67    3.33
                 .83    7.23 |  1.83   12.11 |  2.83    4.77 |  3.83    3.15
                1.00   10.76 |  2.00    9.44 |  3.00    4.38 |  4.00    2.99


--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0001) |   Area    (ha)=    .24
|ID= 1 DT= 5.0 min |   Total Imp(%)=  99.00   Dir. Conn.(%)=  99.00
--------------------
                              IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .24          .00
     Dep. Storage     (mm)=       1.00         1.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      40.00        40.00
     Mannings n           =       .013         .250

         NOTE:  RAINFALL WAS TRANSFORMED TO   5.0 MIN. TIME STEP.


                             ---- TRANSFORMED HYETOGRAPH ----
                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                .083    3.43 | 1.083   24.57 | 2.083    7.80 |  3.08    4.05
                .167    3.43 | 1.167   24.57 | 2.167    7.80 |  3.17    4.05
                .250    3.91 | 1.250  101.31 | 2.250    6.69 |  3.25    3.77
                .333    3.91 | 1.333  101.31 | 2.333    6.69 |  3.33    3.77
                .417    4.57 | 1.417   31.90 | 2.417    5.88 |  3.42    3.54
                .500    4.57 | 1.500   31.90 | 2.500    5.88 |  3.50    3.54
                .583    5.56 | 1.583   17.28 | 2.583    5.26 |  3.58    3.33
                .667    5.56 | 1.667   17.28 | 2.667    5.26 |  3.67    3.33
                .750    7.23 | 1.750   12.11 | 2.750    4.77 |  3.75    3.15
                .833    7.23 | 1.833   12.11 | 2.833    4.77 |  3.83    3.15
                .917   10.76 | 1.917    9.44 | 2.917    4.38 |  3.92    2.99
               1.000   10.76 | 2.000    9.44 | 3.000    4.38 |  4.00    2.99

     Max.Eff.Inten.(mm/hr)=     101.31       457.39
                over (min)        5.00         5.00
     Storage Coeff.  (min)=       1.47 (ii)    2.58 (ii)
     Unit Hyd. Tpeak (min)=       5.00         5.00
     Unit Hyd. peak  (cms)=        .33          .29
                                                      *TOTALS*
```

```
     PEAK FLOW       (cms)=        .07          .00           .067 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.33           1.33
     RUNOFF VOLUME    (mm)=      46.95        19.96          46.67
     TOTAL RAINFALL   (mm)=      47.95        47.95          47.95
     RUNOFF COEFFICIENT   =        .98          .42            .97

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0003) |   Area    (ha)=    .07
|ID= 1 DT= 5.0 min |   Total Imp(%)=  50.00   Dir. Conn.(%)=  50.00
--------------------
                            IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .04          .04
     Dep. Storage     (mm)=       1.00         5.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      21.60        40.00
     Mannings n           =       .013         .250

     Max.Eff.Inten.(mm/hr)=     101.31        25.92
               over (min)         5.00        15.00
     Storage Coeff.  (min)=       1.01 (ii)   13.13 (ii)
     Unit Hyd. Tpeak (min)=       5.00        15.00
     Unit Hyd. peak  (cms)=        .34          .08
                                                        *TOTALS*
     PEAK FLOW       (cms)=        .01          .00           .011 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.50           1.33
     RUNOFF VOLUME    (mm)=      46.95        17.33          32.05
     TOTAL RAINFALL   (mm)=      47.95        47.95          47.95
     RUNOFF COEFFICIENT   =        .98          .36            .67

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------

--------------------
| ADD HYD   (0005) |
|   1 +  2 =  3    |         AREA    QPEAK    TPEAK     R.V.
--------------------         (ha)    (cms)    (hrs)      (mm)
          ID1= 1 (0001):      .24    .067     1.33    46.67
        + ID2= 2 (0003):      .07    .011     1.33    32.05
          ================================================
          ID = 3 (0005):      .31    .078     1.33    43.37

     NOTE:  PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

--------------------------------------------------------------------------------
--------------------
| RESERVOIR (0006) |
| IN= 2---> OUT= 1 |
| DT=  5.0 min     |     OUTFLOW    STORAGE   |  OUTFLOW    STORAGE
--------------------      (cms)     (ha.m.)   |   (cms)     (ha.m.)
                           .0000      .0000   |    .0070       .0110
                           .0050      .0055   |    .0080       .0160

                                AREA      QPEAK       TPEAK       R.V.
                                (ha)      (cms)       (hrs)       (mm)
     INFLOW : ID= 2 (0005)       .310       .078        1.33       43.37
     OUTFLOW: ID= 1 (0006)       .310       .006        2.17       42.48

                   PEAK   FLOW   REDUCTION [Qout/Qin](%)=  7.97
                   TIME SHIFT OF PEAK FLOW         (min)= 50.00
                   MAXIMUM  STORAGE   USED       (ha.m.)=   .0088

--------------------------------------------------------------------------------
  ****************************
```

```
  ** SIMULATION NUMBER:   3 **
  ****************************

--------------------
| CHICAGO STORM    |    IDF curve parameters: A= 918.280
| Ptotal= 55.20 mm |                          B=   5.000
--------------------                          C=    .763
                       used in:   INTENSITY =  A / (t + B)^C

                       Duration of storm  =  4.00 hrs
                       Storm time step    = 10.00 min
                       Time to peak ratio =   .33

                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                 .17    3.96 |  1.17   28.29 |  2.17    9.00 |  3.17    4.68
                 .33    4.51 |  1.33  116.31 |  2.33    7.72 |  3.33    4.36
                 .50    5.28 |  1.50   36.70 |  2.50    6.78 |  3.50    4.09
                 .67    6.42 |  1.67   19.91 |  2.67    6.07 |  3.67    3.85
                 .83    8.35 |  1.83   13.96 |  2.83    5.51 |  3.83    3.64
                1.00   12.41 |  2.00   10.89 |  3.00    5.06 |  4.00    3.46


--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0001) |   Area    (ha)=    .24
|ID= 1 DT= 5.0 min |   Total Imp(%)=  99.00   Dir. Conn.(%)=  99.00
--------------------
                            IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .24          .00
     Dep. Storage     (mm)=       1.00         1.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      40.00        40.00
     Mannings n           =       .013         .250

         NOTE:  RAINFALL WAS TRANSFORMED TO   5.0 MIN. TIME STEP.


                              ---- TRANSFORMED HYETOGRAPH ----
                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                .083    3.96 | 1.083   28.29 | 2.083    9.00 |  3.08    4.68
                .167    3.96 | 1.167   28.29 | 2.167    9.00 |  3.17    4.68
                .250    4.51 | 1.250  116.31 | 2.250    7.72 |  3.25    4.36
                .333    4.51 | 1.333  116.31 | 2.333    7.72 |  3.33    4.36
                .417    5.28 | 1.417   36.70 | 2.417    6.78 |  3.42    4.09
                .500    5.28 | 1.500   36.70 | 2.500    6.78 |  3.50    4.09
                .583    6.42 | 1.583   19.91 | 2.583    6.07 |  3.58    3.85
                .667    6.42 | 1.667   19.91 | 2.667    6.07 |  3.67    3.85
                .750    8.35 | 1.750   13.96 | 2.750    5.51 |  3.75    3.64
                .833    8.35 | 1.833   13.96 | 2.833    5.51 |  3.83    3.64
                .917   12.41 | 1.917   10.89 | 2.917    5.06 |  3.92    3.46
               1.000   12.41 | 2.000   10.89 | 3.000    5.06 |  4.00    3.46

     Max.Eff.Inten.(mm/hr)=     116.31       787.00
               over (min)          5.00         5.00
     Storage Coeff.  (min)=       1.39 (ii)    2.45 (ii)
     Unit Hyd. Tpeak (min)=       5.00         5.00
     Unit Hyd. peak  (cms)=        .33          .30
                                                      *TOTALS*
     PEAK FLOW       (cms)=        .08          .00          .077 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.33          1.33
     RUNOFF VOLUME    (mm)=      54.20        24.96         53.90
     TOTAL RAINFALL   (mm)=      55.20        55.20         55.20
     RUNOFF COEFFICIENT   =        .98          .45           .98

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0003) |   Area    (ha)=    .07
|ID= 1 DT= 5.0 min |   Total Imp(%)=  50.00   Dir. Conn.(%)=  50.00
```

```
--------------------
                              IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .04          .04
     Dep. Storage     (mm)=       1.00         5.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      21.60        40.00
     Mannings n           =       .013         .250

     Max.Eff.Inten.(mm/hr)=     116.31        33.88
               over (min)         5.00        15.00
     Storage Coeff.  (min)=        .96 (ii)   11.84 (ii)
     Unit Hyd. Tpeak (min)=       5.00        15.00
     Unit Hyd. peak  (cms)=        .34          .09
                                                        *TOTALS*
     PEAK FLOW       (cms)=        .01          .00          .012 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.50          1.33
     RUNOFF VOLUME    (mm)=      54.20        22.16         38.09
     TOTAL RAINFALL   (mm)=      55.20        55.20         55.20
     RUNOFF COEFFICIENT   =        .98          .40           .69

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------

--------------------
| ADD HYD   (0005) |
|   1 +  2 =  3    |          AREA    QPEAK    TPEAK     R.V.
--------------------          (ha)    (cms)    (hrs)     (mm)
          ID1= 1 (0001):      .24    .077     1.33    53.90
        + ID2= 2 (0003):      .07    .012     1.33    38.09
          ================================================
          ID = 3 (0005):      .31    .089     1.33    50.33

     NOTE:  PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

--------------------------------------------------------------------------------
--------------------
| RESERVOIR (0006) |
| IN= 2---> OUT= 1 |
| DT=  5.0 min     |     OUTFLOW    STORAGE   |  OUTFLOW    STORAGE
--------------------      (cms)     (ha.m.)   |   (cms)     (ha.m.)
                           .0000      .0000    |    .0070       .0110
                           .0050      .0055    |    .0080       .0160

                                AREA      QPEAK       TPEAK       R.V.
                                (ha)      (cms)       (hrs)       (mm)
     INFLOW : ID= 2 (0005)      .310       .089        1.33       50.33
     OUTFLOW: ID= 1 (0006)      .310       .007        2.25       49.45

                   PEAK   FLOW   REDUCTION [Qout/Qin](%)=  7.55
                   TIME SHIFT OF PEAK FLOW         (min)= 55.00
                   MAXIMUM  STORAGE   USED       (ha.m.)=   .0103

--------------------------------------------------------------------------------
  ****************************
  ** SIMULATION NUMBER:   4 **
  ****************************

--------------------
| CHICAGO STORM    |    IDF curve parameters: A=1065.950
| Ptotal= 64.43 mm |                          B=   5.000
--------------------                          C=    .762
                         used in:   INTENSITY =  A / (t + B)^C

                         Duration of storm  =  4.00 hrs
                         Storm time step    = 10.00 min
                         Time to peak ratio =   .33

                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                 .17    4.64 |  1.17   33.01 |  2.17   10.53 |  3.17    5.48
                 .33    5.29 |  1.33  135.38 |  2.33    9.03 |  3.33    5.11
                 .50    6.18 |  1.50   42.80 |  2.50    7.94 |  3.50    4.79
                 .67    7.52 |  1.67   23.26 |  2.67    7.11 |  3.67    4.51
```

.83	9.77	1.83	16.31	2.83	6.45	3.83	4.27
1.00	14.51	2.00	12.73	3.00	5.92	4.00	4.05

CALIB	
STANDHYD (0001)	Area (ha)= .24
ID= 1 DT= 5.0 min	Total Imp(%)= 99.00 Dir. Conn.(%)= 99.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	.24	.00
Dep. Storage	(mm)=	1.00	1.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	40.00	40.00
Mannings n	=	.013	.250

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

---- TRANSFORMED HYETOGRAPH ----

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
.083	4.64	1.083	33.01	2.083	10.53	3.08	5.48
.167	4.64	1.167	33.01	2.167	10.53	3.17	5.48
.250	5.29	1.250	135.38	2.250	9.03	3.25	5.11
.333	5.29	1.333	135.38	2.333	9.03	3.33	5.11
.417	6.18	1.417	42.80	2.417	7.94	3.42	4.79
.500	6.18	1.500	42.80	2.500	7.94	3.50	4.79
.583	7.52	1.583	23.26	2.583	7.11	3.58	4.51
.667	7.52	1.667	23.26	2.667	7.11	3.67	4.51
.750	9.77	1.750	16.31	2.750	6.45	3.75	4.27
.833	9.77	1.833	16.31	2.833	6.45	3.83	4.27
.917	14.51	1.917	12.73	2.917	5.92	3.92	4.05
1.000	14.51	2.000	12.73	3.000	5.92	4.00	4.05

Max.Eff.Inten.	(mm/hr)=	135.38	1035.63	
over	(min)	5.00	5.00	
Storage Coeff.	(min)=	1.31 (ii)	2.30 (ii)	
Unit Hyd. Tpeak	(min)=	5.00	5.00	
Unit Hyd. peak	(cms)=	.33	.30	
				TOTALS
PEAK FLOW	(cms)=	.09	.00	.090 (iii)
TIME TO PEAK	(hrs)=	1.33	1.33	1.33
RUNOFF VOLUME	(mm)=	63.43	31.70	63.11
TOTAL RAINFALL	(mm)=	64.43	64.43	64.43
RUNOFF COEFFICIENT	=	.98	.49	.98

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 80.0 Ia = Dep. Storage (Above)
(ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
(iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB	
STANDHYD (0003)	Area (ha)= .07
ID= 1 DT= 5.0 min	Total Imp(%)= 50.00 Dir. Conn.(%)= 50.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	.04	.04
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	21.60	40.00
Mannings n	=	.013	.250

Max.Eff.Inten.	(mm/hr)=	135.38	55.17	
over	(min)	5.00	10.00	
Storage Coeff.	(min)=	.90 (ii)	9.86 (ii)	
Unit Hyd. Tpeak	(min)=	5.00	10.00	
Unit Hyd. peak	(cms)=	.34	.11	
				TOTALS
PEAK FLOW	(cms)=	.01	.00	.016 (iii)
TIME TO PEAK	(hrs)=	1.33	1.42	1.33
RUNOFF VOLUME	(mm)=	63.43	28.73	45.99
TOTAL RAINFALL	(mm)=	64.43	64.43	64.43
RUNOFF COEFFICIENT	=	.98	.45	.71

```
***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------

--------------------
| ADD HYD   (0005) |
|   1 +  2 =  3    |          AREA    QPEAK    TPEAK     R.V.
--------------------          (ha)    (cms)    (hrs)     (mm)
         ID1= 1 (0001):       .24     .090     1.33    63.11
       + ID2= 2 (0003):       .07     .016     1.33    45.99
         ================================================
         ID = 3 (0005):       .31     .106     1.33    59.24

     NOTE:  PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

--------------------------------------------------------------------------------
--------------------
| RESERVOIR (0006) |
| IN= 2---> OUT= 1 |
| DT=  5.0 min     |     OUTFLOW    STORAGE   |  OUTFLOW    STORAGE
--------------------      (cms)     (ha.m.)   |   (cms)     (ha.m.)
                           .0000      .0000   |    .0070       .0110
                           .0050      .0055   |    .0080       .0160

                                 AREA      QPEAK       TPEAK       R.V.
                                 (ha)      (cms)       (hrs)       (mm)
     INFLOW : ID= 2 (0005)       .310       .106        1.33       59.24
     OUTFLOW: ID= 1 (0006)       .310       .007        2.33       58.37

                   PEAK   FLOW   REDUCTION [Qout/Qin](%)=  6.89
                   TIME SHIFT OF PEAK FLOW         (min)= 60.00
                   MAXIMUM  STORAGE   USED       (ha.m.)=   .0124

--------------------------------------------------------------------------------
  ****************************
  ** SIMULATION NUMBER:   5 **
  ****************************

--------------------
| CHICAGO STORM    |    IDF curve parameters: A=1172.340
| Ptotal= 71.25 mm |                          B=   5.000
--------------------                          C=    .761
                        used in:   INTENSITY =  A / (t + B)^C

                        Duration of storm  =  4.00 hrs
                        Storm time step    = 10.00 min
                        Time to peak ratio =   .33

                TIME    RAIN |  TIME    RAIN |  TIME    RAIN |  TIME    RAIN
                 hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr |   hrs   mm/hr
                 .17    5.16 |  1.17   36.50 |  2.17   11.67 |  3.17    6.08
                 .33    5.87 |  1.33  149.30 |  2.33   10.01 |  3.33    5.67
                 .50    6.86 |  1.50   47.31 |  2.50    8.81 |  3.50    5.31
                 .67    8.34 |  1.67   25.73 |  2.67    7.89 |  3.67    5.01
                 .83   10.83 |  1.83   18.06 |  2.83    7.16 |  3.83    4.74
                1.00   16.07 |  2.00   14.10 |  3.00    6.57 |  4.00    4.50


--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0001) |   Area    (ha)=    .24
|ID= 1 DT= 5.0 min |   Total Imp(%)=  99.00   Dir. Conn.(%)=  99.00
--------------------
                              IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .24          .00
     Dep. Storage     (mm)=       1.00         1.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      40.00        40.00
     Mannings n           =       .013         .250

         NOTE:  RAINFALL WAS TRANSFORMED TO   5.0 MIN. TIME STEP.
```

---- TRANSFORMED HYETOGRAPH ----

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
.083	5.16	1.083	36.50	2.083	11.67	3.08	6.08
.167	5.16	1.167	36.50	2.167	11.67	3.17	6.08
.250	5.87	1.250	149.30	2.250	10.01	3.25	5.67
.333	5.87	1.333	149.30	2.333	10.01	3.33	5.67
.417	6.86	1.417	47.31	2.417	8.81	3.42	5.31
.500	6.86	1.500	47.31	2.500	8.81	3.50	5.31
.583	8.34	1.583	25.73	2.583	7.89	3.58	5.01
.667	8.34	1.667	25.73	2.667	7.89	3.67	5.01
.750	10.83	1.750	18.06	2.750	7.16	3.75	4.74
.833	10.83	1.833	18.06	2.833	7.16	3.83	4.74
.917	16.07	1.917	14.10	2.917	6.57	3.92	4.50
1.000	16.07	2.000	14.10	3.000	6.57	4.00	4.50

Max.Eff.Inten.(mm/hr)=	149.30	1379.37	
over (min)	5.00	5.00	
Storage Coeff. (min)=	1.26 (ii)	2.21 (ii)	
Unit Hyd. Tpeak (min)=	5.00	5.00	
Unit Hyd. peak (cms)=	.33	.30	
			TOTALS
PEAK FLOW (cms)=	.10	.00	.099 (iii)
TIME TO PEAK (hrs)=	1.33	1.33	1.33
RUNOFF VOLUME (mm)=	70.25	36.90	69.91
TOTAL RAINFALL (mm)=	71.25	71.25	71.25
RUNOFF COEFFICIENT =	.99	.52	.98

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 80.0 Ia = Dep. Storage (Above)
(ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
(iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB	
STANDHYD (0003)	Area (ha)= .07
ID= 1 DT= 5.0 min	Total Imp(%)= 50.00 Dir. Conn.(%)= 50.00

	IMPERVIOUS	PERVIOUS (i)	
Surface Area (ha)=	.04	.04	
Dep. Storage (mm)=	1.00	5.00	
Average Slope (%)=	1.00	2.00	
Length (m)=	21.60	40.00	
Mannings n =	.013	.250	
Max.Eff.Inten.(mm/hr)=	149.30	65.91	
over (min)	5.00	10.00	
Storage Coeff. (min)=	.87 (ii)	9.21 (ii)	
Unit Hyd. Tpeak (min)=	5.00	10.00	
Unit Hyd. peak (cms)=	.34	.12	
			TOTALS
PEAK FLOW (cms)=	.01	.00	.018 (iii)
TIME TO PEAK (hrs)=	1.33	1.42	1.33
RUNOFF VOLUME (mm)=	70.25	33.83	51.94
TOTAL RAINFALL (mm)=	71.25	71.25	71.25
RUNOFF COEFFICIENT =	.99	.47	.73

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 80.0 Ia = Dep. Storage (Above)
(ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
(iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

ADD HYD (0005)				
1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0001):	.24	.099	1.33	69.91
+ ID2= 2 (0003):	.07	.018	1.33	51.94
ID = 3 (0005):	.31	.117	1.33	65.85

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

RESERVOIR (0006)				
IN= 2---> OUT= 1				
DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	.0000	.0000	.0070	.0110
	.0050	.0055	.0080	.0160

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0005)	.310	.117	1.33	65.85
OUTFLOW: ID= 1 (0006)	.310	.008	2.42	64.97

PEAK FLOW REDUCTION [Qout/Qin](%)= 6.49
TIME SHIFT OF PEAK FLOW (min)= 65.00
MAXIMUM STORAGE USED (ha.m.)= .0139

****
** SIMULATION NUMBER: 6 **
****

CHICAGO STORM	IDF curve parameters: A=1281.340
Ptotal= 77.88 mm	B= 5.000
	C= .761

used in: INTENSITY = A / (t + B)^C

Duration of storm = 4.00 hrs
Storm time step = 10.00 min
Time to peak ratio = .33

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
.17	5.63	1.17	39.89	2.17	12.75	3.17	6.65
.33	6.41	1.33	163.18	2.33	10.94	3.33	6.20
.50	7.49	1.50	51.70	2.50	9.62	3.50	5.81
.67	9.11	1.67	28.13	2.67	8.62	3.67	5.47
.83	11.83	1.83	19.74	2.83	7.83	3.83	5.18
1.00	17.56	2.00	15.41	3.00	7.18	4.00	4.92

CALIB		
STANDHYD (0001)	Area (ha)= .24	
ID= 1 DT= 5.0 min	Total Imp(%)= 99.00	Dir. Conn.(%)= 99.00

	IMPERVIOUS	PERVIOUS (i)
Surface Area (ha)=	.24	.00
Dep. Storage (mm)=	1.00	1.00
Average Slope (%)=	1.00	2.00
Length (m)=	40.00	40.00
Mannings n =	.013	.250

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

---- TRANSFORMED HYETOGRAPH ----

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
.083	5.63	1.083	39.89	2.083	12.75	3.08	6.65
.167	5.63	1.167	39.89	2.167	12.75	3.17	6.65
.250	6.41	1.250	163.18	2.250	10.94	3.25	6.20
.333	6.41	1.333	163.18	2.333	10.94	3.33	6.20
.417	7.49	1.417	51.70	2.417	9.62	3.42	5.81
.500	7.49	1.500	51.70	2.500	9.62	3.50	5.81
.583	9.11	1.583	28.13	2.583	8.62	3.58	5.47
.667	9.11	1.667	28.13	2.667	8.62	3.67	5.47
.750	11.83	1.750	19.74	2.750	7.83	3.75	5.18
.833	11.83	1.833	19.74	2.833	7.83	3.83	5.18
.917	17.56	1.917	15.41	2.917	7.18	3.92	4.92
1.000	17.56	2.000	15.41	3.000	7.18	4.00	4.92

Max.Eff.Inten.(mm/hr)=	163.18	1647.87
over (min)	5.00	5.00

```
     Storage Coeff.  (min)=       1.21 (ii)    2.14 (ii)
     Unit Hyd. Tpeak (min)=       5.00         5.00
     Unit Hyd. peak  (cms)=        .33          .31
                                                      *TOTALS*
     PEAK FLOW       (cms)=        .11          .00          .108 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.33          1.33
     RUNOFF VOLUME    (mm)=      76.88        42.10         76.52
     TOTAL RAINFALL   (mm)=      77.88        77.88         77.88
     RUNOFF COEFFICIENT   =        .99          .54           .98

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------
--------------------
| CALIB            |
| STANDHYD  (0003) |   Area    (ha)=    .07
|ID= 1 DT= 5.0 min |   Total Imp(%)=  50.00   Dir. Conn.(%)=  50.00
--------------------
                           IMPERVIOUS    PERVIOUS (i)
     Surface Area     (ha)=        .04          .04
     Dep. Storage     (mm)=       1.00         5.00
     Average Slope     (%)=       1.00         2.00
     Length            (m)=      21.60        40.00
     Mannings n           =       .013         .250

     Max.Eff.Inten.(mm/hr)=     163.18        76.98
               over (min)        5.00        10.00
     Storage Coeff.  (min)=        .84 (ii)    8.67 (ii)
     Unit Hyd. Tpeak (min)=       5.00        10.00
     Unit Hyd. peak  (cms)=        .34          .12
                                                      *TOTALS*
     PEAK FLOW       (cms)=        .02          .01          .020 (iii)
     TIME TO PEAK    (hrs)=       1.33         1.42          1.33
     RUNOFF VOLUME    (mm)=      76.88        38.94         57.81
     TOTAL RAINFALL   (mm)=      77.88        77.88         77.88
     RUNOFF COEFFICIENT   =        .99          .50           .74

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

       (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
            CN*  =  80.0    Ia = Dep. Storage  (Above)
      (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
           THAN THE STORAGE COEFFICIENT.
     (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

--------------------------------------------------------------------------------

--------------------
| ADD HYD   (0005) |
|   1 +  2 =  3    |         AREA    QPEAK    TPEAK     R.V.
--------------------         (ha)    (cms)    (hrs)     (mm)
          ID1= 1 (0001):      .24    .108     1.33    76.52
        + ID2= 2 (0003):      .07    .020     1.33    57.81
          ================================================
          ID = 3 (0005):      .31    .128     1.33    72.30

     NOTE:  PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

--------------------------------------------------------------------------------
--------------------
| RESERVOIR (0006) |
| IN= 2---> OUT= 1 |
| DT=  5.0 min     |     OUTFLOW    STORAGE   |  OUTFLOW    STORAGE
--------------------      (cms)     (ha.m.)   |   (cms)     (ha.m.)
                           .0000      .0000   |    .0070       .0110
                           .0050      .0055   |    .0080       .0160

                                 AREA      QPEAK       TPEAK       R.V.
                                 (ha)      (cms)       (hrs)       (mm)
     INFLOW : ID= 2 (0005)       .310       .128        1.33       72.30
     OUTFLOW: ID= 1 (0006)       .310       .008        2.50       71.43

                  PEAK   FLOW   REDUCTION [Qout/Qin](%)=  6.16
                  TIME SHIFT OF PEAK FLOW         (min)= 70.00
```

```
                  MAXIMUM  STORAGE   USED       (ha.m.)=   .0155

--------------------------------------------------------------------------------

 FINISH
================================================================================================================
```


APPENDIX C

Email Correspondence from Regional Engineering Staff regarding Watermains and hydrant tests thereof

From: Kisneris, John [mailto:John.Kisneris@halton.ca]
Sent: Thursday, July 21, 2022 9:09 AM
To: mark@odandetech.com
Subject: RE: 292 Plains Road East - Burlington - (284 & 292 PRdE), 505-07/21, 520-008/21

Hi Mark. For information, in this case only, if you have already undertaken fireflow tests off of the 300mm watermain and have the results, the Region will not be asking for fireflow tests off of the 400mm watermain.
Question. What does the Mechanical Engineer need from you in order to design the building's water systems ?
Does he/she just need the static pressure, which is something that you should easily be able to undertake/verify ?

John Kisneris
Development Project Manager
Planning Services
Legislative & Planning Services
Halton Region
905-825-6000, ext. 7742 | 1-866-442-5866



This message, including any attachments, is intended only for the person(s) named above and may contain confidential and/or privileged information. Any use, distribution, copying or disclosure by anyone other than the intended recipient is strictly prohibited. If you are not the intended recipient, please notify us immediately by telephone or e-mail and permanently delete the original transmission from us, including any attachments, without making a copy.

From: Mark Harris - Odan Detech Group <mark@odandetech.com>
Sent: Thursday, July 21, 2022 8:35 AM
To: Kisneris, John <John.Kisneris@halton.ca>
Subject: RE: 292 Plains Road East - Burlington -

CAUTION: This email originated from outside the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe. If you are unsure or need assistance please contact the IT Service Desk.

Sorry, with 4 hydrants shown.

Thank you,

Mark Harris, Dipl. Tech. | Senior Project Manager
The Odan/Detech Group Inc.

P : (905) 632-3811 ext.122 | **F :** (905) 632-3363 | **C : (**289) 439-7281
5230, SOUTH SERVICE ROAD, UNIT 107 | BURLINGTON, ONTARIO | L7L 5K2
www.odandetech.com | mark@odandetech.com

Vacation Alert – I will be on vacation July 7th returning Monday July 11th.
Vacation Alert – I will be on vacation August 5th returning Monday August 22nd.
I will respond to your email upon my return.
If this is urgent please forward your email to detech@odandetech.com

NOTICE OF CONFIDENTIALITY: This message and all files transmitted with it may contain information that is considered confidential and which may be prohibited from disclosure under applicable law or contractual agreement. It is intended solely for the use of the individual or entity to whom it is addressed. If you are not the named recipient, disclosing, copying, distributing or making use of the information contained in or attached to this message is strictly prohibited. If you have received this email transmission in error, please notify the sender immediately by replying to this email and then delete it from your system. The attached file(s) are for reference purposes only. It is the responsibility of the parties receiving this information to verify its accuracy. The Odan/Detech Group Inc. is not responsible for modified or reproduced versions of the data being transferred. These files are to be treated as unstamped and unsealed. To receive officially stamped and/or sealed files, contact The Odan/Detech Group Inc. to arrange for the receipt of hard copies.

From: Mark Harris - Odan Detech Group [mailto:mark@odandetech.com]
Sent: Thursday, July 21, 2022 8:34 AM
To: John Kisneris (John.Kisneris@halton.ca) <John.Kisneris@halton.ca>
Subject: 292 Plains Road East - Burlington -
Importance: High

John,

With regards to our site located at 292 Plains Road the Region requested that connection be made to the 400mm dia. water main and not the 300mm dia. water main.
We had originally proposed connection to the 300mm and complete flow tests of this water main which were sufficient.
As additional costs will be incurred by the Owner to test the 400mm water main would the Region be able to provide flow testing in this area related to the 400mm water main?
Based on the OPS mapping attached I have identified 4 hydrants, 2 on the 400mm main and 2 on side streets with 150mm water mains.

Please let me know if the Region can provide flow information on these hydrants for our use to avoid additional testing.

Thank you,



Mark Harris, Dipl. Tech. | Senior Project Manager
The Odan/Detech Group Inc.

P : (905) 632-3811 ext.122 | **F :** (905) 632-3363 | **C : (**289) 439-7281
5230, SOUTH SERVICE ROAD, UNIT 107 | BURLINGTON, ONTARIO | L7L 5K2
www.odandetech.com | mark@odandetech.com

Vacation Alert – I will be on vacation July 7th returning Monday July 11th.
Vacation Alert – I will be on vacation August 5th returning Monday August 22nd.
I will respond to your email upon my return.
If this is urgent please forward your email to detech@odandetech.com

NOTICE OF CONFIDENTIALITY: This message and all files transmitted with it may contain information that is considered confidential and which may be prohibited from disclosure under applicable law or contractual agreement. It is intended solely for the use of the individual or entity to whom it is addressed. If you are not the named recipient, disclosing, copying, distributing or making use of the information contained in or attached to this message is strictly prohibited. If you have received this email transmission in error, please notify the sender immediately by replying to this email and then delete it from your system. The attached file(s) are for reference purposes only. It is the responsibility of the parties receiving this information to verify its accuracy. The Odan/Detech Group Inc. is not responsible for modified or reproduced versions of the data being transferred. These files are to be treated as unstamped and unsealed. To receive officially stamped and/or sealed files, contact The Odan/Detech Group Inc. to arrange for the receipt of hard copies.

APPENDIX D

Functional Servicing Plan
Functional Grading Plan