MATCH EXISTING ELEVATIONS ALONG PROPERTY LINE. TYP.

REFER TO LANDSCAPE DRAWINGS FOR FENCING DETAILS ALONG PROPERTY LINE

MAX. 3:1 SLOPE

Seasonal Planter Urn

Outdoor Tables & Chairs

1.8m ht. Wood Screen Fence

Shrub Bed (typ.)

Soil Volume Required:
14 x 15m³ = 210m³
Soil Volume Provided:
= 500.6m³ (Assuming .75m Planting Depth)
Please note: all proposed trees are provided with a minimum planing depth of .75m

Access Easement

Transformer. Refer to Site Plan

Municipal Sidewalk

Entrance Easement

Planter Urns with Evergreens

LEGEND

- Property Line
- Extent of Underground
- Tree Protection Hoarding
- Existing Tree to Remain
- Proposed Deciduous Tree
- Asphalt Paving
- Concrete Paving
- Unit Paving A
- Unit Paving B
- 150mm Depth Compacted Topsoil, Finegrade, and Sod
- Sedum
- Planting Beds (Shrubs, Perennials, and/or Ornamental Grasses)
- 1.8m Ht. Wood Screen Fence
- Outdoor Furniture
- Bike Racks
- Seasonal Planter Urn
- Planter Urn With Evergreen

2m High Privacy/ Wind Screens. To be detailed by Structural Engineer.

Outdoor Tables & Chairs

Patio Pavers

Seasonal Planter Urn

2m High Glass Wind Screen. To be detailed by Structural Engineer.

Green Roof

Ground Floor Landscape Plan
1:150

Roof Terrace Landscape Plan
1:150

LC1 MAPLE AVE. CONDOMINIUM LANDSCAPE CONCEPT PLAN

Scale: As Shown
October 26, 2020
BTI-1408

Baker Turner inc
Landscape Architecture I Site Design

S:\BTI-CURRENT\BTI-Projects Current\1408 - Maple Ave. Condominium\Drawings\Concept\1408-LC1(R4).dwg
Oct 26, 2020 9:10:35am kfoff